

Estimate of Restoration Expenses and Construction Timeline for
David Rosonina
3806 Acushnet Avenue, New Bedford, MA
(Revised 10/29/18)

Survey Work

- Staking of erosion control line, original wetland line, and 25-foot no disturbance line
 - **\$350**

Environmental Oversight

- Review of excavation activity and seeding/planting operations (3-4 days)
 - **\$1,500**
- Fall 2019 Monitoring Report
 - **\$300**
- Fall 2020 Monitoring Report
 - **\$300**
- Fall 2021 Monitoring Report
 - **\$300**

Equipment Operator and Hauling of Material

- Use of backhoe with operator
 - **\$2,000**
- Trucking service and disposal
 - \$450 per/20yrd load, estimated 10, 20-yard loads of material
 - **\$4,050**

Materials

- Wetland Seed Mix **\$220**
- Erosion Control Seed Mix **\$110**
- Split Rail Fence \$60 per 10 linear foot section (280-ft total) **\$1700**
- Siltation Fence \$30 per 100 linear feet (612-ft total) **\$210**
- Wetland Plantings (16 trees (20-ft OC) \$6 per tree + \$30 shipping) **\$126**
 - Species Selected
 - Red Maple (*Acer rubrum*), Yellow Birch (*Betula allegheniensis*), Black Gum (*Nyssa sylvatica*), Swamp White Oak (*Quercus bicolor*)

\$350

\$1500

\$300

\$300

\$300

\$2000

\$4050

\$220

\$110

\$1700

\$210

\$126

\$11,166 (Estimated Total)

Construction Timeline

- Work is to begin by April 15, 2019 or sooner (weather permitting)
- Work proposed under the NOI application is to be completed by May 15, 2019