
NUMEN POSED SITI

100 DUCHAINE BOULE'N NEW BEDFORD, MASS,



SCALE: 1"=600

ENGINEER:

LOGAL, LLC. 89 BLACKMER STREET NEW BEDFORD, MA 02744 FIELD ENGINEERING CO., INC. 11D INDUSTRIAL DRIVE P.O. BOX 1178 MATTAPOISETT, MA 02739

APPLICANT/OWNER:


DRAWINGS

DATE ISSUED: MAY 7, 2014 LATEST ISSUE: JUNE 24, 2014 D FOR: PERMITTING ISSUEI

INDEX TO DRAWINGS

DRAWING TITLE	TITLE SHEET	NOTES & LEGEND	EXISTING CONDITIONS	OVERALL SITE LAYOUT	SITE LAYOUT	SITE GRADING & DRAINAGE	DETAIL SHEET 1	DETAIL SHEET 2	BIORETENTION AREA LANDSCAPING
SHEET		Z-7	EC-1	OSL-1	SL-1	SGD-1	D-1	D-2	LAND-1

100' NOTIFICATION LINE 300' NOTIFICATION LINE PROJECT SITE



PROJECT LOCATION:

ASSESSORS MAP 133 LOT 15 NEW BEDFORD, MASSACHUSETTS

づ	PEIN CENTRAL CO., CONSOCIONIED RAIL CORP.	
	GREATER NEW BEDFORD INDUSTRIAL FOUNDATION	
	MULTILAYER COATING TECHNOLOGIES LLC	
	JOSEPH L. ABREU	
	N E PLASTICS CORP.	
_	ARTHUR L. MILHENCH TRUSTEE	
	THE MILHENCH 2001 NOMINEE TRUST	PROPOSED
$\overline{}$	CP BOURG INC.	ATIS:
	CITY OF NEW BEDFORD PUMP STATION	
_	GNBIF/POLAROID LLC, C/O CORPORATE REAL ESTATE	DEVELOPMEN
	COMMONWEALTH ELECTRIC CO.,	
	C/O PROPERTY TAX DEPARTMENT	
	COMMONWEALTH ELECTRIC CO.,	
	C/O PROPERTY TAX DEPARTMENT	100 DUCHAINE BOULEVARD
	PATRICK THOMAS JR. & RACHAEL L. O'BRIEN	MAP 133 LOT 15
	COMMONWEALTH ELECTRIC CO.,	NEW BEDFORD, MA
	C/O PROPERTY TAX DEPARTMENT	
	VICTORIA J. & DENNIS S. CRAPO	
	ROBERT & JESSIE D. HATHAWAY,	
	C/O ROBERT J. HATHAWAY	TO DE 181
	CITY OF NEW BEDFORD	100 mm
	CITY OF NEW BEDFORD, INTERCEPTING SEWER	AND RICHARD R
	BARRY A. BRYANT TRUSTEE, BRYANT FAMILY	SOW!
	IRREVOCABLE SPECIAL NEEDS TRUST	No. 45898
	- 1	Service Servic
_	DANIEL R. JR. & KRYSTAL A. TREMBLAY	となる。
	필	7
	RAYMOND & FLORABELL SYLWA IRREVOCABLE TRUST	
	LISA & JEFFREY SWAIN	>
	BERNARD G. & DONNA M. POYANT	
	EDNA SCHARD	
	DANIEL & RACHEL DACOSTA	
	MARIA BARBOSA & STACEY BARBOSA	
	GUILHERME E. & LAUDELINA MEDINA	CO. INC.
	LORRAINE TRAVERS	ZS.
	LAWRENCE A. & JACQUELINE A. ST ONGE	
	JOAO M. & JUDITH GONSALVES	11D INDUSTRIAL DRIVE
	WTALIA M. STUPALSKI	P.O. BOX 1178
	JEFFERY A. & LORIE A. SEIFERT	MATTAPOISETT, MA 02739
1	RAYMOND & DIANE C. DUBOIS	TEL: (508) 758-2749
1	KEWN P. KEIGHLEY, C/O SOVEREIGN BANK	FAX: (508) / 56-2849
1		
1	GAIL A. BATES	THE CROCKER BUILDING
T	ELSIE A. SOARES	TAUNTON, MA 02780
1	JOSE TAVARES	TEL: (508) 824-9279
1	LUISA P. BARBOSA	FAX: (508) 824-9276
T	DENNIS P. & WANDA M. BOUCHARD	
	GEORGE G. JR. & CHERYL LORANTOS	Project No.
T		4 1

2 OF

NEW BEDFORD, MASSACHUSETTS

PROPOSED SITE DEVELOPMENT

100 DUCHAINE BOULEVARD

SOIL OBSERVATION LOG DATE: 6/2/14

OBSERVED DEPTH TO WEEPING — 64" ESTIMATED DEPTH TO SEASONAL HIGH GROUNDWATER — 48" (MOTTLE DEPTH)

FINE TO MEDIUM SAND (LOOSE) 2.5 Y 5/4 ELEV. 72.4

₀%

LOAMY SAND (FRIABLE) 2.5 Y 6/3 ELEV. 74.4

ວ້

SANDY LOAM (FRIABLE) 10 YR 5/6 ELEV. 75.4

SANDY LOAM (FRIABLE) 10 YR 3/2 ELEV. 76.4

DAT SOIL EVALUATOR: F

LOGAL, LLC

3. THE LOCATION AND ELEVATION OF ALL EXISTING UTILITIES SHALL BE CONSIDERED APPROXIMATE AND MUST BE VERIFIED BY THE CONTRACTOR PRIOR TO ANY CONSTRUCTION. UNDERGROUND UTILITIES SHOWN ARE FROM FIELD OBSERVATION AND THE BEST AVAILABLE RECORD INFORMATION AND ARE NOT WARRANTED THAT ALL UNDERGROUND PIPES OR STRUCTURES ARE SHOWN. THE CONTRACTOR SHALL CONTACT THE RESPECTIVE UTILITY COMPANIES RELATIVE TO THE LOCATION AND ELEVATION OF ALL EXISTING LINES. 1. THE MATERIALS AND CONSTRUCTION OF ALL THE PROPOSED WATER, SEWER AND STORM DRAINAGE UTILITIES SHALL CONFORM TO THE LOCAL D.P.W. STANDARDS AND SPECIFICATIONS AS WELL AS ALL APPLICABLE MASSDOT STANDARDS AND SPECIFICATIONS, LATEST EDITION. THE MATERIALS AND CONSTRUCTION OF ALL ELECTRIC, TELEPHONE & CATVUTILITIES SHALL CONFORM TO THE SPECIFICATIONS OF EACH RESPECTIVE PUBLIC UTILITY PROVIDER. 2. ALL CONSTRUCTION MATERIALS, AS WELL AS ALL MATERIAL SHOP DRAWINGS AND MANUFACTURERS DATA SHALL RECEIVE THE WRITTEN APPROVAL OF THE LOCAL D.P.W., AND THE PROJECT ENGINEER PRIOR TO FABRICATION AND INSTALLATION.

6. ALL EXCAVATED MATERIAL DESIGNATED FOR REUSE SHALL BE STOCKPILED ON SITE NO HIGHER THAN 8 FEET AND SHALL BE ENCLOSED BY TEMPORARY SILT FENCES TO PREVENT TRAVEL OF SEDIMENT TO ADJACENT PROPERTIES OR DRAINAGE WAYS. STOCKPILES SHALL NOT BE ALLOWED WITHIN THE 100' WE'LLAND BUFFER ZONE.
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DISPOSAL OF ALL WASTE MATERIAL AT AN APPROVED LOCATION BURIAL OF WASTE MATERIAL ON SITE WILL NOT PERMITTED. 5. WHENEVER EXISTING STRUCTURES ARE ENCOUNTERED, THE CONTRACTOR SHALL REPAIR ANY DAMAGED STRUCTURES OR REPLACE ANY REMOVED STRUCTURES, AND MAKE ANY IMPROVEMENTS ABOVE OR BELOW GRADE TO A CONDITION BETTER THAN OR EQUAL TO PRE-EXISTING CONDITIONS. 8. EROSION CONTROL MEASURES SHALL REMAIN IN PLACE AND MAINTAINED IN GOOD CONDITION UNTIL SURFACE RESTORATION IS COMPLETE AND ALL AREAS DISTURBED BY THE CONTRACTORS OPERATIONS ARE STABILIZED.

11. THE OWNER AND THE PROJECT ENGINEER SHALL APPROVE ALL FIELD CHANGES IN THE WORK PRIOR TO SHOP LIMPLEMENTATION. NO FIELD CHANGES SHALL BE MADE IN ANY SPECIFIED SITE WORK OR ANY MATERIALS FOR WHICH SHOP DRAWINGS HAVE BEEN SUBMITTED AND APPROVED WITHOUT PRIOR CONSULTATION OF THE OWNER AND THE PROJECT ENGINEER. ANY CHANGES SO MADE WITHOUT THE CONSENT OF THE OWNER AND THE PROJECT ENGINEER SHALL, IF DEEMED UNACCEPTABLE BY EITHER PARTY, BE PROMPILY REMOVED FROM THE WORK AT NO EXPENSE TO THE OWNER OF THE PROJECT. 9. THE CONTRACTOR SHALL PROTECT ADJACENT PROPERTIES FROM ON SITE CONSTRUCTION ACTIVITIES AND REMOVE ANY SEDIMENT OR DEBRIS DEPOSITED THEREON IMMEDIATELY. 10. DRAINAGE GENERATED AS A RESULT OF TRENCH DEWATERING SHALL BE DISCHARGED TO EXISTING DRAINAGE COURSES WITH PROPER EROSION CONTROL AND DEWATERING MEASURES MEASURES SUBJECT TO APPROVAL BY THE PROJECT ENGINEER. DIRECT DISCHARGE ONTO PAVEMENT, WETLANDS OR PRIVATE PROPERTY SHALL NOT BE ALLOWED WITHOUT CONSENT OF THE PROJECT ENGINEER AND THE OWNER.

13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SITE PREPARATION, THE COORDINATION AND INSTALLATION OF ALL UTILITY CONNECTIONS, AND RELATED WORK INCLUDING BUT NOT LIMITED TO ALL NECESSARY SHORING, BRACING AND TRENCH DEWATERING FOR THE COMPLETE INSTALLATION OF THE PROJECT FACILITIES DURING CONSTRUCTION. 12. ANY WORK OR MATERIALS NOT MEETING THE APPROVED STANDARDS AND SPECIFICATIONS OF THE LOCAL DEPT. OF PUBLIC WORKS SHALL BE IMMEDIATELY REMOVED AND REPLACED AT THE FULL RESPONSIBILITY AND COST/EXPENSE TO THE CONTRACTOR.

14. ALL OPEN EXCAVATIONS SHALL BE ADEQUATELY SAFEGUARDED IN STRICT ACCORDANCE WITH OSHA GUIDELINES AND TO THE SATISFACTION OF THE LOCAL POLICE DEPARTMENT. PROVISIONS FOR TEMPORARY BARRICADES, CAUTION SIGNS, LIGHTS AND OTHER MEANS TO PREVENT ACCIDENTS AND DAMAGE TO PROPERTY ARE THE RESPONSIBILITY OF THE CONTRACTOR SHALL PROVIDE SUITABLE AND SAFE BRIDGES AND OTHER CROSSINGS FOR ACCOMMODATING TRAVEL BY PEDESTRIANS AND WORKMEN. NO EXCAVATIONS SHALL REMAIN OPEN OVERNIGHT. 15. REFER TO CONSTRUCTION DETAIL SHEETS FOR ADDITIONAL UTILITY REQUIREMENTS AND SPECIFICATIONS.

18. ANY MINOR MODIFICATIONS (AS DETERMINED BY THE CITY ENGINEER) TO THE INFORMATION SHOWN ON THE APPROVED SITE PLANS SHALL BE SUBMITTED TO THE CITY ENGINEER AS A MINOR PLAN REVISION FOR APPROVAL PRIOR TO THE WORK BEING PERFORMED. 16. THESE PLANS HAVE BEEN PREPARED SPECIFICALLY AS SUPPLEMENTAL INFORMATION TO ACCOMPANY APPLICABLE PERMIT APPLICATIONS AND ARE NOT INTENDED FOR ACTUAL CONSTRUCTION WITHOUT THE EXPRESSED WRITTEN APPROVAL OF FIELD ENGINEERING CO., INC. 17. IN THE EVENT OF AN INCONSISTENCY BETWEEN THESE SPECIFICATIONS AND THE LOCAL D.P.W., THE LOCAL D.P.W. SPECIFICATIONS SHALL GOVERN. THE CONTRACTOR SHALL OBTAIN ALL APPLICABLE SPECIFICATIONS FROM THE LOCAL DEPARTMENT OF PUBLIC WORKS.

20. ALL EROSION CONTROL MEASURES SHALL BE IN PLACE PRIOR TO CONSTRUCTION. EROSION CONTROL SHALL CONFROM TO THE CITY OF NEW BEDFORD CONSERVATION COMMISSION REQUIREMENTS AS STATED IN THE ORDER OF CONDITIONS (REFER TO SITE GRADING AND LAYOUT PLAN FOR EROSION CONTROL LOCATIONS)

ALL HANDICAP PARKING, RAMPS, AND ACCESS SHALL CONFORM TO AAB & MAAB REQUIREMENTS.

21. ALL PAVEMENT MARKINGS AND SIGNS SHALL CONFORM TO MUTCD REQUIREMENTS.

42 × (123:4 EXISTING INTERMEDIATE CONTOUR INDEX CONTOUR SPOT ELEVATION LEGEND

UNDERGROUND WATER WATER FIRE SERVICE WATER DOMESTIC SERVICE UNDERGROUND GASLINE
UNDERGROUND ELECTRIC,
CABLE & TELEPHONE
LIGHT POLE
UTILITY POLE APPING SLEEVE & GATE AI VF SEWER MANHOLE DRAIN MANHOLE ROOF DRAIN CATCH BASIN FLARED END

974 1793 POST & RAIL FENCE CHAIN LINK FENCE UTILITY POLE GUY WRE OVERHEAD WRE HANDICAP RAMP CONCRETE CURB BIT CONC BERM TREE LINE BUILDING

BORDERING VEGETATED WETLAND & FLAG NO.

1. ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE EXECUTED IN ACCORDANCE WITH THE FOLLOWING REQUIREMENTS AND THE NPDES STORMWATER POLLUTION PREVENTION PLAN (SWPPP).

GENERAL ABBREVIATIONS

2. THOSE AREAS UNDERGOING ACTUAL CONSTRUCTION WILL BE LEFT IN AN UNTREATED OR UNVEGETATED CONDITION FOR A MINIMUM TIME, AREAS SHALL BE PERMANENTY STABILIZED WITHIN 15 DAYS OF FINAL GRADING AND TEMPORARILY STABILIZED WITHIN 30 DAYS OF INITIAL DISTURBANCE OF THE SOIL IF THE DISTURBANCE IS WITHIN 100 FEET OF A WETLAND RESOURCE AREA. THE DISTURBED AREAS SHALL BE STABILIZED WITHIN 7 DAYS OR PRIOR TO ANY FORECASTED STORM EVENT.

(SILT FENCE, HAY BARRIERS, ETC.) SHOULD BE INSTALLED PRIOR TO ANY SOIL DISTURBANCE OF THE INTING DRAINAGE AREA. MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL AREAS WITH SLOPES AFTER OCTOBER 1ST. 4. INSTALL SILT FENCE AT TOE OF SLOPE TO FILTER SILT FROM RUNOFF. SEE SILT FENCE DETAIL FOR PROPER INSTALLATION. SILT FENCE WILL REMAIN IN PLACE PER NOTE #5. 3. SEDIMENT BARRIERS UPGRADIENT CONTRIBI GREATER THAN 8.0%

1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER INSPECTION AND MAINTENANCE OF ALL STORMWATER MANAGEMENT FACILITIES UNTIL SUCH TIME AS THE STORMWATER NANAGEMENT SYSTEM IS ACCEPTED BY THE OWNER. THEREAFTER THE OWNER SHALL BE RESPONSIBLE FOR THE PROPER INSPECTION AND MAINTENANCE OF THE STORMWATER FACILITIES IN ACCORDANCE WITH THIS OPERATION AND MAINTENANCE PLAN AS WELL AS THE CONTINUING CONDITIONS OF THE CERTIFICATE OF COMPLIANCE ON THE PROPERTY.

2. ALL STRUCTURAL BEST MANAGEMENT PRACTICES (BMP'S) INCLUDING SHOULD BE INSPECTED AFTER EVERY MAJOR RAINFALL EVENT EXCEEDING 1.0—INCH FOR THE FIRST 6 MONTHS AFTER CONSTRUCTION TO ENSURE PROPER STABILIZATION AND CONSTRUCTION.

3. THEREAFTER, REGULAR BMP INSPECTIONS SHOULD BE CONDUCTED ACCORDING TO THE FOLLOWING SCHEDULE:

ASPECTIONS PER YEAR

BMP STRUCTURE
DEEP SUMP CATCH BASINS
DETENTION BASINS/WET BASINS
SUBSURFACE DETENTION SYSTEM
OIL/WATER SEPARATOR TANK
WATER QUALITY INLETS

5. ALL EROSION CONTROL STRUCTURES WILL BE INSPECTED, REPLACED AND/OR REPAIRED EVERY 7 DAYS AND IMMEDIATELY FOLLOWING ANY SIGNIFICANT RAINFALL, SNOW MELT OR WHEN NO LONGER SERVICEABLE DUE TO SEDIMENT ACCUMULATION OR DECOMPOSURE. SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH STORM EVENT AND WHEN THE DEPOSITS REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE BARRIER. SEDIMENT CONTROL DEVICES SHALL REMAIN IN PLACE AND BE MAINTAINED BY THE CONTRACTOR UNTIL AREAS UPSLOPE ARE STABILIZED BY TURF.

7. IF FINAL SEEDING OF THE DISTURBED AREAS IS NOT COMPLETED 45 DAYS PRIOR TO THE FIRST KILLING FROST, USE TEMPORARY MULCH OR DORMANT SEEDING TO PROTECT THE SITE AND DELAY SEEDING UNTIL THE NEXT RECOMMENDED SEEDING PERIOD. NO SLOPES, EITHER PERMANENT OR TEMPORARY, SHALL BE STEEPER THAN TWO TO ONE (2 TO 1) UNLESS NOTED OTHERWISE.

9. REVEGETATION MEASURES WILL COMMENCE UPON COMPLETION OF CONSTRUCTION EXCEPT AS NOTED ABOVE. ALL DISTURBED AREAS NOT OTHERWISE STABILIZED WILL BE GRADED, SMOOTHED, AND PREPARED FOR FINAL SEEDING AS FOLLOWS: 8. TEMPORARY SEEDING OF DISTURBED AREAS THAT HAVE NOT BEEN FINAL GRADED SHALL BE COMPLETED 45 DAYS PRIOR TO THE FIRST KILLING FROST TO PROTECT FROM SPRING RUNOFF PROBLEMS.

C) THE DESIGN MIX FOR SEEDING SHALL BE IN ACCORDANCE WITH THE FOLLOWING TABLE. THE SEED MIX SHALL BE INOCULATED WITHIN TWENTY-FOUR (24) HOURS, BEFORE MIXING AND PLANTING, WITH APPROPRIATE INOCULUM FOR EACH VARIETY. A) THE TOPSOIL SHALL HAVE A SANDY LOAM TEXTURE RELATIVELY FREE OF SUBSOIL MATERIAL, STONES, ROOTS, LUMPS OF SOIL, TREE LIMBS, TRASH OR CONSTRUCTION DEBRIS, AND SHALL BE PLACED TO A DEPTH OF FOUR (4) INCHES ON ALL LOAM AND SEED AREAS OR AS SPECIFIED ON THE DRAWINGS. B) APPLY FERTILIZER AT A RATE OF 800 LB PER ACRE OR 18.4 LB PER 1,000 SF. APPLY GROUND LIMESTONE EQUIVALENT TO 50% CALCIUM PLUS MAGNESIUM OXIDE) AT A RATE OF 3 TONS PER ACRE OR 138 LB PER 1,000 S.F.

ACCUMULATED SILT AND SEDIMENT SHOULD BE REMOVED FOUR TIMES A YEAR FOR SEDIMENT FOREBAYS OR MORE FREQUENTLY IF ACCUMULATED DEPTH OF SEDIMENT EXCEEDS SIX INCHES AT THE PROPOSED STONE CHECK DAMS. ACCUMULATED SILT AND SEDIMENT SHOULD BE REMOVED AT LEAST ONCE A YEAR FOR DEEP SUMP CATCH BASINS OR MORE FREQUENTLY IF ACCUMULATED DEPTH OF SEDIMENT EXCEEDS SIX INCHES.

ALL REMOVED SEDIMENTS ARE TO BE PROPERLY DISPOSED OF AT A LOCATION TO BE APPROVED BY THE BOARD OF HEALTH. TRANSPORTATION AND DISPOSAL OF SEDIMENTS SHALL COMPLY WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL REGULATIONS.

THE DETENTION BASIN, WET BASINS, SEDIMENT FOREBAYS AND ALL LANDSCAPED AREAS SHOULD BE INSPECTED FOR TRASH ON A MONTHLY BASIS. ANY ACCUMULATED TRASH, LITTER AND DISCARDED MATERIALS SHALL BE REMOVED.

THE DRIVEWAY AND PARKING AREAS SHALL BE SWEPT AT LEAST TWICE PER YEAR.

THE OWNER SHALL MAINTAIN AND SUBMIT TO THE CONSERVATION COMMISSION UPON REQUEST A BMP INSPECTION REPORT SHALL IDENTIFY THE DATE OF INSPECTION, THE NAME AND CONTACT NUMBER OF THE RESPONSIBLE PARTY, SPECIFIC STRUCTURES INSPECTED, SPECIFIC MAINTENANCE REQUIRED AND OBSERVATIONS AT A MINIMUM, INSPECTION REPORTS SHOULD ADDRESS THE FOLLOWING CONDITIONS WHERE APPLICABLE:

TYPE
RED FESCUE
KENTUCKY 31
DOMESTIC RYE
RED TOP
LADINO CLOVER
APPLICATION RATE

LOAM AND SEED AREAS

11. THE EMBANKMENTS, SIDE SLOPES, AND BOTTOM, APPLIES TO TRASH, FILL MATERAL, CONSTRUCTION DEBRIS, GRASS CLIPPINGS, WELL BE DERMITTED WITHIN THE ANY OF THE STORMWATER MANAGEMENT SYSTEM WET BASIN AREAS SHALL BE MOWED AT LEAST TWICE ANNUALLY TO FACILITATE MAINTENANCE OF THE BASINS.

12. AN OPERATION AND MAINTENANCE INSPECTION FORM SHALL BE DEVELOPED AND COPIES OF THE COMPLETED FORMS SHALL BE COMPILED BY THE OWNER. THESE FORMS SHALL BE AVAILABLE FOR REVIEW BY THE CONSERVATION COMMISSION UPON REQUEST.

13. THE OWNER SHALL CONTRACT WITH A MAINTENANCE CONSERVATION FOR HIS COMPILED OF THE STORMWATER.

14. THE STORM WATER BMP'S WILL PE PROVIDED TO THE STORMWATER.

14. THE STORM WATER BMP'S WILL PE PROVIDED TO THE STORMWATER.

14. THE STORM WATER BMP'S WILL PE THE STORMWATER.

15. THE OWNER BMP'S WILL PE THE STORMWATER.

16. THE STORM WATER BMP'S WILL PETALL BE PROVIDED TO THE STORMWATER.

16. THE STORM WATER BMP'S WILL PETALL BE PROVIDED TO THE STORMWATER.

17. THE STORM WATER BMP'S WILL PETALL BE PROVIDED TO THE STORMWATER.

18. THE STORM WATER BMP'S WILL PETALL BE PROVIDED THE STORMWATER.

19. THE STORM WATER BMP'S WILL PETALL BE PROVIDED THE STORMWATER.

19. THE STORM WATER BMP'S WILL PETALL BE PROVIDED THE STORMWATER.

19. THE STORM WATER BMP'S WILL PETALL BE PROVIDED THE STORMWATER.

19. THE STORM WATER BMP'S WILL PETALL BE PROVIDED THE STORMWATER.

19. THE STORM WATER BMP'S WILL PETALL BE PROVIDED THE STORMWATER.

19. THE STORM WATER BMP'S WILL PETALL BETTER BMP'S WILL PETALL BETTER BMP'S WILL PETALL 10. HAY OR STRAW MULCH SHALL BE LOOSELY SPREAD TO A UNIFORM DEPTH AT THE RATE OF 4.5 TONS PER ACRE EXCEPT OVER CERTAIN SELECTED SEEDED AREAS WHERE 2 TONS PER ACRE SHALL BE USED AS DIRECTED BY THE ENGINEER AND/OR THE PLANNING BOARD. A HYDRO—APPLICATION OF WOOD OR PAPER FIBER SHALL BE APPLIED FOLLOWING SEEDING. A SUITABLE BINDER SUCH AS CURASOL OR RMB PLUS WILL BE USED ON HAY MULCH FOR WIND CONTROL. 11. ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED ONCE THE SITE IS STABILIZED TO THE SATISFACTION OF THE PROJECT ENGINEER AND/OR THE CONSERVATION COMMISSION. 16. STOCKPILES OF TOP SOIL SHALL NOT BE LOCATED NEAR WATERWAYS. THEY SHALL HAVE SIDE SLOPES NO GREATER THAN 1:1. 12, ADJACENT PROPERTIES WILL BE PROTECTED WITH HAY BALES AND/OR SILT FENCING INSTALLED AS SHOWN ON THE DRAWINGS, ADDITIONAL HAY BALES OR SAND BAGS SHALL BE LOCATED AS CONDITIONS WARRANT OR AS DIRECTED BY THE PROJECT ENGINEER AND/OR THE CONSERVATION COMMISSION. 15. THE NORMAL ACCEPTABLE SEASONAL SEEDING DATES ARE APRIL 1ST THROUGH JUNE 15TH AND AUGUST 15TH THROUGH SEPTEMBER 30TH. 14, THE CONTRACTOR MUST REPAIR OR RESEED ANY AREAS THAT DO NOT DEVELOP WITHIN THE PERIOD OF ONE YEAR AND SHALL DO SO AT NO ADDITIONAL EXPENSE TO THE OWNER. 13. TEMPORARY HAY BALE EROSION CHECKS OR FILTER FABRIC GRATE INSERTS SHALL BE PROVIDED AT ALL DRAINAGE STRUCTURE INLETS DURING CONSTRUCTION. UPON COMPLETION OF CONSTRUCTION AND SATISFACTORY STABILIZATION OF DISTURBED AREAS, THE CONTRACTOR SHALL CLEAN ALL CATCH BASIN SUMPS AND DRAIN INVERTS.

MULCH ANCHORING MAY BE ACCOMPLISHED WITH PEG AND TWINE (1 SQ. YD/BLOCK); MULCH NETTING (PER MANUFACTURERS SPECIFICATIONS); WOOD CELLULOSE FIBER (750 LBS/ACRE); OR CHEMICAL TACK (PER MANUFACTURERS SPECIFICATIONS). (1) A HYDRO—APPLICATION OF WOOD OR PAPER FIBER MAY BE APPLIED FOLLOWING SEEDING. SUCH AS CURASOL OR RMB PLUS SHALL BE USED ON HAY MULCH FOR WIND CONTROL. MODERATE TO HIGH VWLOCITY AREAS STEEP SLOPES GREATER THAN 3:1 MULCH LOCATION MILD SLOPES LESS THAN 3:1 HIGH WIND VELOCITY AREAS MULCH AND A

THE OWNER WILL MONITOR THE DETENTION BASINS, WET BQSINS, AND SEDIMENT FOREBAYS PURSUANT TO THE RECOMMENDATIONS OUTLINED IN THE USACE DOCUMENT TITLED 'NEW_ENGLAND_DISTRICT_COMPENSATORY OF THE BMP'S TO THE EXISTING BORDERING VEGETATED WETLAND, THE APPLICANT HAS CHOSEN A MECHANICAL CONTROL METHOD OF REMOVAL INVASIVE SPECIES WILL BE REMOVED BY HAND (PULLING, MOWING OR EXCAVATING ON—SITE). NO CHEMICAL CONTROL WILL BE UTILIZED.

SPECIAL ATTENTION WILL BE GIVEN TO ASSURE THAT NONE OF THE FOLLOWING INVASIVE SPECIES POPULATE THE STORM WATER BMP'S: COMMON REED (PHRAGMITES AUSTRALIS), PURPLE LOOSESTRIFE (LYTHRUM SALICARIA), SMOOTH AND COMMON BUCKTHORN (FRANGULA ALNUS, RHAMNUS CARTHARTICA), RUSSIAN AND AUTUMN OLIVES (ELAEAGNUS ANGUSTIFOLIA AND E. UMBELLATA), MULTIFLORA ROSE (ROSA MULTIFLORA), REED CANARY—GRASS (PHALARIS ARUNDINACEA), AND JAPANESE KNOTWEED (FALLOPIA JAPONICA).

1. CONSTRUCTION ACTIVITY EXECUTED DURING THE WINTER CONSTRUCTION PERIOD BETWEEN NOVEMBER 1 THROUGH APRIL SHALL BE SUBJECT TO THE FOLLOWING ADDITIONAL REQUIREMENTS. EROSION CONTROL NOTES DURING

SOIL OBSERVATION LOG DATE: 6/2/14

SOIL EVALUATOR:

IF THE DATE IS AFTER NOVEMBER 1ST AND IF THE EXPOSED AREA HAS BEEN LOAMED, FINAL GRADED AND IS SMOOTH, THEN THE AREA MAY BE DORMANT SEEDED AT A RATE OF 200 TO 300% HIGHER THAN SPECIFIED FOR PERMANENT SEED AND THEN MULCHED. IF CONSTRUCTION CONTINUOUSLY GRADED BEFORE FREEZING AND THE SURFACE TEMPORARILY PROTECTED FROM EROSION BY THE APPLICATION OF MULCH. SLOPES SHALL NOT BE LEFT UNEXPOSED OVER THE WINTER OR ANY OTHER EXTENDED TIME OF WORK SUSPENSION UNLESS TREATED IN THE ABOVE MANNER. BETWEEN THE DATES OF OCTOBER 15 AND APRIL 1ST, LOAM OR SEED WILL NOT BE PERMITTED. DURING PERIODS OF ABOVE FREEZING TEMPERATURES, THE SLOPES SHALL BE FINE GRADED AND EITHER PROTECTED WITH MULCH OR TEMPORARILY SEEDED AND MULCHED UNTIL SUCH TIME AS THE FINAL TREATMENT CAN BE APPLIED. CONTINUATION OF EARTHWORK OPERATIONS ON ADDITIONAL AREAS SHALL NOT BEGIN UNTIL THE EXPOSED SOIL, SURFACE ON THE AREA BEING WORKED HAS BEEN STABILIZED SUCH THAT NO AREA IN EXCESS OF ONE ACRE IS WITHOUT EROSION CONTROL PROTECTION. CONSIDERED TO HAVE BEEN STABILIZED WHEN EXPOSED SURFACES HAVE BEEN EITHER MULCHED WITH ADEQUATELY ANCHORED BY AN APPROVED ANCHORING TECHNIQUE. UNTIL SUCH TIME AS WEATHER CONDITIONS ALLOW DITCHES TO BE FINISHED WITH THE PERMANENT SURFACE TREATMENT, EROSION SHALL BE CONTROLLED BY THE INSTALLATION OF HAY BALE/SAND BAG CHECK DAMS. MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL DRAINAGE WAYS WITH A SLOPE GREATER THAN 3%, FOR SLOPES EXPOSED TO DIRECT WINDS, AND FOR ALL OTHER SLOPES GREATER THAN 8%. 2. WINTER EXCAVATION AND EARTHWORK SHALL BE DONE SUCH THAT NO MORE THAN 1 ACRE OF THE SITE IS WITHOUT STABILIZATION AT ANY ONE TIME. ULD BE LIMITED TO THAT WHICH CAN BE MULCHED IN ONE DAY PRIOR TO ANY SNOW EVENT. 7. BETWEEN THE DATES OF NOVEMBER 1ST AND APRIL 15TH ALL MULCH SHALL BE ANCHORED BY EITHER PEG LINE, MULCH NETTING, ASPHALT EMULSION CHEMICAL, TRACK OR WOOD CELLULOSE FIBER. 3. EXPOSED AREA SHO 5. AN AREA SHALL BE STRAW OR HAY AND

B) <u>CALCIUM CHLORIDE</u> CALCIUM CHLORIDE SHOULD BE EITHER LOOSE DRY GRANULES OR FLAKES FINE ENOUGH TO FEED THROUGH A SPREADER AT A RATE THAT WILL KEEP THE SURFACE MOIST BUT NOT CAUSE POLLUTION OR PLANT DAMAGE. CONTRACTOR SHALL NOT USE CALCIUM CHLORIDE ON STEEPER SLOPES (GREATER THAN 3:1) OR IN AREAS THAT WILL DRAIN DIRECTLY TOWARDS THE WETLANDS.

2. SPECIAL CONSIDERATION FOR DUST CONTROL SHALL BE GIVEN AT ALL SITE ACCESS DRIVEWAYS TO MINIMIZE THE AMOUNT OF DUST IN THE STREETS. 1. DUST SHALL BE CONTROLLED BY THE CONTRACTOR AS NEEDED, OR AS DIRECTED BY THE TOWN OR OWNER BY USING ONE OF THE FOLLOWING TWO METHODS: A) WAIER THE CONTRACTOR SHALL SPRAY WATER OVER EXPOSED SOIL SURFACES UNTIL MOISTENED AS NEEDED TO CONTROL DUST. 8. ALL EROSION MITIGATION SHALL BE IN PLACE PRIOR TO ANY SOIL DISTURBANCE ACTIVITIES ON THE SITE.

MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL AREAS WITH SLOPES GREATER THAN 15% AFTER THE SAME APPLIES FOR ALL SLOPES GREATER THAN 8%.

ALTERNATIVE METHODS FOR DUST CONTROL SUCH AS THE USE OF MULCH OR SPRAY ON ADHESIVES SHALL BE REVIEWED WITH THE PROJECT ENGINEER PRIOR TO THEIR IMPLEMENTATION.


5/7/14 N.T.S.


	Checked By	RRR		D D	
	Designed By	RRR/DTB		PERMITTING	RICHARD HICEON NO. 45898
	Drawn By	ОТВ	Issued For	PE	THE THE PARTY OF T
•					


TEST PIT #2 TOP ELEVATION:	ELEV. 75.2	SANDY LOAM (FRIABLE) 10 YR 3/2 ELEV. 74.20		MEDIUM/COARSE SAND (LOOSE) 2.5 Y 6/3 ELEV. 72.2	OBSERVED DEPTH TO WEEPING — 72" ESTIMATED DEPTH TO SEASONAL HIGH GROUNDWATEI — 48" (MOTTLE DEPTH)
TEST PIT #2 TOP ELEVATIO	를	₹	υ ⁻	<u> </u>	OBSERVED DEPTH TO WESTIMATED DEPTH TO SI - 48" (MOTTLE DEPTH)
TEST TOP E	0"-36"	36"-48"		48"-72"	OBSERVESTIMA - 48"
T #4 :VATION:78.0	A/ FILL	SANDY LOAM (FRIABLE) 10 YR 3/2 ELEV. 76.0	2,-	FINE SAND (LOOSE) 2.5 Y 5/3 ELEV. 74.0	OBSERVED DEPTH TO WEEPING — 36" ESTIMATED DEPTH TO SEASONAL HIGH GROUNDWATER — 24" (MOTTLE DEPTH)
TEST PT #4 TOP ELEVATION:		12"-24"		24"48"	OBSERVEC ESTIMATEI - 24" (M


ELEV. 75.2	SANDY LOAM (FRIABLE) 10 YR 3/2 ELEV. 74.20		MEDIUM/COARSE SAND (LOOSE) 2.5 Y 6/3 ELEV. 72.2	OBSERVED DEPTH TO WEEPING - 72"
E	¥	ပ်		DEPT
0*36*	36"-48"		48"72"	OBSERVED


NOTES & LEGEND














BIORETENTION AREA LANDSCAPING PLAN 9 OF 9 AND-1 Project No. 1998

-PLANTING DETAIL

WET-BASIN

100 DUCHAINE BOULEVARD

NEW BEDFORD, MASSACHUSETTS

LOGAL, LLC PROPOSED SITE DEVELOPMENT

		K		
ო	CONS	ᄓᅎᆝ	6/24/14	RRR
7	CONS	REV PER CON COM CONSULTANT REVIEW	6/6/14	RRR
-	REV LO	LOADING DOCK AREA	5/20/14	RRR
N O	1	Description	Date	Appvd.
Date		5/8/14		
Scale	<i>a</i>	1"=20'		
Drawn By	n By	Designed By	Checked	d By
Ш	DTB	RRR/DTB	RRR	æ
Issue	Issued For			
	Д.	RMITTIN	O	
	The second of th	RICHARD R. CIVIL.	William Control	Δ.
_		して きるい ここく// コンド		

-TREE SHALL BE PLANTED SO THAT CROWN IS 1-2" ABOVE FINISH GRADE AFTER SETTLEMENT -2-3" MULCH WITHIN SAUCER PULL MULCH AWAY FROM TRUNK ROOTBALL SHALL BE PLACED ON COMPACTED OR UNDISTURBED SUBGRADE SAUCER UP 4" ABOVE SURROUNDING GRADE -PREPARED TOPSOIL ! -FERTILIZER -FINISH GRADE 1.) PREPARED TOPSOIL MIX SHALL CONSIST OF HIGH ORGANIC SOIL WITH NO LESS THAN 10% ORGANIC MATTER.

2.) ALL PLANTS SHALL BE FLODDED WITH WATER TWICE WITHIN THE TWENTY—FOUR HOUR PERIOD AFTER PLANTING.

TREE PLANTING DETAIL

NOT TO SCALE THREE EQUALLY SPACED WHITE OR RED CEDAR STAKES, 8'-10' LONG BY 2"X2" AT 5'-0" MIN. ABOVE FINISH GRADE

QUALITY AND SIZE OF PLANTS, SPREAD OF ROOTS, AND SIZE OF BALLS SHALL BE IN ACCORDANCE WITH ANSI 260 (REV. 1980) "AMERICAN STANDARD FOR NURSERY STOCK" AS PUBLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMEN, INC.

ALL PLANTS SHALL BE PLANTED IN TRANSPORTED TOP SOIL THAT IS THOROUGHLY WATERED AND TAMPED AS BACK FILLING PROGRESSES. PLANTING MIX TO BE AS SHOWN ON PLANTING DETAILS. RAISE AND REPLANT ANY PLANT WHICH SETTLES MORE THAN 2" AFTER PLANTING AND WATERING.

/%/

岸

INSOFAR AS IT IS PRACTICABLE, PLANT MATERIAL SHALL BE PLANTED ON THE DAY OF DELIVERY. IN THE EVENT THIS IS NOT POSSIBLE, THE CONTRACTOR SHALL PROTECT STOCK NOT PLANTED. PLANTS SHALL NOT REMAIN UNPLANTED FOR LONGER THAN A THREE DAY PERIOD AFTER DELIVERY. ANY PLANTS NOT INSTALLED DURING THIS PERIOD WILL BE REJECTED.

8. PLANTS SHALL NOT BE BOUND WITH WIRE OR ROPE AT ANY TIME SO AS TO DAMAGE THE BARK OR BREAK BRANCHES. PLANTS SHALL BE HANDLED FROM THE BOTTOM OF THE BALL ONLY.

7. FERTILIZER FOR WOODY PLANTS SHALL BE SLOW RELEASE, PELLITIZED AND SUITABLE FOR RELEASE UNDER SATURATED SOIL CONDITIONS, FERTILIZER SHALL BE OSMOCOTE 18-5-11, 12-14 MONTH RELEASE OR EQUAL.

9. PLANTING OPERATIONS SHALL BE PERFORMED DURING PERIODS WITHIN THE PLANTING SEASON WHEN WEATHER AND SOIL CONDITIONS ARE SUITABLE AND IN ACCORDANCE WITH ACCEPTED PRACTICE. PLANTS SHALL NOT BE INSTALLED IN TOPSOIL THAT IS IN A MUDDY OR FROZEN CONDITION. ALL PLANT MATERIAL SHALL BE SPRAYED WITH "WILT--PRUF" OR EQUAL AS PER MANUFACTURER'S INSTRUCTIONS.

CONSULTING ENGINEERS

11D INDUSTRIAL DRIVE P.O. BOX 1178 MATTAPOISETT, MA 02739 TEL: (508) 758-2749 FAX: (508) 758-2849

1. PLANT MATERIAL SHALL BE FURNISHED AND INSTALLED AS INDICATED; INCLUDING ALL LABOR, MATERIALS, PLANTS, EQUIPMENT, INCIDENTALS, AND CLEAN-UP.


PLANTING NOTES

2. PLANTS SHALL BE TYPICAL OF THEIR SPECIES AND VARIETY; HAVE NORMAL GROWTH HABITS; WELL DEVELOPED BRANCHES, DENSELY FOLIATED, VIGOROUS ROOT SYSTEMS AND BE FREE FROM DEFECTS AND INJURIES.

3. ALL PLANT MATERIAL SHALL BE GUARANTEED BY THE CONTRACTOR TO BE IN VIGOROUS GROWING CONDITION. PROVISIONS SHALL BE MADE FOR A GROWTH GUARANTEE OF AT LEAST ONE YEAR FROM THE DATE OF ACCEPTANCE FOR TREES AND SHRUBS. REPLACEMENTS SHALL BE MADE AT THE BEGINNING OF THE FIRST SUCCEEDING PLANTING SEASON. ALL REPLACEMENTS SHALL HAVE A GUARANTEE EQUAL TO THAT STATED ABOVE.

THE CROCKER BUILDING 4 COURT STREET SUITE 10 TAUNTON, MA 02780 TEL: (508) 824-9279 FAX: (508) 824-9276





IST					
KEY	KEY BOTANICAL NAME	COMMON NAME	SIZE	SPACING	COMMENTS
AR	ACER RUBRUM "RED SUNSET"	RED SUNSET RED MAPLE	3" CAL.	AS SHOWN	В&В
SZ	ZELKOVA SERRATA "GREEN VASE"	GREEN VASE JAPANESE ZEKOVA	3" CAL.	AS SHOWN	CONTAINER

1.) BOTTOM AREAS OF THE WET-BASINS TO BE PLANTED WITH A MIX OF 2" PLUGS OF SWITCH GRASS, BROOM SEDGE, AND FOX SEDGE TO BE SPACED APPROXIMATELY 24" 0.C STORMWATER MANAGEMENT SYSTEM PLANTING NOTES

2.) DETENTION BASIN AND WET BASIN BOTTOM AREAS AND SIDE SLOPES TO BE SEEDED WITH NEW ENGLAND CONSERVATION/WILDLIFE MIX AS SUPPLIED BY NEW ENGLAND WETLAND PLANTS, INC. (OR APPROVED EQUAL)

WF4142-

W2

긜

14. NEW PLANTING AREAS SHALL BE ADEQUATELY IRRIGATED OR WATERED TO ESTABLISH THE PROPOSED PLANTS AND SEED AREAS.

13. TREES SHALL BE SUPPORTED IMMEDIATELY AFTER PLANTING, TREES SHALL BE STAKED AS SHOWN ON THE DETAIL. THE LANDSCAPE CONTRACTOR SHALL REMOVE STAKING AND GUYING AT THE END OF THE ONE YEAR MAINTENANCE AND GUARANTEE PERIOD.

11. SET ALL PLANTS PLUMB AND STRAIGHT. LOCATE PLANT IN THE CENTER OF THE PIT.

10. NO PLANT, EXCEPT GROUND COVERS, SHALL BE PLANTED LESS THAN TWO FEET FROM EXISTING STRUCTURES AND SIDEWALKS.

12. ALL DEADWOOD, SUCKERS, AND BROKEN OR BADLY BRUISED BRANCHES SHALL BE REMOVED. CONTAINER GROWN PLANTS SHALL NOT BE THINNED.

15. PRIOR TO THE ACCEPTANCE BY THE OWNER, THE PROPOSED LANDSCAPE AS SHOWN ON THE APPROVED LANDSCAPE PLAN MUST BE INSTALLED, INSPECTED AND APPROVED BY THE OWNERS REPRESENTATIVE. ANY PLANTING INSTALLED IN CONFLICT WITH THESE REQUIREMENTS MUST RECEIVE THE WRITTEN APPROVAL OF THE PRIOR TO PLANTING. FAILURE TO COMPLY WITH THESE REQUIREMENTS WILL REQUIRE THE REMOVAL OF THE PLANTING IN QUESTION. THIS REQUIREMENT DOES NOT APPLY TO SEEDING OR SODDING OR PLANTINGS SPECIFICALLY FOR SOIL STABILIZATION.

16.

1-PLANTING DETAIL **DETENTION BASIN**

 \mathbb{N}^{2}