

# PROPOSED WETLANDS REPLICATION

THE CONSERVATION AGENT SHALL BE GIVEN 48 HOURS PRIOR NOTICE TO THE BEGINNING OF THE CONSTRUCTION OF THE REPLACEMENT AREA. THE CONSERVATION AGENT SHALL MEET WITH THE CONSTRUCTION ENGINEER/CONTRACTOR AND THE WETLAND PROFESSIONAL PRIOR TO THE ONSET OF CONSTRUCTION OF THE REPLICATION AREA TO GO OVER THE PLANS, SPECIAL CONDITIONS AND CONSTRUCTION METHODOLOGY.

### OBJECTIVES AND WORK SCHEDULE

THE OVERALL OBJECTIVE IS TO REPLACE 3,500 SF± OF A BORDERING VEGETATED WETLANDS (BVW) AREA WITH APPROXIMATELY 3,500 SF OF REPLICATION. THIS RESTORATION AREA WILL BE ESTABLISHED WITHIN SIXTY (60) DAYS OF THE ISSUANCE OF A FINAL ORDER OF CONDITIONS, WEATHER CONDITIONS PERMITTING. THIS WORK WILL BE CONSIDERED COMPLETE IF AT LEAST 75 PERCENT OF THE PLANTED VEGETATION IS SUCCESSFULLY ESTABLISHED AFTER THE END OF THE SECOND GROWING SEASON.

### FROSION CONTRO

PRIOR TO THE BEGINNING OF THE RESTORATION WORK, A SILT FENCE EROSION CONTROL BARRIER WILL BE INSTALLED ALONG AND ABOVE THE EDGE OF BVW, DOWNGRADIENT OF ALL WORK AREAS. THE EROSION CONTROL BARRIER WILL BE CONSTRUCTED IN ACCORDANCE WITH STANDARD PRACTICES.

### EXCAVATION AND GRADING OF REPLICATION AREAS

THE ORGANIC TOPSOIL WITHIN THE ALTERED WETLANDS AREA WILL BE STOCKPILED FOR REUSE IN THE REPLICATION AREA. THE RESULTING SURFACE EDGE BETWEEN THE REGRADED RESTORATION AREA AND THE EXISTING WETLANDS WILL BE THE SAME ELEVATION. THE IMPORTED ORGANIC TOPSOIL WILL BE GRADED THROUGHOUT THE RESTORATION AREA TO THE ELEVATIONS SHOWN ON THE PLAN. THE FINAL ELEVATIONS OF THE WETLAND REPLICATION AREA SHALL BE SHOWN ON AN AS-BUILT PLAN (0.50' CONTOURS) AND STAMPED BY A MASSACHUSETTS PROFESSIONAL LAND SURVEYOR. A COPY OF THE STAMPED AS-BUILT SHALL BE PROVIDED TO THE NEW BEDFORD CONSERVATION COMMISSION FOR ACCEPTANCE PRIOR TO THE WETLANDS PLANTINGS.

# PLANT LIST

THE WETLAND REPLICATION AREA SHALL BE PLANTED DURING THE SPRING (APRIL 1 THROUGH JUNE 15) OR FALL (AUGUST 15 THROUGH SEPTEMBER 30) PLANTING SEASON.

- (11) BLACK GUM (NYSSA SYLVATICA)

   4' (MIN.) PLANTING HEIGHT
- (11) RED MAPLE (ACER RUBRUM)

   4' (MIN.) PLANTING HEIGHT
- (11) WINTERBERRY (ILEX VERTICILLATA)
- (11) HIGHBUSH BLUEBERRY (VACCINIUM CARYMBUSOM)

   2 GALLON CONTAINER
- 2 GALLON CONTAINER

PLANTS SHALL BE MIXED AND EVENLY SPACED WITHIN THE REPLICATION AREA.

# PLANTING SPECIFICATIONS - HERBACEOUS SPECIES

UPON COMPLETION OF THE REGRADING AND PLANTING, A WETLAND SEED MIX WITH FINE MULCH WILL BE SPREAD (OR HYDROSEED) WITH THE FOLLOWING:

NEW ENGLAND WET MIX (WETLAND SEED MIX)
SUPPLIER: NEW ENGLAND WETLAND PLANTS, INC.
820 WEST STREET
AMHERST, MA 01002
(413)548-8000

SITEC, INC. / CEC, INC. IS PROPOSING THIS MIXTURE FOR QUICK ESTABLISHMENT THE FIRST YEAR. APPLICATION RATE SHALL BE AS SPECIFIED BY THE SUPPLIER. THE SEED MIXTURE WILL BE SPREAD EVENLY THROUGHOUT THE RESTORATION AREA, AROUND THE PLANTED WETLAND SHRUBS. IT WILL BE WORKED INTO THE TOP 1/4 INCH OF THE SOIL AND ROLLED. MULCH WILL THEN BE APPLIED TO COVER ALL SEEDED SOIL SURFACES.

# MONITORING & REPORTING

WE PROPOSE TO NOTIFY THE CONSERVATION COMMISSION IN WRITING TWO WEEKS AFTER COMPLETION OF REGRADING AND PLANTING OF THE OF THE WETLAND REPLICATION AREA. AN AS-BUILT PLAN PREPARED AND STAMPED BY A MASSACHUSETTS PROFESSIONAL LAND SURVEYOR (0.5' CONTOURS) SHALL BE PROVIDED TO THE MATTAPOISETT CONSERVATION COMMISSION FOR ACCEPTANCE PRIOR TO THE WETLAND PLANTINGS.

IN COMPLIANCE WITH 310 CMR 10.55(4), THE WETLAND PROFESSIONAL SHALL SUBMIT MONITORING REPORTS DOCUMENTING THE SUCCESS OF THE WETLAND REPLICATION AREAS. THESE REPORTS SHALL DOCUMENT THE ESTABLISHMENT OF AT LEAST 75% COVERAGE OF INDIGENOUS WETLAND PLANTS WITHIN THE REPLICATION AREA. THESE REPORTS SHALL BE PROVIDED AT THE END OF CONSTRUCTION AND ONCE A YEAR FOR TWO YEARS. THE CONSERVATION COMMISSION RESERVES THE RIGHT TO REQUEST ADDITIONAL SEEDING OR PLANTING TO GUARANTEE THE SUCCESS OF THE REPLICATION AREAS. PROPOSED SHRUB AND TREE PLANTINGS THAT DIE DURING THIS TIME PERIOD SHALL BE REPLACED. THE REPORTS SHALL ALSO DOCUMENT THE PRESENCE OF INVASIVE SPECIES WITHIN THE REPLICATION AREA AND RECOMMEND CONTROLS METHODS FOR IMPLEMENTATION.


### QUALITY CONTRO

-1-1/4" SCH 40 P.V.C. PIPE

ALL WORK SHALL BE CARRIED OUT BY A QUALIFIED NURSERY, UNDER THE DIRECT SUPERVISION OF A SITEC, INC. WETLANDS SCIENTIST. THE RESUME OF THE WETLAND SPECIALIST WHO WILL OVERSEE CONSTRUCTION OF THE REPLICATION AREA SHALL BE FORWARDED TO THE CONSERVATION COMMISSION FOR ACCEPTANCE TWO WEEKS PRIOR TO INITIATION OF THE REPLICATION ACTIVITIES.

# **GENERAL NOTES:**

- CONTRACTOR SHALL NOTIFY DIG SAFE AT LEAST 72 HOURS PRIOR TO THE START OF CONSTRUCTION.
- CONTRACTOR SHALL VERIFY THE LOCATION AND ELEVATION OF ALL UTILITIES PRIOR TO THE START OF CONSTRUCTION. THESE PLANS ARE BASED ON FIELD AND RECORD INFORMATION AND, THEREFORE, MAY NOT COMPLETELY DEPICT ALL EXISTING UTILITIES.
- CONTRACTOR SHALL NOTIFY THE OWNER AND ENGINEER IMMEDIATELY IF FIELD CONDITIONS ARE FOUND TO DIFFER WITH THESE DRAWINGS.
- 4. THE CONTRACTOR SHALL PROVIDE ADEQUATE PROTECTION OF THE ABUTTING AREA AND UTILITIES IN THE CONSTRUCTION OF THIS SITE. REPAIR OF DAMAGED PROPERTY SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AT NO COST TO THE OWNER.
- 5. THE SITE CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLETING ALL CONSTRUCTION.
- ALL WORK SHALL BE IN ACCORDANCE WITH THE DEPARTMENT OF PUBLIC INFRASTRUCTURE CONSTRUCTION SPECIFICATIONS, LATEST REVISION.
- 7. ALL CONSTRUCTION SHALL COMPLY WITH THE CITY OF NEW BEDFORD DPI STANDARDS.
- 8. SEWER PERMIT MUST BE OBTAINED FROM THE DEPARTMENT OF PUBLIC INFRASTRUCTURE (DPI) ENGINEERING DIVISION BY OWNER.
- 9. ALL UTILITY WORK TO BE CONDUCTED PER DPI SPECIFICATION.
- THE DEVELOPER AND SITE CONTRACTOR MUST SCHEDULE A PRE-CONSTRUCTION MEETING WITH THE DEPARTMENT OF PUBLIC INFRASTRUCTURE PRIOR TO START OF CONSTRUCTION.
- UPON COMPLETION OF THE SEWER MAIN INSTALL, THE ENGINEER MUST SUBMIT AS—BUILT DRAWINGS TO DPI PRIOR TO THE ISSUANCE OF THE SEWER SERVICE PERMIT FOR 732 MT. PLEASANT STREET.



## NOTES:

LOW PRESSURE-


SEWER LINE

- SEE UTILITY TRENCH DETAIL FOR BACKFILLING OVER NEWLY INSTALLED MAINS OR SERVICES WITHIN EXISTING ROADWAYS.
- 2. DUCTILE IRON PIPE SHALL BE USED FOR SHALLOW INSTALLATIONS, (LESS THAN 3'). NO SEWER MAIN OR SEWER SERVICE SHALL BE INSTALLED WITH LESS THAN THREE (3) FEET OF COVER, UNLESS GRANTED WRITTEN APPROVAL BY THE DIRECTOR OR HIS DESIGNEE.
- METALLIC 3" WIDE DETECTABLE IDENTIFICATION TAPE SHALL BE INSTALLED OVER SEWER LINES 12" BELOW FINISH GRADE.

# TYPICAL SEWER TRENCH DETAIL

NOT TO SCALE

-ELBOW



PAVING SECTION

NOT TO SCALE

SS STRAP 24" O.C.

—ELBOW —GRAVITY SEWER

TYPICAL DROP CONNECTION
LPSS IN MANHOLE

NOT TO SCALE

# LID ASSEMBLY WITH PENTAGON HEAD PLUG MATERIAL: CAST IRON WITH ASPHALT—BASE PAINT LABELED "SEWER" LATERAL ASSEMBLY 1—1/4" SCH 40 P.V.C. PIPE — EXTENSION TYPE CURB BOX WITH BASE MATERIAL: CAST IRON HEAVILY COATED WITH

\* 3.0 FT. 3.5 FT. 4.5 FT. 5.0 FT. 5.5 FT. 0PTIONAL 6.0 FT. 7.5 FT. 7.5 FT. 8.0 FT. 8.0

PACK JOINT COUPLING
MATERIAL: WATER WORKS BRASS

PACK JOINT COUPLING
MATERIAL: WATER WORKS BRASS

1-1/4" MNPT

1-1/4" SCH 40
P.V.C. PIPE

PVC ADAPTER/COUPLING

PVC ADAPTER/COUPLING

VALVE CURB STOP WITH PACK JOINT COUPLING
MATERIAL: WATER WORKS BRASS


\*FOR ORDERING INFORMATION SEE PA1372P01 LATERAL ORDER CODE

LATERAL ASSEMBLY

NOT TO SCALE


- CHECK VALVE

MATERIAL: GLASS FILLED PVC



SEWER CLEANOUT

NOT TO SCALE



GRINDER PUMP DETAIL

NOT TO SCALE

BEDDING MATERIAL (6" MIN. DEPTH)
ROUNDED 3/4" AGGREGATE GRAVEL IN DRY TRENCH.

CONCRETE IS BEING POURED AROUND EXTERIOR.

NB 311-027 DET.DWG File No. 311-027

ELO,

AST

BY