

RECORD OWNER:

70 SYCAMORE STREET,

NEW BEDFORD, MA 02740 DEED BOOK 13891 PAGE 14

PLAN BOOK 173 PAGE 49

ASSESSORS MAP 136A LOT 884

FARIA & OLIVEIRA PROPERTIES, LLC

VERTICAL ELEVATIONS REFER TO AN ASSUMED DATUM.

CLEARED VEGETATION TO BE CHIPPED AND SPREAD WITHIN REMAINING WOODED AREAS

AND EROSION CONTROL TO BE SET IMMEDIATELY AFTER CLEARING. SOIL TEST HOLE PERFORMED BY STEVIE CARVALHO, APRIL 26, 2022.


RECORDED IN BOOK 13871 PAGE 21.


RIM=92.72


INV=85.5

EROSION CONTROL

TEST HOLE









SCALE: 1"=10'

JOB NO. 21-022

LATEST REVISION: MAY 4, 2022

SITE PLAN


SHEET 1 OF 2

GENERAL CONSTRUCTION NOTES:

- 1. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AND STRUCTURES AS SHOWN ON THESE PLANS IS BASED ON RECORDS PROVIDED BY THE CITY OF NEW BEDFORD DPI AND WHERE POSSIBLE. MEASUREMENTS TAKEN IN THE FIELD. THIS INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE LOCATION OF ALL UNDERGROUND UTILITIES AND STRUCTURES SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR MUST CONTACT THE APPROPRIATE UTILITY COMPANY, ANY GOVERNING PERMITTING AUTHORITY, AND "DIG SAFE" AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION WORK TO REQUEST EXACT FIELD LOCATION OF UTILITIES INTERFERING WITH THE PROPOSED CONSTRUCTION AND APPROPRIATE REMEDIAL ACTION TAKEN BEFORE PROCEEDING WITH THE WORK. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLAN.
- 2. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH ALL APPLICABLE STATE AND LOCAL STANDARDS AND REGULATIONS.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ESTABLISHING AND MAINTAINING ALL CONTROL POINTS AND BENCH MARKS NECESSARY FOR THE WORK.
- 4. ALL BENCHMARKS SHOWN ON THIS PLAN ARE TO BE CHECKED FOR CONSISTENCY BY THE CONTRACTOR. ANY DISCREPANCIES MUST BE RESOLVED BY THIS OFFICE PRIOR TO CONSTRUCTION.
- 5. WHERE PROPOSED PAVEMENT AND WALKS ARE TO MEET EXISTING, THE CONTRACTOR SHALL SAW-CUT A NEAT LINE AND MATCH GRADE. SEAL ALL JOINTS WITH HOT BITUMINOUS ASPHALT JOINT SEALER.
- 6. ALL EXISTING TREES, SHRUBS AND GROUND COVER WHERE NATURAL GRADE IS TO BE RETAINED SHALL BE KEPT IN THEIR EXISTING STATE UNLESS REMOVAL IS REQUIRED FOR CONSTRUCTION PURPOSES.
- 7. ALL AREAS DISTURBED BY CONSTRUCTION AND NOT TO BE PAVED OR OTHERWISE TREATED AS NOTED ON PLAN SHALL BE TREATED WITH 4" OF LOAM, SEEDED AND HAY MULCHED FOR EROSION CONTROL. DUE TO THE UNKNOWN LOCATION OF THE STRUCTURES DOWNSPOUTS IT SHALL BE THE
- CONTRACTORS RESPONSIBILITY TO ENSURE THAT ALL DOWNSPOUTS ARE CONNECTED TO A ROOF RECHARGE SYSTEM AND THAT THE FLOWS TO EACH SYSTEM ARE PROPORTIONATELY DISTRIBUTED. 9. CONTRACTOR SHALL THOROUGHLY FAMILIARIZE THEMSELVES WITH ALL CONSTRUCTION
- DOCUMENTS, SPECIFICATIONS AND SITE CONDITIONS PRIOR TO BIDDING AND PRIOR TO 10. ANY DISCREPANCIES BETWEEN DRAWINGS, SPECIFICATIONS AND SITE CONDITIONS SHALL
- BE REPORTED IMMEDIATELY TO THE OWNER'S REPRESENTATIVE FOR CLARIFICATION AND RESOLUTION PRIOR TO BIDDING OR CONSTRUCTION. 11. THESE PLANS ARE PERMITTING PLANS AND SHALL NOT TO BE USED FOR
- CONSTRUCTION. A FINAL SET OF STAMPED PLANS FOR CONSTRUCTION WILL BE ISSUED AFTER RECEIVING FINAL APPROVAL FROM THE LOCAL AND/OR STATE

SOIL EROSION AND SEDIMENT CONTROL NOTES:

- THE CONSERVATION COMMISSION SHALL BE NOTIFIED, AT LEAST 72 HOURS PRIOR TO ANY LAND DISTURBANCE.
- 2. A COPY OF THE SOIL EROSION AND SEDIMENT CONTROL PLAN MUST BE MAINTAINED ON THE PROJECT SITE DURING CONSTRUCTION.
- 3. SOIL EROSION AND SEDIMENT CONTROL PRACTICES IN THE PLAN SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS. 4. ALL APPLICABLE SOIL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE IN
- PLACE PRIOR TO ANY DEMOLITION GRADING OPERATIONS AND/OR INSTALLATION OF PROPOSED STRUCTURES OR UTILITIES. 5. ALL APPLICABLE SOIL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE LEFT IN
- PLACE UNTIL CONSTRUCTION IS COMPLETED AND/OR THE AREA IS STABILIZED. 6. ALL SOIL EROSION AND SEDIMENT CONTROL STRUCTURES SHALL BE INSPECTED AND MAINTAINED ON A REGULAR BASIS AND AFTER EVERY STORM EVENT.
- THE MAINTENANCE OF SOIL EROSION AND SEDIMENT CONTROL MEASURES AND FACILITIES DURING AND IMMEDIATELY AFTER CONSTRUCTION RESTS WITH THE GENERAL CONTRACTOR. UPON ACCEPTANCE OF THE PROJECT, THE OWNER SHALL BECOME
- RESPONSIBLE FOR MAINTENANCE OF ANY REMAINING MEASURES AND FACILITIES. 8. OFF SITE SEDIMENT DISTURBANCE MAY REQUIRE ADDITIONAL CONTROL MEASURES TO
- BE DETERMINED BY THE ENGINEER. 9. THE CONSERVATION COMMISSION AND/OR ENGINEER MAY REQUIRE ADDITIONAL SOIL EROSION MEASURES TO BE INSTALLED, AS DIRECTED BY THE DISTRICT INSPECTOR.
- 10. THE CONTRACTOR SHALL UTILIZE ALL METHODS NECESSARY TO PREVENT BLOWING AND MOVEMENT OF DUST FROM THE EXPOSED SOIL SURFACES. 11. PAVED ROADWAYS MUST BE KEPT CLEAN AT ALL TIMES.
- 12. ALL CRITICAL AREAS SUBJECT TO EROSION SHALL RECEIVE A TEMPORARY SEEDING AND BE MULCHED IN ACCORDANCE WITH THE SPECIFICATIONS IMMEDIATELY FOLLOWING ROUGH GRADING. 13. MAXIMUM SIDE SLOPES OF ALL EXPOSED SURFACES SHALL NOT BE CONSTRUCTED
- STEEPER THAN 3:1 UNLESS OTHERWISE APPROVED BY THE DISTRICT.
- 14. ALL DEWATERING OPERATIONS MUST DISCHARGE DIRECTLY INTO A SEDIMENT FILTRATION DEVICE. THE SEDIMENT FILTER MUST BE CAPABLE OF FILTERING THE SEDIMENT AND BE PLACED SO AS NOT TO CAUSE EROSION OF THE DOWNSTREAM AREA.
- 15. ANY EXCAVATED MATERIAL NOT TO BE REUSED ON SITE SHALL BE REMOVED OFF SITE.



ROOF RECHARGE SYSTEM

NOT TO SCALE


<u>SUBSURFACE ROOF RECHARGE UNIT SIZING CALCULATIONS:</u>

2,362 SF, 100.00% IMPERVIOUS, INFLOW DEPTH = 6.76" FOR 100-YEAR STORM EVENT INFLOW AREA 0.37 CFS @ 12.08 HRS. VOLUME= 1.351 CF 0.01 CFS @ 9.11 HRS, 0.01 CFS @ 9.11 HRS, VOLUME= 959 CF, ATTEN= 97%, LAG= 0.0 MIN

ROUTING BY DYN-STOR-IND METHOD, TIME SPAN= 0.00-30.00 HRS, DT= 0.01 HRS / 3 PEAK ELEV= 89.21' @ 15.90 HRS SURF.AREA= 457 SF REQUIRED STORAGE= 748 CF


AVAIL.STORAGE 14.75'W X 31.00'L X 3.21'H PRISMATOID X 1 1,467 CF OVERALL - 528 CF EMBEDDED = 939 CF X 40.0% VOIDS 86.80 376 CF 47.0"W X 26.5"H X 8.00'L PARABOLIC ARCH WITH 1' OVERLAP 528 CF

TOTAL AVAILABLE STORAGE = 904 CF >>> 748 CF




WATER SERVICE DETAIL

NOT TO SCALE



STAKED STRAW WATTLE

NOT TO SCALE



12" NYLOPLAST

INLET GRATE

YARD DRAIN INLET

NOT TO SCALE

SEWER SERVICE CLEANOUT

NOT TO SCALE

T.H. #1

ELEV.=90.2±

4/26/22

0"-62"


MATERIAL


62"-120" C HORIZON

LOAMY SAND 2.5Y 5/1 REDOX

@ 48**"**

ELEV.=86.2±





TREE PLANTING


NOT TO SCALE

RECHARGE SYSTEM

COMPACTED GRAVEL

ALL AROUND

PROPOSED ADS N-12 REDUCING TEE



3" BARK MULCH IN SAUCER, NOT TO BE FILLED AGAINST ROOT FLARE OR TRUNK. PLANT SAUCER, 4" CONTINUOUS, NO SAUCERWHERE SHRUBS OCCUR IN BEDS.

- FINISH GRADE

CUT AND REMOVE ALL BURLAP FROM ROOT BALL. PLANTING SOIL MIX: BACKFILL IN LOOSE LIFTS OF 6"-8" DEPTH. SETTLE WITH THOROUGH WATERING. PLACE ROOT BALL ON UNDISTURBED SOIL. IF SOIL HAS BEEN DISTURBED, COMPACT TO MINIMIZE SETTLING.

- 1. SHRUB SHALL BEAR SAME RELATIONSHIP TO FINISHED GRADE AS IT BORE TO NURSERY OR FIELD GRADE
- 2. WHERE SHRUBS OCCUR IN GROUPINGS IN PLANT BEDS, PROVIDE 2' DEEP CONTINUOUS LOAM BED.

SHRUB PLANTING

NOT TO SCALE

REVISIONS 3/7/22 | CON. COM. COMMENTS DPI COMMENTS CHRISTIAN ALBERT FARLAND



www.FarlandCorp.cor

- 21 VENTURA DRIVE DARTMOUTH, MA 02747 P.508.717.3479
- ENGINEERING
- SITEWORK LAND SURVEYING DEVELOPMENT

DRAWN BY: CKG DESIGNED BY: CKG

CHECKED BY: CAF

884 ETT 년 당 TREE 136A IASSA COUOT S S MAP ORD, M PE(OR:

S Ш S

JANUARY 26, 2022 SCALE: 1"=10' JOB NO. 21-022

LATEST REVISION:

MAY 4, 2022

CONSTRUCTION NOTES & DETAILS SHEET 2 OF 2