NARRATIVE IN SUPPORT OF PROPOSED INTERMODAL TERMINAL AND RAILROAD SPUR AT FRADE'S DISPOSAL FACILITY 781 CHURCH STREET NEW BEDFORD, MA

PREPARED FOR: FRADE'S DISPOSAL, INC. 781 CHURCH STREET NEW BEDFORD, MA

PREPARED BY:

PRIME ENGINEERING, INC. P.O. BOX 1088 LAKEVILLE, MA

TABLE OF CONTENTS

1.0 INTRODUCT	ION	3
2.0 EXISTING C	ONDITIONS	3
3.0 BASIS FOR F	RAILROAD SPUR	4
4.0 WETLAND R	REGULATION PERFROMANCE STANDARDS	4
5.0 PROPOSED I	IMPROVEMENTS	4
6.0 WETLAND R	REPLICATION	5
7.0 STORMWAT	TER	5
APPENDIX A	WETLAND FIELD DATA SHEETS	
APPENDIX B	EROSION AND SEDIMENT CONTROL	
APPENDIX C	CHECKLIST FOR STORMWATER REPORT	
APPENDIX D	PERMANENT OPERATION AND MAINTENANCE PL	AN
APPENDIX E	ILLICIT DISCHARGE STATEMENT	

1.0 INTRODUCTION

It is proposed to construct an intermodal terminal with a railroad spur that will produce a loading siding at the existing Frade's Disposal facility at 781 Church Street, New Bedford, MA. The spur will require crossing Bordering Vegetated Wetlands (BVW), thereby, requiring a Notice of Intent with the New Bedford Conservation Commission. This narrative has been prepared in support of that petition.

2.0 EXISTING CONDITIONS

The Site is a 47-acre parcel comprised from Assessors Map 125-1, Lot 10 and Assessors Map 129, Lots 38, 41, 42, 52, 53 and 55. It is bordered on the west by Route 140. It is bordered on the east by the Penn Central Railroad operating as the Massachusetts Coastal Railway system. It is bordered on the south by undeveloped woodland. The upland areas range from elevation 87 to elevation 116 feet above sea level. The wetland along the main rail line is at elevation 86 to 88.

The upland soils are classified as Paxton extremely stony fine sandy loam and Woodbridge extremely stony fine sandy loam which are Hydrologic Group C. The wetlands are classified as Whitman extremely stony fine sandy loam which is Hydrologic Group D. Typically, the upper layers of this soil consist of 1-inch of matted organic material over 5 inches of black muck. The next layer consists of gray fine sandy loam 15 inches thick. It is underlain by light olive gray, firm mottled fine sandy loam and silt loam to a depth of 60 inches or more.

Included with this in mapping are areas of soils that are fine sandy loam, very fine sandy loam, loamy sand, or loamy coarse sand throughout. Also included are areas of Ridgebury and Scarboro soils that occupy similar positions on the landscape and areas where stones and boulders cover more than 15 percent of the surface. Included areas make up about 20 percent of the unit.

The permeability of this Whitman soil is moderate or moderately rapid in the surface layer and subsoil, and slow or very slow in the substratum. Available water capacity is moderate.

The Site has been operated as a solid waste transfer station and processing area for decades. There is a significant amount of bordering vegetated wetlands between the Mass Coastal Rail and the Frades Disposal processing operation.

In early March and April, David Gordon and Hugh Webb, wetland scientists, flagged the edges of the bordering vegetated wetlands with sequentially numbered plastic ribbons. Subsequently a Prime Engineering survey crew located the flags. The wetland field data sheets are presented in Appendix A.

Twelve of the forty-seven acres of the Site are cleared. The remaining acreage is mature woodlands.

The southern third of the site slopes westerly and then southerly, so runoff from the existing buildings and the land to the south flows southwesterly. The area north of the existing buildings flows northerly to an existing intermittent brook that flows to the northwest end of the site.

3.0 BASIS FOR THE RAIL SPUR

The Massachusetts Department of Environmental Protection years ago determined that solid waste landfills were a significant cause of groundwater pollution and initiated a campaign to close the vast majority of in-state landfills. The landfill closure campaign was combined with a major thrust to increase recycling. The result of both campaigns was a massive amount of trash trucks on the state's highways hauling the trash out-of-state and the recyclables to recycling facilities. The truck hauling is inefficient and not environmentally sound. Rail transport, on the other hand, is more efficient and more environmentally friendly.

The proposed rail siding will provide an opportunity to efficiently load rail cars with trash and with recyclable material, and subsequently haul the material by rail to recycling facilities and to out-of-state disposal facilities. It will also allow other local products such as milled lumber to be loaded and shipped.

4.0 WETLAND REGULATION PERFORMANCE STANDARDS

The Massachusetts Wetland Regulations require that wetland impacts be avoided, if at all possible. If wetland impacts are unavoidable, the standards require that the impacts be minimized. In this case, the wetland impacts cannot be avoided because the BVW occurs along almost the entire rail frontage. In order to assure safe operation of the rail system, the Massachusetts Coastal Rail system has stringent design standards with regards to angles of departure from the main line, maximum allowed degrees of curvature, avoidance of reverse curves, minimum and maximum grades, etc. Adherence to these standards resulted in crossing the wetlands at the narrowest allowable point with the least amount of wetland impact. The proposed wetland crossing exceeds 5,000 square feet of impact to the Bordering Vegetated Wetland; however, this may be permitted under the provisions of 310 CMR 10.53 (3)(e) as a limited project with a roadbed of minimum legal and practical width where reasonable means of access to the upland is not otherwise available. The access to the main rail line is a key component of the intermodal terminal where truck cargo is being converted to rail cargo.

5.0 PROPOSED IMPROVEMENTS

In localized areas where the rail will be significantly higher than the wetlands, it is proposed to drive steel H-piles into the geotechnically sound glacial fill 9 feet on either side of the centerline of the proposed spur, and then, insert steel sheathing between the webs of the H-piles. The top 20 inches of the soil will be excavated and placed in the previously prepared wetland replication area. The 40 inches of soil below the 20 inches initially excavated, will either be blended with more granular material and compacted in one-foot lifts under the rail spur or, if deemed too silty, moved to an upland area away from the wetlands. The railroad ballast shown on the site plans, will then be installed prior to the placement of the ties and rails.

In most locations, the rail improvement will be 13 feet wide comprised of a series of 9-foot-long rail ties bordered on both sides by a 2-foot width of sloping ballast as shown on the site plans.

The proposed rail sidings will result in approximately 2 ¼ acres of upland trees to be cleared at the south end, and 2 ½ acres of primarily upland trees to be cleared at the north end, with minimal to no clearing in the central section of the proposed rail siding. There will be a minor amount of fill in the northern end of the sidings, minimum to slight earth cutting in the central section of the sidings, and 5 feet to 10 feet of earth cut at the southern end of the proposed siding.

The rails and ties will be supported by a 12-inch depth of gravel overlain by a minimum 8-inch depth of crushed stone ballast, so rainfall will typically infiltrate through the ballast to the native soil below resulting in no increase in runoff compared to existing conditions.

At station X of the proposed spur, there will be a crossing of an intermittent stream.

6.0 WETLAND REPLICATION

As shown on the plans, prior to any wetland impacts, a wetland replication area twice the size of the proposed wetland impact will be excavated and graded. When the upper wetland soils at the rail spur site are excavated, they will be brought directly to the replication area blended with an equal volume of imported organic soil and spread without compaction at a level grade. The excavator's bucket teeth will be dragged across the level surface in order to form a microtopography. The shrub and tree plantings will be installed by hand labor. Even though it is expected that the native soil will have embedded in it a large stock of wetland plant seeds, the wetland replication area will be seeded with a wetland seed mix.

7.0 STORMWATER

7.1 STORMWATER COLLECTION SYSTEM

To route water to the replication area, the stormwater collection system will be in the form of overland flow. Water from rail sidings will be routed to the stormwater Best Management Practices (BMPs) through overland flow and swales.

7.2 STORMWATER MANAGEMENT FACILITIES

Current MassDEP standards require that the peak runoff rate after development is not more than peak runoff rate prior to development for 2 and 10-year 24-hour storm events. Additionally, it is required that the stormwater management system be evaluated for 100-year storm projections.

Hydrologic modeling has been conducted for the design of the ponds to determine appropriate sizing and outflow characteristics. HydroCAD Version 7.10 was utilized to perform this hydrologic and hydraulic modeling. The 2, 10, 25, and 100-year design storms were evaluated. The hydrologic and hydraulic modeling established that the stormwater management system will effectively attenuate the full range of design storms. That is, the peak rate of flow after development will be less than or equal to existing conditions. The drainage summary provided

with this document tabulates the projected decrease of peak runoff rates when the site is subjected to the design storm events. The complete hydrologic and hydraulic computational output is presented in Appendix A.

The rain gardens will be constructed with check dams.

7.3 WATER QUALITY CONSIDERATIONS AND STORMWATER STANDARDS

MassDEP issued Stormwater Management standards. The goal is to improve water quality and address water quantity problems, which are sometimes caused by development projects, by the implementation of performance standards for stormwater management. The project was designed to meet the primary standards established in the manual. The following sections describe how each of these standards will be achieved on this project by incorporating Best Management Practices into the design. Standards 1 through 10 are described below.

7.3.1 UNTREATED STORMWATER (STANDARD 1)

Standard 1 of the MassDEP Stormwater Policy requires that no new stormwater conveyance, such as storm drain outfalls, discharge untreated stormwater directly to wetlands or waterways of the Commonwealth. Flows from woods, fields, and other undeveloped areas are considered uncontaminated, however, runoff from paved road and parking lot surfaces must receive treatment prior to discharge.

The project does not propose any new untreated stormwater discharges. No stormwater outlets which discharge directly to wetland resource areas are proposed without being treated first. The vegetated swale with check dams and rain gardens has been strategically designed to allow for treated stormwater from the proposed development.

7.3.2 POST DEVELOPMENT DISHCHARGE RATES (STANDARD 2)

Standard 2 of the MassDEP Stormwater Policy prescribes that stormwater management systems be implemented in order to ensure that post-development peak rates of discharge do not exceed existing rates of runoff for standard 2 year and 10-year 24-hour design storms. In addition, the preand post-peak rates for the 100-year storm must be evaluated to assure that there will not be increased off-site flooding.

The soils in the wetlands are hydrologic Group D with water at the surface for the majority of the year, so there is no significant infiltration except for in the hot summer months. Therefore, most of the rainfall ends up as runoff rather than infiltration. The proposed rails and ties will be impervious but they will be surrounded by crushed stone. There will be a 9-inch wide by 9-footlong tie separated by a 12-inch gap to the next tie with 2 feet of ballast beyond each end of the tie. As a result, each tie will have a 13-foot wide by 1.75-foot-long bed of crushed stone that is at least 8 inches deep. The void volume will be:

(13' wide) (1.75' long) (.67' deep) (.40 void) = 6.1 CF storage

The 2-year design storm (3.2-inch rainfall) can be stored in its entirety in this void space. As

opposed to the 100 percent runoff that presently occurs, the vast majority of storms will be stored providing an opportunity for the rainfall to infiltrate, thereby recharging the groundwater.

7.3.3 RECHARGE TO GROUNDWATER (STANDARD 3)

Standard 3 of the MassDEP Stormwater Policy prescribes that the stormwater runoff volume to be recharged to groundwater should be determined using existing soil characteristics. According to the Bristol County Soil Survey, this soil onsite is categorized as;

• Paxton, Whitman and Woodbridge extremely stony, fine, sandy loam. These are in hydrologic soil group C and D.

For C and D soils, infiltration needs to be provided to the maximum extent practicable. Due to the high-water table and relative impermeable soils, it was determined not to be practicable to provide subsurface infiltrators. Therefore, Standard 3 is met.

7.3.4 REMOVAL OF 80% OF TOTAL SUSPENDED SOLIDS (STANDARD 4)

Standard 4 of the MassDEP Stormwater Policy requires removal of 80% of total suspended solids before discharge of stormwater. This standard is met because no additional pavement area is proposed.

7.3.5 USES WITH HIGHER POTENTIAL POLLUNTANT LOADS (STANDARD 5)

Standard 5 of the MassDEP Stormwater Policy requires that stormwater discharges with higher potential pollutant loads, such as gas stations, be provided with specific BMPs. This site is not classified as a LUHPPLS, therefore Standard 5 does not apply.

7.3.6 STORMWATER DISCHARGES TO CRITICAL AREAS (STANDARD 6)

Standard 6 of the MassDEP Stormwater Policy seeks to protect critical areas. Critical areas are specifically designated Outstanding Resource Waters such as shell fish beds, swimming beaches, cold water fisheries and recharge areas for public water supplies. This site is not in an area as defined by the Stormwater Standards as a Critical Area. Therefore, Standard 6 does not apply.

7.3.7 REDEVELOPMENT OR PREVIOUSLY DEVELOPED SITES (STANDARD 7)

Standard 7 of the MassDEP Stormwater Policy applies to sites which have been previously developed and are being re-developed. Diminished performance of BMPs is allowed in these areas. This site qualifies as re-development; however, the design was able to meet the primary MassDEP requirements. Therefore, this standard is met.

7.3.8 EROSION AND SEDIMENT CONTROL (STANDARD 8)

Standard 8 of the MassDEP Stormwater Policy requires that erosion and sediment control measures be designed. Please refer to the Erosion Plan in Appendix B. Further, a NPDES SWPPP will be prepared prior to construction because the project area is greater than 1 acre.

7.3.9 OPERATIONS AND MAINTENANCE PLANS (STANDARD 9)

Standard 9 of the MassDEP Stormwater Policy prescribes the adoption of a formal operation and maintenance plan to ensure that the stormwater management systems function properly as designed. Appendix D presents the Operation and Maintenance Plan, so Standard 9 is met.

7.3.10 PROHIBITION OF ILLICIT DISCHARGES (STANDARD 10)

Standard 10 prohibits illicit discharges. Appendix E addresses the non-existence of illicit discharges.

APPENDIX A WETLAND FIELD DATA SHEETS

MassDEP Bordering Vegetated Wetland (310 CMR 10.55) Delineation Field Data Form

Α			

Prepared by: **Ecosystem Solutions** Project Location: **Church St. New Bedford** DEP File #:

Check all that apply:

□ Vegetation alone presumed adequate to delineate BVW boundary: fill out Section I only

Observation Plot Number

- ☑ Vegetation and other indicators of hydrology used to delineate BVW boundary: fill out Sections I and II
- ☐ Method other than dominance test used (attach additional information)

Section I.

		Observation Plot Number.	U	Hansect #. AZO	Date. 4/2//2022		4
	Common Name	Scientific Name	Percent Cover	Percent Dominance	Dominant Plant?	Wetland Indicator Plant?	Wetland Indicator Category
р	Wild-lily-of-the-valley	Maianthemum canadense	10.5	33	YES	NO	FAC-
Ground	American starflower	Trientalis borealis*	10.5	33	YES	YES	FAC
9	Pennyslyvania sedge	Carex pensylvanica	10.5	33	YES	NO	NI
Shrub	Coast pepper-bush*	Clethra alnifolia	85.5	89	YES	YES	FAC+
Shi	American holly	llex opaca	10.5	11	NO	NO	FACU+
Vine	Common greenbrier*	Smilax rotundifolia	63	100	YES	YES	FAC
	Eastern white pine	Pinus strobus	63	67	YES	NO	FACU
Tree	White oak	Quercus alba	20.5	22	YES	NO	FACU-
	Red maple*	Acer rubrum	10.5	11	NO	YES	FAC

ш

Transect # A28

Date: 4/27/2022

FAC, FAC+, FACW-, FACW+, or OBL; or plants with physiological or morphological adaptations. If any plants are identified as wetland indicator plants due to physiological or morphological adaptations, describe the adaptation next to the asterisk

Vegetation conclusion:

Number of dominant wetland indicator plants: 3 Number of dominant non-wetland indicator plants: 4

Is the number of dominant wetland plants equal to or greater than the number of dominant non-wetland plants?

NO

Upland @ A28

Section II. Indicators of Hydrology

Hydric Soil Interpretation 1. Soil Survey Is there a published soil survey for this site? Yes				Other Indicators of Hydrology: (check al Site Inundated:	that apply & de	escribe)	
Title/date:		Brist	Yes ol County South, 1981 d via Web Soil Survey	☐ Depth to free water in observa	tion hole:		
Soil type i Hydric soi	mapped:	312B/WtB- Wo	odbridge estfsl, 0-8% Ridgebury	☐ Depth to soil saturation in obse	ervation hole:		
Are field o	bservatio	ns consistent with soil surve	y? Yes	☐ Water marks:			
Remarks:				☐ Drift lines:			
				☐ Sediment Deposits:			
2. Soil De	escription	1		☐ Drainage patterns in BVW:			
Horizon	Depth	Color	Redox	☐ Oxidized rhizospheres:			
Α	0-2	10YR 2/2 (fsl)	-				
E	2-4	10YR 4/1 (sl)	-	☐ Water-stained leaves:			
Bh	4-6	10YR 3/3 (sl)	-				
Bw	6-12	10YR 5/6 (sl)	-	☐ Recorded Data (streams, lake, or tidal gauge; aerial photo):			
С	12-20	10YR 5/4 (Is)	-				
				☐ Other:			
Remarks:				Vegetation & Hydrolog	y Conclusion YES	NO	
3. Other:				Number of wetland indicator plants ≥ # of non-wetland indicator plants		Ø	
Conclusio	on: Is soil l	nydric? No		Wetland hydrology present Hydric soil Other indicators of hydrology		<u>ଏ</u>	
				Sample location is in a BVW	N	0	

MassDEP Bordering Vegetated Wetland (310 CMR 10.55) Delineation Field Data Form

Applicant: Prepared by: Ecosystem Solut	ions	Project Location: Church St. New Bedford	DEP File #:	
Check all that apply:				
☐ Vegetation a	lone presumed adequate to deli	lineate BVW boundary: fill out Section I only		
☑ Vegetation and other indicators of hydrology used to delineate BVW boundary: fill out Sections I and II				
☐ Method othe	r than dominance test used (atta	ach additional information)		
Section I.	·	·		

Observation Plot Number: U Transect #: A28 Date: 4/27/2022

	Common Name	Scientific Name	Percent Cover	Percent Dominance	Dominant Plant?	Wetland Indicator Plant?	Wetland Indicator Category
Ground	Bog blackberry*	Rubus hispidoides	10.5	100	YES	YES	FACW
Shrub	Coast pepper-bush*	Clethra alnifolia	98	83	YES	YES	FAC+
Shr	Highbush blueberry*	Vaccinium corymbosum	20.5	17	NO	YES	FACW-
Vine	Common greenbrier*	Smilax rotundifolia	85.5	100	YES	YES	FAC
	Red maple*	Acer rubrum	85.5	73	YES	YES	FAC
Tree	White oak	Quercus alba	20.5	18	NO	NO	FACU-
	Eastern white pine	Pinus strobus	10.5	9	NO	NO	FACU

FAC, FAC+, FACW-, FACW+, or OBL; or plants with physiological or morphological adaptations. If any plants are identified as wetland indicator plants due to physiological or morphological adaptations, describe the adaptation next to the asterisk

Vegetation	conclusion:
	000.0.0

Number of dominant wetland indicator plants: 4 Number of dominant non-wetland indicator plants: 0

Is the number of dominant wetland plants equal to or greater than the number of dominant non-wetland plants?

YES

If vegetation alone is presumed adequate to delineate the BVW boundary, submit this form with the Request for Determination of Applicability or Notice of Intent

Wetland @ A28

Section II. Indicators of Hydrology

Hydric So 1. Soil Su	ırvey	retation d soil survey for this site?	Yes		ors of Hydrology: (check all Site Inundated:	that apply & d	escribe)
Title/date	•	•	ol County South, 1981		Depth to free water in observat	ion hole: 12"	
Soil type	Map number: Accessed via Web Soil Survey Soil type mapped: 73A/WhA- Whitman estfsl, 0-3% Hydric soil inclusions: Ridgebury, Scarboro, Swansea		-	Ø C	Depth to soil saturation in obse	rvation hole: 8"	
		_			Vater marks:		
		ons consistent with soil survey	? Yes		Orift lines:		
Remarks:					Sediment Deposits:		
2. Soil De	escription	1			Orainage patterns in BVW:		
Horizon	Depth	Color	Redox	☐ Oxidized rhizospheres:			
Α	0-3	10YR 2/1 (fsl)	-	<u> </u>			
Е	3-5	10YR 5/1 (sl)	7.5YR 4/6	☐ Water-stained leaves:			
Bw	5-8	10YR 5/4 (sl)	7.5YR 4/6				
С	8-20	2.5Y 5/4 (Is)	2.5Y 6/2 (depletions)		Recorded Data (streams, lake,	or tidal gauge;	aerial photo):
]	Other:		
Remarks:	:				Vegetation & Hydrology	y Conclusion	
						YES	NO
3. Other:					wetland indicator plants wetland indicator plants	\square	
				Wetland hyd	drology present		
				Hydric so		\square	
Conclusio	n: Is soil	hydric? Yes			icators of hydrology		
				Sample loc	ation is in a BVW	YE	S

MassDEP Bordering Vegetated Wetland (310 CMR 10.55) Delineation Field Data Form

Α			

Prepared by: **Ecosystem Solutions** Project Location: **Church St. New Bedford** DEP File #:

Check all that apply:

□ Vegetation alone presumed adequate to delineate BVW boundary: fill out Section I only

Observation Plot Number:

- ☑ Vegetation and other indicators of hydrology used to delineate BVW boundary: fill out Sections I and II
- ☐ Method other than dominance test used (attach additional information)

Section I.

		Observation Flot Number.	U	Transect #. D43	Date. 4/2/12022		_
	Common Name	Scientific Name	Percent Cover	Percent Dominance	Dominant Plant?	Wetland Indicator Plant?	Wetland Indicator Category
Ground	Wild-lily-of-the-valley	Maianthemum canadense	10.5	100	YES	NO	FAC-
Shrub	Coast pepper-bush*	Clethra alnifolia	98	90	YES	YES	FAC+
Shi	American holly	llex opaca	10.5	10	NO	NO	FACU+
Vine	Common greenbrier*	Smilax rotundifolia	20.5	100	YES	YES	FAC
	White oak	Quercus alba	63	44	YES	NO	FACU-
	Red maple* Acer rubrum		38	27	YES	YES	FAC
Tree	American holly	llex opaca	20.5	14	NO	NO	FACU+
'	Northern red oak	Quercus rubra	10.5	7	NO	NO	FACU-
	Eastern white pine	Pinus strobus	10.5	7	NO	NO	FACU

ш

Transect # B49

Date: 4/27/2022

FAC, FAC+, FACW-, FACW+, or OBL; or plants with physiological or morphological adaptations. If any plants are identified as wetland indicator plants due to physiological or morphological adaptations, describe the adaptation next to the asterisk

Vegetation conclusion:

Number of dominant wetland indicator plants:

3 Number of dominant non-wetland indicator plants:

Is the number of dominant wetland plants equal to or greater than the number of dominant non-wetland plants?

YES

Upland @ B49

Section II. Indicators of Hydrology

Hydric Soil Interpretation 1. Soil Survey				ther Indicators of Hydrology: (check	all that apply & de	escribe)
	•	locil curvey for this cite?	Vac	☐ Site Inundated:		
Title/date:			Yes ol County South, 1981 d via Web Soil Survey	☐ Depth to free water in obser	vation hole:	
Soil type i	mapped:	312B/WtB- Wo	odbridge estfsl, 0-8% Ridgebury	☐ Depth to soil saturation in ob	servation hole:	
Trydrio 30i	ii iiioidoloi		Ridgebary	□ Water marks:		
Are field o	heervatio	ns consistent with soil surve	u? Vas	□ Water marks.		
Ale lielu c	bosei valio	ns consistent with son surve	y: 163	☐ Drift lines:		
Remarks:				□ Diiit iiiles.		
Remarks.				☐ Sediment Deposits:		
2. Soil De	escription	ı		☐ Drainage patterns in BVW:		
Horizon	Depth	Color	Redox	☐ Oxidized rhizospheres:		
Α	0-2	10YR 2/2 (fsl)	-			
Е	2-4	10YR 4/1 (sl)	1	☐ Water-stained leaves:		
Bh	4-6	10YR 3/3 (sl)	-			
Bw	6-12	10YR 5/6 (sl)	-	☐ Recorded Data (streams, lal	ke, or tidal gauge;	aerial photo):
С	12-20	10YR 5/4 (Is)	-			
				☐ Other:		
Remarks:				Vegetation & Hydrolo	ogy Conclusion YES	NO
3. Other:				Number of wetland indicator plants ≥ # of non-wetland indicator plants		
Conclusio	on: Is soil h	nydric? No		Wetland hydrology present Hydric soil Other indicators of hydrology		
				Sample location is in a BVW		

MassDEP Bordering Vegetated Wetland (310 CMR 10.55) Delineation Field Data Form

Applicant:				
Prepared by: Ecosystem Solutions	Project Location: Church St. New Bedford	DEP File #:		
Check all that apply:				
Vegetation alone presumed adequate to delineat	te BVW boundary: fill out Section I only			
☑ Vegetation and other indicators of hydrology used to delineate BVW boundary: fill out Sections I and II				
☐ Method other than dominance test used (attach a	additional information)			
Section I.				

		Observation Plot Number:	W	Transect #: B49		Date: 4/27/202 2	2
	Common Name	Scientific Name	Percent Cover	Percent Dominance	Dominant Plant?	Wetland Indicator Plant?	Wetland Indicator Category
Ground	Cinnamon fern*	Osmunda cinnamomea	38	100	YES	YES	FACW
Shrub	Coast pepper-bush*	Clethra alnifolia	98	83	YES	YES	FAC+
Shi	Highbush blueberry*	Vaccinium corymbosum	20.5	17	NO	YES	FACW-
Vine	Common greenbrier*	Smilax rotundifolia	63	100	YES	YES	FAC
	Red maple*	Acer rubrum	63	75	YES	YES	FAC
Tree	Eastern white pine	Pinus strobus	10.5	13	NO	NO	FACU
·	White oak	Quercus alba	10.5	13	NO	NO	FACU-

FAC, FACH, FACW-, FACW, FACW+, or OBL; or plants with physiological or morphological adaptations. If any plants are identified as wetland indicator plants due to physiological or morphological adaptations, describe the adaptation next to the asterisk

Vegetation conclusion:

Number of dominant wetland indicator plants: Number of dominant non-wetland indicator plants: 0

Is the number of dominant wetland plants equal to or greater than the number of dominant non-wetland plants?

YES

If vegetation alone is presumed adequate to delineate the BVW boundary, submit this form with the Request for Determination of Applicability or Notice of Intent

Wetland @ B49

Section II. Indicators of Hydrology

Hydric So 1. Soil Su	urvey	retation d soil survey for this site?	Yes		ators of Hydrology: (check all Site Inundated:	that apply & de	escribe)
Title/date	•	•	ol County South, 1981		Depth to free water in observat	ion hole: 12"	
Map number: Soil type mapped: Hydric soil inclusions: Accessed via Web Soil Surve 73A/WhA- Whitman estfsl, 0-30 Ridgebury, Scarboro, Swanse		Whitman estfsl, 0-3%	☑	Depth to soil saturation in obse	rvation hole: 9"		
Ana field a	Are field observations consistent with soil survey? Yes				Water marks:		
Are field (observatio	ons consistent with soil survey	? Yes		Drift lines:		
Remarks:	• •			_			
					Sediment Deposits:		
2. Soil De	escriptio	n			Drainage patterns in BVW:		
Horizon	Depth	Color	Redox] 🗆	Oxidized rhizospheres:		
Oa	0-4	2.5Y 2.5/1	-				
С	4-14	2.5Y 6/3 (Is)	7.5YR 4/6		Water-stained leaves:		
Cg	14-18	10YR 5/1 (Is)	-				
Cr	18+	Refusal	-		Recorded Data (streams, lake,	or tidal gauge;	aerial photo):
] 	Other:		
Remarks:	:				Vegetation & Hydrology	/ Conclusion	
						YES	NO
3. Other:					of wetland indicator plants n-wetland indicator plants	\square	
				Hydric			
Conclusio	on: Is soil	hydric? Yes		Other in	ndicators of hydrology	\square	
				Sample I	ocation is in a BVW	Ye	?S

MassDEP Bordering Vegetated Wetland (310 CMR 10.55) Delineation Field Data Form

Ann	licant:
, ,PP	iioaiit.

Prepared by: **Ecosystem Solutions**Project Location: **Church St. New Bedford**DEP File #:

Check all that apply:

☐ Vegetation alone presumed adequate to delineate BVW boundary: fill out Section I only

Observation Dlot Number:

- ☑ Vegetation and other indicators of hydrology used to delineate BVW boundary: fill out Sections I and II
- ☐ Method other than dominance test used (attach additional information)

Section I.

		Observation Plot Number:	U	ransect #: F15	ļ	Date: 4/2//202 2	
	Common Name	Scientific Name	Percent Cover	Percent Dominance	Dominant Plant?	Wetland Indicator Plant?	Wetland Indicator Category
Ground	Pennyslyvania sedge	Carex pensylvanica	20.5	100	YES	NO	NI
	Coast pepper-bush*	Clethra alnifolia	63	55	YES	YES	FAC+
Shrub	Highbush blueberry*	Vaccinium corymbosum	20.5	18	NO	YES	FACW-
Sh	Eastern white pine	Pinus strobus	20.5	18	NO	NO	FACU
	American holly	llex opaca	10.5	9	NO	NO	FACU+
Vine	Common greenbrier*	Smilax rotundifolia	63	100	YES	YES	FAC
Tree	Red maple*	Acer rubrum	38	65	YES	YES	FAC
بّ	Northern red oak	Quercus rubra	20.5	35	YES	NO	FACU-

Transact #: E15

Date: 4/27/2022

FAC, FAC+, FACW-, FACW+, or OBL; or plants with physiological or morphological adaptations. If any plants are identified as wetland indicator plants due to physiological or morphological adaptations, describe the adaptation next to the asterisk

Vegetation conclusion:

Number of dominant wetland indicator plants: 3 Number of dominant non-wetland indicator plants: 2

Is the number of dominant wetland plants equal to or greater than the number of dominant non-wetland plants?

YES

Section II. Indicators of Hydrology

-	oil Interpreta	tion			ators of Hydrology: (check all	that apply & de	scribe)
1. Soil Su	•				Site Inundated:		
	•	il survey for this site?	Yes				
Title/date		Bristol County	•		Depth to free water in observat	ion hole:	
Map num		Accessed via Wel	-				
Soil type		73A/WhA- Whitman	-		Depth to soil saturation in obse	rvation hole:	
Hydric so	il inclusions:	Ridgebury, Scarbo	oro, Swansea				
					Water marks:		
Are field	observations	consistent with soil survey? Yes					
					Drift lines:		
Remarks							
					Sediment Deposits:		
				_	D : " : D\AA		
2. Soil De	escription			Ц	Drainage patterns in BVW:		
Horizon	Depth	Color F	Redox		Oxidized rhizospheres:		
110112011	Берит	COIOI	Tedox		Oxidized Mizospheres.		
					Water-stained leaves:		
					Recorded Data (streams, lake,	or tidal gauge; a	erial photo):
					Other:		
							-
Remarks					Vegetation & Hydrology		NO
						YES	NO
3. Other:				Number o	f wetland indicator plants		
				≥# of nor	ı-wetland indicator plants	_	
				Wetland h	nydrology present		
				Hydric	soil		
Conclusion	n: Is soil hyd	ric? No		Other in	ndicators of hydrology		
				Sample le	ocation is in a BVW		

MassDEP Bordering Vegetated Wetland (310 CMR 10.55) Delineation Field Data Form

Applicant: Prepared by: Ecosystem Solutions	Project Location: Church St. New Bedford	DEP File #:
Check all that apply:		
☐ Vegetation alone presumed adequate to deline.	ate BVW boundary: fill out Section I only	
Vegetation and other indicators of hydrology us	sed to delineate BVW boundary: fill out Sections I and II	
☐ Method other than dominance test used (attach	n additional information)	
` ` ` ` ` ` ` ` ` ` ` ` ` ` ` ` ` ` `	•	

Observation Plot Number:

Section I.

		Observation Flot Number.	VV	Transect #. 1 13		Jaic. TIZITZUZZ	-
	Common Name	Scientific Name	Percent Cover	Percent Dominance	Dominant Plant?	Wetland Indicator Plant?	Wetland Indicator Category
Ground	Sphagnum moss*	Sphagnum spp.	10.5	100	YES	YES	OBL
Q	Coast pepper-bush*	Clethra alnifolia	85.5	64	YES	YES	FAC+
Shrub	Highbush blueberry*	Vaccinium corymbosum	38	28	YES	YES	FACW-
S	Eastern white pine	Pinus strobus	10.5	8	NO	NO	FACU
Vine	Common greenbrier*	Smilax rotundifolia	85.5	69	YES	YES	FAC
Ν̈́	Poison ivy*	Toxicodendron radicans	38	31	YES	YES	FAC
0)	Red maple*	Acer rubrum	98	76	YES	YES	FAC
Tree	Eastern white pine	Pinus strobus	20.5	16	NO	NO	FACU
	Sassafras	Sassafras albidum	10.5	8	NO	NO	FACU-

W

Transect #: F15

Date: 4/27/2022

FAC, FAC+, FACW-, FACW+, or OBL; or plants with physiological or morphological adaptations. If any plants are identified as wetland indicator plants due to physiological or morphological adaptations, describe the adaptation next to the asterisk

Vegetation	conclusion:
· ogotation	oonoraoron.

Number of dominant wetland indicator plants:

6 Number of dominant non-wetland indicator plants:

0

Is the number of dominant wetland plants equal to or greater than the number of dominant non-wetland plants?

YES

Wetland @ F15

Section II. Indicators of Hydrology

1. Soil S	Hydric Soil Interpretation 1. Soil Survey Is there a published soil survey for this site? Yes			Other Indicators of Hydrology: (check all the Site Inundated:	nat apply & d	escribe)
Title/date Map num	· :	Bristo	ol County South, 1981 d via Web Soil Survey	☑ Depth to free water in observation	n hole:	
Soil type mapped: 73A/WhA- Whitman estfsl, 0-3 Hydric soil inclusions: Ridgebury, Scarboro, Swans		Whitman estfsl, 0-3%		/ation hole:		
Are field	observatio	ons consistent with soil survey?	? Yes	☐ Water marks:		
Remarks	:			☐ Drift lines:		
				☐ Sediment Deposits:		
2. Soil D	escriptior	1		☐ Drainage patterns in BVW:		
Horizon	Depth	Color	Redox	☐ Oxidized rhizospheres:		
^C Oab	0-10 10-20	10YR 3/1 (gsl) 2.5Y 2.5/1		☑ Water-stained leaves:		
				☐ Recorded Data (streams, lake, c	r tidal gauge;	aerial photo):
				☐ Other:		
Remarks	:			Vegetation & Hydrology	Conclusion YES	NO
3. Other:				Number of wetland indicator plants ≥ # of non-wetland indicator plants	Ø	
				Wetland hydrology present Hydric soil	☑	
Conclusion	on: Is soil	hydric? Yes		Other indicators of hydrology	Ø	
				Sample location is in a BVW	YI	ES

APPENDIX B

EROSION AND SEDIMENT CONTROL

Erosion and Sediment Controls

Soil erosion is the process by which the surface of the land is worn away by the action of wind, water, ice, and gravity. Natural or geologic erosion is a factor in creating the topographic features of the earth as we know it today. Except for some cases of shoreline and stream channel erosion, natural erosion occurs at a very slow and uniform rate. Accelerated erosion occurs when the surface of the land is disturbed and vegetation is removed by either natural forces or man's activities. Exposed, unprotected soil is then subject to rapid erosion by the action of wind or water. The erosive action of water can be separated into two categories: raindrop erosion which is the result of the vertical force of falling water; and sheet, rill, and gully erosion which are the result of the horizontal force of flowing water. Both forces detach and move soil particles.

During construction, the contractor is directed to comply with the precautionary measures provided in the contract documents, and to conduct his construction activities in such a manner as to prevent damage or impairment to the environment. It shall be the contractor's responsibility not to undertake at any time, in any particular area, more than that magnitude of work which can be safely and adequately controlled by the forces at his disposal. Failure on the part of the contractor to cooperate with the responsible person to regulate the works set forth in the contract documents to successful completion, shall constitute grounds for suspension of construction activities of the contract. An emphasis shall be made to control erosion before it occurs. Upon completion of the project, no soil shall be left exposed (bare) in any of the construction areas of the site.

Erosion and Sediment Control Plan

To address the above issues, an Erosion and Sedimentation Control Plan has been developed which describes the potential for erosion and sedimentation problems on the project and explains and illustrates the measures which are to be taken to control those issues. The plan is implemented by the project contractor(s) based on requirements shown on the construction drawings and technical specification, as well as requirements detailed in permits which become part of the contract between the owner and contractor.

Erosion and Sediment Control Techniques

Erosion and sedimentation controls shall be employed to minimize erosion and transport of sediment into on-site and adjacent resource areas during the earthwork and construction phases of the project. The major erosion control techniques proposed include hay bale barriers, silt fence barriers, inlet sediment traps, a stabilized construction entrance, and erosion control matting. A detailed description of each technique is discussed below.

Temporary Erosion Control Measures

During construction activities, the following measures shall be employed to minimize the potential impacts to wetland and water resources within the project area from siltation and sedimentation. The erosion control measures are shown on the site plans.

Preservation of Natural Vegetation

Natural vegetation shall be preserved on site where possible. This measure will prevent erosion by providing continuous anchoring of the soil.

Drainage Swale Hay Bale Check Dams

Hay bales shall also be placed across construction ditches during construction to limit the transport of sediment into drainage systems and waterways.

Silt Fences

Silt fences shall be placed at the limits of work where the slope is less than two percent. Typically, they shall be installed adjacent to resource areas, where soil will be exposed due to construction related activities, as depicted on the plans. The fence shall be placed in a sturdy, upright position and supported/anchored to withstand the forces of the elements and the circumstances of construction activities. The fence shall be installed in a manner that shall prevent runoff from passing over, under or around the fence (i.e. all of the runoff will pass through the fence). They shall be attached to posts (either steel or wood) in sufficient number to support the fence. The posts shall typically be placed 4 to 8 feet apart. It shall be the construction contractor's responsibility to maintain the fence in a functional condition throughout the duration of construction activities. The contractor shall also remove any large accumulations of sediment in a timely manner and dispose the material appropriately.

Hay Bales

Hay bales shall be placed, in conjunction with silt fences, at the limit of work on steep slopes only. Steep slopes for this project are those which are greater than two percent. The hay bales shall be staked with metal or wood stakes to anchor them to the ground. The contractor shall be responsible for maintaining the hay bales in good condition and replacing them as necessary. Bales that deteriorate and are no longer intact or that become plugged with sediment shall be removed and disposed. They shall be replaced with new hay bales installed as described above.

Erosion and Sediment Control - Maintenance

The general contractor shall have primary responsibility for implementing temporary and permanent controls described in the plan and shall be responsible for assuring contractor compliance with contract documents including all erosion and sediment control measures.

- 1. The on-site contractor shall inspect sediment and erosion control structures weekly and after each rainfall event greater than ½ inch. Records of the inspections shall be prepared and maintained on site by the contractor (Attachment 1).
- 2. Silt shall be removed from behind barriers if greater than 6 inches deep or as needed to ensure the stability of the control device.
- 3. Damaged or deteriorated items shall be repaired or replaced immediately after identification.

4. The underside of hay bales shall be kept in close contact with the earth and reset as necessary.

Once construction in a particular area has been completed and the areas have been stabilized, these temporary devices shall be removed.

Δ	$\Gamma T A$	CHN	MENT	1
	_			

INSPECTION AND MAINTENANCE REPORT FORM

STORMWATER POLLUTION PREVENTION PLAN WEEKLY INSPECTION AND MAINTENANCE REPORT FORM

Inspector:	Title	Date:					
Specific Site Location:							
STABILIZATION MEASURES							
AREA	INSTALLED? (Yes/No)	CONDITION OF STABILIZATION MEASURE					
Silt Fences							
Haybales							
Stabilization for Stockpiles							
Seeding and Planting							
Geotextile Fabrics							
TO BE PERFORMED BY	':	_ON OR					
BE	FORE:						
Make note of	the date and location of	of the following:					
•7	The start of grading activ	ities					
•Temporary or permanent cease of grading activities							
•Implem	nentation of temporary st	abilization					
•Impl	lementation of final stabi	lization					

STORMWATER POLLUTION PREVENTION PLAN WEEKLY INSPECTION AND MAINTENANCE REPORT FORM Continued

construction activity if the first inspection) including a best estimate of the beginning of storm event, duration of each storm event, approximate amount of rainfall for each storm (in inches), and whether any discharges occurred;	each
Weather information and a description of any discharges occurring at the time of the insp	ection

Form A-III

STORMWATER POLLUTION PREVENTION PLAN (SWPPP) INSPECTION CHECKLIST - TO BE COMPLETED BY CONTRACTOR

Inspected By:			, Title Date:
YES	NO	DOES NOT APPLY	ITEM
			Are the BMPs called for on the SWPPP installed in the proper location and according to the specification of the SWPPP?
			Are all operational stormwater inlets protected from sediment flow?
			Do any erosion/siltation control measure require repair or clean- out to maintain adequate function? If yes, indicate which ones.
			Are on-site construction traffic routes, parking, and storage of equipment and supplies restricted to areas specifically designated for those uses?
			Are the locations of temporary soil stockpiles or construction materials in approved areas?
			Do any seeded or landscaped areas require maintenance irrigation, fertilization, seeding or mulching?
			Is there any evidence that sediment is leaving the site?
			Is there any evidence of erosion on cut or fill slopes?
			Is there any evidence of sediment, debris, or mud on public roads at intersections with site access roads?
			Notes:
Action to l	be Taken:		

Note: See Page 13, Part 4 (Inspections) of the General Permit (Attachment "L") for additional inspection report requirements.

ATTACHMENT C

CHECKLIST FOR STORMWATER REPORT



Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

A. Introduction

Important: When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.





A Stormwater Report must be submitted with the Notice of Intent permit application to document compliance with the Stormwater Management Standards. The following checklist is NOT a substitute for the Stormwater Report (which should provide more substantive and detailed information) but is offered here as a tool to help the applicant organize their Stormwater Management documentation for their Report and for the reviewer to assess this information in a consistent format. As noted in the Checklist, the Stormwater Report must contain the engineering computations and supporting information set forth in Volume 3 of the Massachusetts Stormwater Handbook. The Stormwater Report must be prepared and certified by a Registered Professional Engineer (RPE) licensed in the Commonwealth.

The Stormwater Report must include:

- The Stormwater Checklist completed and stamped by a Registered Professional Engineer (see page 2) that certifies that the Stormwater Report contains all required submittals. This Checklist is to be used as the cover for the completed Stormwater Report.
- Applicant/Project Name
- Project Address
- Name of Firm and Registered Professional Engineer that prepared the Report
- Long-Term Pollution Prevention Plan required by Standards 4-6
- Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan required by Standard 8²
- Operation and Maintenance Plan required by Standard 9

In addition to all plans and supporting information, the Stormwater Report must include a brief narrative describing stormwater management practices, including environmentally sensitive site design and LID techniques, along with a diagram depicting runoff through the proposed BMP treatment train. Plans are required to show existing and proposed conditions, identify all wetland resource areas, NRCS soil types, critical areas, Land Uses with Higher Potential Pollutant Loads (LUHPPL), and any areas on the site where infiltration rate is greater than 2.4 inches per hour. The Plans shall identify the drainage areas for both existing and proposed conditions at a scale that enables verification of supporting calculations.

As noted in the Checklist, the Stormwater Management Report shall document compliance with each of the Stormwater Management Standards as provided in the Massachusetts Stormwater Handbook. The soils evaluation and calculations shall be done using the methodologies set forth in Volume 3 of the Massachusetts Stormwater Handbook.

To ensure that the Stormwater Report is complete, applicants are required to fill in the Stormwater Report Checklist by checking the box to indicate that the specified information has been included in the Stormwater Report. If any of the information specified in the checklist has not been submitted, the applicant must provide an explanation. The completed Stormwater Report Checklist and Certification must be submitted with the Stormwater Report.

¹ The Stormwater Report may also include the Illicit Discharge Compliance Statement required by Standard 10. If not included in the Stormwater Report, the Illicit Discharge Compliance Statement must be submitted prior to the discharge of stormwater runoff to the post-construction best management practices.

² For some complex projects, it may not be possible to include the Construction Period Erosion and Sedimentation Control Plan in the Stormwater Report. In that event, the issuing authority has the discretion to issue an Order of Conditions that approves the project and includes a condition requiring the proponent to submit the Construction Period Erosion and Sedimentation Control Plan before commencing any land disturbance activity on the site.



Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

B. Stormwater Checklist and Certification

The following checklist is intended to serve as a guide for applicants as to the elements that ordinarily need to be addressed in a complete Stormwater Report. The checklist is also intended to provide conservation commissions and other reviewing authorities with a summary of the components necessary for a comprehensive Stormwater Report that addresses the ten Stormwater Standards.

Note: Because stormwater requirements vary from project to project, it is possible that a complete Stormwater Report may not include information on some of the subjects specified in the Checklist. If it is determined that a specific item does not apply to the project under review, please note that the item is not applicable (N.A.) and provide the reasons for that determination.

A complete checklist must include the Certification set forth below signed by the Registered Professional Engineer who prepared the Stormwater Report.

Registered Professional Engineer's Certification

I have reviewed the Stormwater Report, including the soil evaluation, computations, Long-term Pollution Prevention Plan, the Construction Period Erosion and Sedimentation Control Plan (if included), the Long-term Post-Construction Operation and Maintenance Plan, the Illicit Discharge Compliance Statement (if included) and the plans showing the stormwater management system, and have determined that they have been prepared in accordance with the requirements of the Stormwater Management Standards as further elaborated by the Massachusetts Stormwater Handbook. I have also determined that the information presented in the Stormwater Checklist is accurate and that the information presented in the Stormwater Report accurately reflects conditions at the site as of the date of this permit application.

Registered Professional Engineer Block and Signature

\$

RICHARD J. RHEAUME No. 28373 OSTERER	Signature and Date	6/23/2022
	Checklist	

Project Type: Is the application for new development, redevelopment, or a mix of new and redevelopment?
Redevelopment
Mix of New Development and Redevelopment



Checklist for Stormwater Report

Checklist (continued)

rironmentally sensitive design and LID Techniques were considered during the planning and design of project:
No disturbance to any Wetland Resource Areas
Site Design Practices (e.g. clustered development, reduced frontage setbacks)
Reduced Impervious Area (Redevelopment Only)
Minimizing disturbance to existing trees and shrubs
LID Site Design Credit Requested:
☐ Credit 1
☐ Credit 2
☐ Credit 3
Use of "country drainage" versus curb and gutter conveyance and pipe
Bioretention Cells (includes Rain Gardens)
Constructed Stormwater Wetlands (includes Gravel Wetlands designs)
Treebox Filter
Water Quality Swale
Grass Channel
Green Roof
Other (describe):
andard 1: No New Untreated Discharges
No new untreated discharges
Outlets have been designed so there is no erosion or scour to wetlands and waters of the Commonwealth
Supporting calculations specified in Volume 3 of the Massachusetts Stormwater Handbook included.



Checklist for Stormwater Report

Cr	necklist (continued)
Sta	ndard 2: Peak Rate Attenuation
	Standard 2 waiver requested because the project is located in land subject to coastal storm flowage and stormwater discharge is to a wetland subject to coastal flooding. Evaluation provided to determine whether off-site flooding increases during the 100-year 24-hour storm.
~	Calculations provided to show that post-development peak discharge rates do not exceed pre- development rates for the 2-year and 10-year 24-hour storms. If evaluation shows that off-site flooding increases during the 100-year 24-hour storm, calculations are also provided to show that post-development peak discharge rates do not exceed pre-development rates for the 100-year 24-hour storm.
Sta	indard 3: Recharge
V	Soil Analysis provided.
	Required Recharge Volume calculation provided.
	Required Recharge volume reduced through use of the LID site Design Credits.
	Sizing the infiltration, BMPs is based on the following method: Check the method used.
	☐ Static ☐ Simple Dynamic ☐ Dynamic Field ¹
	Runoff from all impervious areas at the site discharging to the infiltration BMP.
	Runoff from all impervious areas at the site is <i>not</i> discharging to the infiltration BMP and calculations are provided showing that the drainage area contributing runoff to the infiltration BMPs is sufficient to generate the required recharge volume.
	Recharge BMPs have been sized to infiltrate the Required Recharge Volume.
	Recharge BMPs have been sized to infiltrate the Required Recharge Volume <i>only</i> to the maximum extent practicable for the following reason:
	Site is comprised solely of C and D soils and/or bedrock at the land surface
	☐ M.G.L. c. 21E sites pursuant to 310 CMR 40.0000
	☐ Solid Waste Landfill pursuant to 310 CMR 19.000
	Project is otherwise subject to Stormwater Management Standards only to the maximum extent practicable.
	Calculations showing that the infiltration BMPs will drain in 72 hours are provided.
	Property includes a M.G.L. c. 21E site or a solid waste landfill and a mounding analysis is included.

¹ 80% TSS removal is required prior to discharge to infiltration BMP if Dynamic Field method is used.



Checklist for Stormwater Report

Cł	necklist (continued)
Sta	ndard 3: Recharge (continued)
	The infiltration BMP is used to attenuate peak flows during storms greater than or equal to the 10-year 24-hour storm and separation to seasonal high groundwater is less than 4 feet and a mounding analysis is provided.
	Documentation is provided showing that infiltration BMPs do not adversely impact nearby wetland resource areas.
Sta	ndard 4: Water Quality
The	E Long-Term Pollution Prevention Plan typically includes the following: Good housekeeping practices; Provisions for storing materials and waste products inside or under cover; Vehicle washing controls; Requirements for routine inspections and maintenance of stormwater BMPs; Spill prevention and response plans; Provisions for maintenance of lawns, gardens, and other landscaped areas; Requirements for storage and use of fertilizers, herbicides, and pesticides; Pet waste management provisions; Provisions for operation and management of septic systems; Provisions for solid waste management; Snow disposal and plowing plans relative to Wetland Resource Areas; Winter Road Salt and/or Sand Use and Storage restrictions; Street sweeping schedules; Provisions for prevention of illicit discharges to the stormwater management system; Documentation that Stormwater BMPs are designed to provide for shutdown and containment in the event of a spill or discharges to or near critical areas or from LUHPPL; Training for staff or personnel involved with implementing Long-Term Pollution Prevention Plan; List of Emergency contacts for implementing Long-Term Pollution Prevention Plan.
	A Long-Term Pollution Prevention Plan is attached to Stormwater Report and is included as an attachment to the Wetlands Notice of Intent. Treatment BMPs subject to the 44% TSS removal pretreatment requirement and the one inch rule for calculating the water quality volume are included, and discharge:
	is within the Zone II or Interim Wellhead Protection Area
	is near or to other critical areas
	is within soils with a rapid infiltration rate (greater than 2.4 inches per hour)
	involves runoff from land uses with higher potential pollutant loads.
	The Required Water Quality Volume is reduced through use of the LID site Design Credits.

☐ Calculations documenting that the treatment train meets the 80% TSS removal requirement and, if

applicable, the 44% TSS removal pretreatment requirement, are provided.



Checklist for Stormwater Report

Ch	ecklist (continued)
Stai	ndard 4: Water Quality (continued)
	The BMP is sized (and calculations provided) based on:
	☐ The ½" or 1" Water Quality Volume or
	☐ The equivalent flow rate associated with the Water Quality Volume and documentation is provided showing that the BMP treats the required water quality volume.
	The applicant proposes to use proprietary BMPs, and documentation supporting use of proprietary BMP and proposed TSS removal rate is provided. This documentation may be in the form of the propriety BMP checklist found in Volume 2, Chapter 4 of the Massachusetts Stormwater Handbook and submitting copies of the TARP Report, STEP Report, and/or other third party studies verifying performance of the proprietary BMPs.
	A TMDL exists that indicates a need to reduce pollutants other than TSS and documentation showing that the BMPs selected are consistent with the TMDL is provided.
Sta	ndard 5: Land Uses With Higher Potential Pollutant Loads (LUHPPLs)
	The NPDES Multi-Sector General Permit covers the land use and the Stormwater Pollution Prevention Plan (SWPPP) has been included with the Stormwater Report. The NPDES Multi-Sector General Permit covers the land use and the SWPPP will be submitted <i>prior</i> (1997).
	to the discharge of stormwater to the post-construction stormwater BMPs. The NPDES Multi-Sector General Permit does not cover the land use.
	LUHPPLs are located at the site and industry specific source control and pollution prevention measures have been proposed to reduce or eliminate the exposure of LUHPPLs to rain, snow, snow melt and runoff, and been included in the long term Pollution Prevention Plan.
	All exposure has been eliminated.
	All exposure has <i>not</i> been eliminated and all BMPs selected are on MassDEP LUHPPL list.
	The LUHPPL has the potential to generate runoff with moderate to higher concentrations of oil and grease (e.g. all parking lots with >1000 vehicle trips per day) and the treatment train includes an oil grit separator, a filtering bioretention area, a sand filter or equivalent.
Sta	ndard 6: Critical Areas
	The discharge is near or to a critical area and the treatment train includes only BMPs that MassDEP has approved for stormwater discharges to or near that particular class of critical area.
	Critical areas and BMPs are identified in the Stormwater Report.



Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Checklist (continued)

Standard 7: Redevelopments and Other Projects Subject to the Standards only to the maximum extent practicable

✓	The project is subject to the Stormwater Management Standards only to the maximum Extent Practicable as a:
	✓ Limited Project
	 Small Residential Projects: 5-9 single family houses or 5-9 units in a multi-family development provided there is no discharge that may potentially affect a critical area. Small Residential Projects: 2-4 single family houses or 2-4 units in a multi-family development with a discharge to a critical area Marina and/or boatyard provided the hull painting, service and maintenance areas are protected from exposure to rain, snow, snow melt and runoff
	☐ Bike Path and/or Foot Path
	Redevelopment Project
	Redevelopment portion of mix of new and redevelopment.
	Certain standards are not fully met (Standard No. 1, 8, 9, and 10 must always be fully met) and an explanation of why these standards are not met is contained in the Stormwater Report. The project involves redevelopment and a description of all measures that have been taken to improve existing conditions is provided in the Stormwater Report. The redevelopment checklist found in Volume 2 Chapter 3 of the Massachusetts Stormwater Handbook may be used to document that the proposed stormwater management system (a) complies with Standards 2, 3 and the pretreatment and structural BMP requirements of Standards 4-6 to the maximum extent practicable and (b) improves existing conditions.

Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan must include the following information:

- Narrative;
- Construction Period Operation and Maintenance Plan;
- Names of Persons or Entity Responsible for Plan Compliance;
- Construction Period Pollution Prevention Measures:
- Erosion and Sedimentation Control Plan Drawings;
- Detail drawings and specifications for erosion control BMPs, including sizing calculations;
- Vegetation Planning;
- Site Development Plan;
- Construction Sequencing Plan;
- Sequencing of Erosion and Sedimentation Controls;
- Operation and Maintenance of Erosion and Sedimentation Controls;
- Inspection Schedule;
- Maintenance Schedule:
- Inspection and Maintenance Log Form.
- A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan containing the information set forth above has been included in the Stormwater Report.



Checklist for Stormwater Report

Checklist (continued)

	Indard 8: Construction Period Pollution Prevention and Erosion and Sedimentation ntinued)	Control
	The project is highly complex and information is included in the Stormwater Report that e it is not possible to submit the Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan with the application. A Construction Period Pollution Prevent Erosion and Sedimentation Control has <i>not</i> been included in the Stormwater Report but submitted <i>before</i> land disturbance begins.	on and
	The project is <i>not</i> covered by a NPDES Construction General Permit.	
	The project is covered by a NPDES Construction General Permit and a copy of the SWP Stormwater Report.	PP is in the
	The project is covered by a NPDES Construction General Permit but no SWPPP been surface SWPPP will be submitted BEFORE land disturbance begins.	bmitted.
Sta	ndard 9: Operation and Maintenance Plan	
	The Post Construction Operation and Maintenance Plan is included in the Stormwater Reincludes the following information:	port and
	☐ Name of the stormwater management system owners;	
	☐ Party responsible for operation and maintenance;	
	☐ Schedule for implementation of routine and non-routine maintenance tasks;	
	☐ Plan showing the location of all stormwater BMPs maintenance access areas;	
	☐ Description and delineation of public safety features;	
	☐ Estimated operation and maintenance budget; and	
	Operation and Maintenance Log Form.	
	The responsible party is not the owner of the parcel where the BMP is located and the State Report includes the following submissions:	ormwater
	A copy of the legal instrument (deed, homeowner's association, utility trust or other legal that establishes the terms of and legal responsibility for the operation and maintenan project site stormwater BMPs;	
	A plan and easement deed that allows site access for the legal entity to operate and BMP functions.	maintain
Sta	ndard 10: Prohibition of Illicit Discharges	
	The Long-Term Pollution Prevention Plan includes measures to prevent illicit discharges;	
	An Illicit Discharge Compliance Statement is attached;	
	NO Illicit Discharge Compliance Statement is attached but will be submitted <i>prior to</i> the any stormwater to post-construction BMPs.	discharge of

ATTACHMENT D

PERMANENT OPERATOIN AND MAINTENANCE PLAN

PERMANENT STORMWATER SYSTEM OPERATION AND MAINTENANCE PROGRAM FRADES INTERMODAL TERMINAL 781 CHURCH STREET NEW BEDFORD, MA

PREPARED FOR:

FRADES DISPOSAL, INC. 781 CHURCH STREET NEW BEDFORD, MA

PREPARED BY:

PRIME ENGINEERING, INC. P.O. BOX 1088 LAKEVILLE, MA

1.0 INTRODUCTION

Frades Disposal facility located at 781 Church Street, New Bedford, proposes to construct an intermodal terminal at a proposed rail siding off the Mass Coastal Rail at the existing facility. The site is an approximately 47-acre parcel of land referenced as Map 125-1, Lot 10 and Map 129, Lots 38, 41, 42, 52, 53 and 55. It is bordered on the north and west by Route 140. It is bordered on the east by the Mass Coastal Rail, and is bordered on the south by undeveloped woodland. Throughout the remainder of this report, Frades Disposal, Inc. and the intermodal terminal will be referred to as "The Project."

2.0 RESPONSIBLE PARTY

Responsible Party: Richard Frades, President

Frades Disposal, Inc. 781 Church Street

New Bedford, MA 02745

508-995-9121

3.0 SOURCE CONTROL MEASURES

The most effective means of providing clean runoff is to prevent pollutants from coming into contact with stormwater in the first place. This involves the following:

- Keeping fertilizers, stockpiles, etc. covered at all times. All such products shall be stored off-site.
- Landscaping, fertilization and other grounds maintenance, if necessary, shall be performed by personnel who are trained to maintain the grounds.
- Periodic removal of windblown debris and litter from the site.

4.0 MAINTENANCE OF STORM SYSTEM

This section presents the periodic maintenance that must be completed:

The swales and rain gardens shall be inspected annually. A bi-annual report signed by a
MA licensed professional engineer shall be provided to the New Bedford Conservation
Commission.

5.0 SPILL PREVENTION AND RESPONSE PLAN

The project consists of a rail spur and siding that will not emit any significant pollutants. The only potential source of pollution is the wind-blown litter which will be controlled with fencing and weekly cleanup. The responsible party shall train maintenance personnel in the proper handling and cleanup of spilled hazardous substances or oil. No spilled hazardous substances or oil shall be allowed to come in contact with stormwater discharges. If such contact occurs, the stormwater discharge shall be contained on site until appropriate measures, in compliance with state and federal regulations, are taken to dispose such contaminated stormwater. The responsible party shall train personnel in spill prevention and cleanup procedures.

In order to prevent or minimize the potential for a spill of hazardous substances or oil to come into contact with stormwater, the following steps shall be implemented:

- A spill control and containment kit (containing, for example, absorbent materials, rags, gloves, plastic and metal trash containers, etc.) is maintained on-site.
- Manufacturer's recommended methods for spill cleanup shall be known and maintenance personnel shall be trained regarding these procedures and the location of the information and cleanup supplies.
- The Responsible Party shall ensure that hazardous waste discovered or generated at the site is disposed properly by a licensed hazardous material disposal company. The Responsible Party shall not exceed hazardous waste storage requirements mandated by the EPA or state and local authorities.

In the event of a spill of hazardous substances or oil, the following procedures must be followed:

- All measures must be taken to contain and abate the spill and to prevent discharge of the hazardous substance or oil to stormwater or off-site.
- For spills of less than a quarter gallon of material, proceed with source control and containment, clean-up with absorbent materials or other applicable means, unless an imminent hazard or other circumstances dictate that the spill should be treated by a professional emergency response contractor.
- For spills greater than a quarter gallon of material, immediately contact Richard J. Rheaume, L.S.P., Prime Engineering, Inc., P.O. Box 1088, Lakeville, MA 02347 at (508) 947-0050. Provide information on the type of material spilled, the location of the spill, the quantity spilled, the time of the spill and proceed with the prevention, containment and/or clean-up.
- Spills of amounts that exceed reportable quantities of certain substances specifically mentioned in federal regulations 40 CFR 110, 40 CFR 117, 40 CFR 302 must be immediately reported to the EPA National Response Center by telephone at (800) 242-8802.

The Responsible Party shall be the spill prevention and response coordinator. She/he shall designate the individuals who shall receive spill prevention and response training. These individuals shall each become responsible for a particular phase of prevention and response. The names of these personnel should be posted in the material storage area and in the property office.

Any spill that occurs shall be documented on a Spill Report form that is enclosed as Attachment 1.

6 SNOW AND ICE REMOVAL

Snow and ice shall be removed primarily by mechanical equipment. Salt and sand shall only be applied when the safety of the personnel is at stake.

ATTACHMEN	
BLANK SPILL REPO)KT

SPILL REPORT

	
QUANTITY:	
AND CODDECTIVE ME	ACUDEC
AND CURRECTIVE ME	ASUKES
	QUANTITY:

ATTACHMENT E

ILLICIT DISCHARGE STATEMENT

INTERIM ILLICIT DISCHARGE STATEMENT

1.0 INTRODUCTION

The following is an Interim Illicit Discharge Statement based on existing conditions and design conditions. Once construction is complete, a final illicit discharge statement shall be issued to the New Bedford Conservation Commission based on as-built conditions.

2.0 EXISTING CONDITIONS

The existing facility is a warehouse and waste handling facility. There are no known illicit connections in this area. No sources of illicit discharges were uncovered when this system was recently surveyed. Based on this investigation, to the best of my knowledge, there are no current illicit discharges to the storm drainage system. If during construction, an illicit discharge is discovered, it shall be removed immediately.

3.0 PROPOSED DESIGN

The proposed design calls for a standard stormwater collection system. There are no points in the proposed storm drainage system where illicit discharges are likely to occur.

Certain types of discharges are allowable under the U.S. Environmental Protection Agency Construction General Permit and it is the intent of the site's Long Term Pollution Prevention Plan to allow such discharges. These types of discharges shall be allowed under the conditions that no pollutants shall be allowed to come in contact with the water prior to or after its discharge. The control measures which have been outlined in the Long Term Pollution Prevention Plan shall be strictly followed to ensure that no contamination of these non-stormwater discharges takes place.

I hereby certify that the preceding is accurate.

(Kichard J. Rheaume

Richard J. Rheaume, P.E., LSP

Prime Engineering, Inc.