

STORMWATER REPORT

June 5, 2019

WS Orchard Street New Bedford, MA 02744

ASSESSORS MAP 78 LOTS NORTON, MASSACHUSETTS



PREPARED FOR:

Lisciotti Development Co. 83 Orchard Hill Park Drive Leominster, MA 01453

TABLE OF CONTENTS

SECTIONS:

- 1. PROJECT SUMMARY
- 2. METHODOLOGY
- 3. EXISTING SOIL CONDITIONS
- 4. STORMWATER MANAGEMENT OVERVIEW
- 5. STORMWATER MANAGEMENT STANDARDS

EXHIBTS:

EXHIBIT "A" – USGS MAP (TOPO! VERSION 2.1.0)

EXHIBIT "B" - HYDROLOGIC CALCULATIONS

EXHIBIT "C" - RECHARGE CALCULATIONS

EXHIBIT "D" - TSS REMOVAL CALCULATIONS

EXHIBIT "E" - LONG TERM POLLUTION PREVENTION PLAN

EXHIBIT "F" - OPERATION & MAINTENANCE PLAN & LOGS

EXHIBIT "G" - ILLICIT DISCHARGE STATEMENT

EXHIBIT "H" - PIPE CAPACITY CALCULATIONS

EXHIBIT "I" - WATERSHED PLANS

STORMWATER MANAGEMENT REPORT AND HYDROLOGIC ANALYSIS

SECTION 1: Project Summary

The project area associated with the proposed development is located on the west side of Orchard Street, between the cross streets of Swift to the north and Cove Road to the south. The site is comprised of one proposed parcel, identified as a portion of Assessors Map 23, Lots 158 & 294. The parcel contains approximately 1.06 acres and is located entirely within the Mixed-Use Business District.

The site is a portion of a large undeveloped piece of land that has been left vacant for many years prior to this project and has been predominantly used as a stockpile area for abutting projects. Going back several decades, this property was used for a large-scale industrial company, and upon the departure of said company, the existing features were all demolished and the grounds were cleared and left roughly graded. Since then, previous owners have prepped the site for possible future development, and now there are several existing utility stubs, an existing drainage system that services nearby properties that lies within a utility easement and access to the site via an existing curb cut along its frontage. The site's frontage lies along the right-of-way known as Orchard Street, and the site is bounded on the south and west by other vacant property left undeveloped. To the north is a recently developed piece of land that now contains the commercial business known as Family Dollar. The surrounding neighborhood includes businesses as well as residential living and can be classified as largely developed urban areas. All the proposed falls outside of any wetland areas or areas subject to flooding, and no protected wildlife habitats or species are known to exist in this area either.

The applicant is seeking permission to construct a 10,000 S.F. commercial building that will house a retail business, as well as site improvements such as parking areas, ingress/egress driveways, and typical utility services and installations. Specifically, the proposed work will close out the existing curb cut on Orchard Street while installing two new ones, the parking areas will contain a total of 50 individual parking spaces and the site will be serviced by new water, sewer and electrical services to be tied into the existing services within Orchard Street. By utilizing the existing stormwater drainage system on site, the underground recharge area can be reduced, and total site runoff has been nearly eliminated.

Finally, all zoning bylaws have been taken into consideration in terms of dimensional regulations and the site is within full compliance of those. Specifically, setbacks to all property lines and lot coverage percentages have been kept under the maximum allowed.

SECTION 2: Methodology

Drainage computations were performed using the Natural Resources Conservation Services (NRCS) TR-20 method and HydroCAD® Drainage Calculation Software to determine the change in the existing and post-development runoff rates from each drainage area for the 2-, 10-, and 100-year 24-hour storm events. Sketches of the existing and proposed watershed

areas, HydroCAD® Report, and copies of the calculation sheets are included as appendices to this report.

SECTION 3: Soil Conditions

The soils underlying the proposed development site are identified in the Natural Resources Conservation Service (NRCS) Soil Survey of Bristol County, Northern Part, and are solely classified as Urban Fill. This site having been used for industrial means in the past, and then demolished, have left the underlying soils in poor condition and not ranked for hydrologic purposes.

Soil testing was performed by a third-party Geotechnical firm to confirm the soil survey and to determine soil suitability for on-site stormwater management purposes. The locations of these test holes are shown on the Site Plans. Seven deep test-holes were performed to depths varying from approximately four to fifteen feet. Groundwater was observed in the deep holes at depths of approximately 9-12 feet. Native coarse sand soils were encountered in a few of the holes, but all test holes were overlain by deep layers of gravelly fill materials. Several of the test holes were refused at varying depths due to ledge and/or bedrock.

SECTION 4: Stormwater Management Overview

Existing Conditions:

One design point was analyzed for this project: Total Off-Site runoff to the surrounding areas mainly to Orchard Street. The subcatchment area that provides the runoff for this design point encompasses the entire property, and is made up of rough graded soils, partial grass cover and large areas of stockpile material from abutting developments.

Proposed Conditions:

Under proposed conditions, two design points were utilized: Off-site Runoff as well as the existing stormwater drainage manhole that discharges to the City drainage system. Four subcatchment areas contribute runoff to the design points in proposed conditions. Runoff toward Orchard Street is described in one sub-catchment area (S-4) and is comprised of grassed/landscape area which sheds untreated runoff toward Orchard Street.

The remaining sub-catchment areas comprise the rest of the site, where runoff is eventually shed toward the southeast corner of the site where the existing drain manhole is located. One sub-catchment area includes the roof runoff which discharge runoff directly to proposed subsurface infiltration chambers. Two sub-catchment areas contribute runoff to two proposed water quality catch basins at either end of the site, and then eventually to the existing drain manhole. The final sub-catchment area, comprised of grassed and landscaped areas, sheds untreated runoff toward the southeast.

The proposed stormwater management practices have been designed in accordance with the DEP Stormwater Handbook to provide appropriate water quality treatment, groundwater recharge, and peak rate attenuation for all storms, including the 100-year storm event.

SECTION 5: Stormwater Management Standards

Standard 1:

 There are no new untreated discharges to any design point from on site to water of the Commonwealth, nor are there any bordering vegetated wetlands that may experience untreated runoff or erosion to the soils. This standard has been met.

Standard 2:

 The stormwater system was designed for the post-development conditions to handle all storms' peak discharges and runoff volume to include the 2, 10, and 100-year storm events.

The results of site drainage calculations are presented in the following Table. The results are based upon evaluation of Pre-development conditions and the design of proposed surface drainage systems for the Post-development condition. These results show the Post-Development offsite runoff rates are reduced to less than the Pre-development conditions, thus meeting the BMP guidelines for this site development. This standard has been met.

Table 1 - Comparison of Pre- versus Post-Development Offsite Runoff							
	Pre-Development Post-Development						
Storm Frequency	Rate (cfs)	Volume (af)	Rate (cfs)	Volume (af)			
2-Year Storm	1.99	0.143	0.07	0.006			
10-Year Storm	3.45	0.247	0.13	0.012			
100-Year Storm	5.84	0.423	0.25	0.021			

Standard 3:

• The site is comprised entirely of soils that are "Unclassified" due to the existence of urban fill throughout the whole site. Soil borings were conducted to reveal a mixture of sand w/ gravel, silty sand w/ gravel and sandy silt w/ gravel below the layers of fill which lead to a determination of mostly C-class soils and is therefore required to meet the recharge requirements of Standard 3 to the maximum extent practicable. The required Recharge Volume has been calculated using the Static Method and calculations are provided in *Exhibit C*. Soil test pit data indicates that the vertical separation from the bottom of the infiltration basins is greater than 2 feet to any indications of seasonal high groundwater. This standard has been met to the maximum extent practical.

Standard 4:

• The proposed stormwater management systems for this project have been designed to remove 80% of the average annual post construction load of Total Suspended Solids in accordance with this standard, as shown in calculations provided in *Exhibit D*. Suitable practices for source control and pollution prevention have been identified in a long-term pollution prevention plan in *Exhibit E*. This standard has been met.

Standard 5:

• The use associated with this project is not classified as a Land Use with Higher Potential Pollutant Load (LUHPPL); therefore, Standard 5 is not applicable to this project. This standard does not apply.

Standard 6:

The site does not discharge within the Zone II or IWPA of a public water supply, nor
does it discharge near or to any critical areas. This standard does not apply.

Standard 7:

 Although a portion of the site may qualify as redevelopment, the project has not been designed as a redevelopment project. This standard does not apply.

Standard 8:

 Where there will be less than one acre of disturbance, an EPA Construction General Permit is not required. However, as a form of better management practices, construction period sedimentation and erosion control plans have been incorporated in the Site Plans. Also, safeguards have been incorporated into the construction period sedimentation and erosion control plans to ensure proper operation and maintenance and to prevent negative impacts to the surrounding sites.

Standard 9:

• A long-term operation and maintenance plan has been prepared to ensure that stormwater management systems function as designed. (Exhibit F)


Standard 10:

 We are not proposing any illicit discharges as defined in the Stormwater Management Regulations. See attached letter in *Exhibit G*



ENGINEERING | SITE WORK | LAND SURVEYING

USGS MAP TOPO! VERSION 2.1.0



HYDROLOGIC CALCULATIONS



Offsite Runoff









19210PRE

Prepared by Farland Corp.

HydroCAD® 10.00-24 s/n 02085 © 2018 HydroCAD Software Solutions LLC

Page 2

Area Listing (all nodes)

Area	CN	Description
(acres)		(subcatchment-numbers)
0.748	79	50-75% Grass cover, Fair, HSG C (S-1)
0.308	86	<50% Grass cover, Poor, HSG C (S-1)
1.056	81	TOTAL AREA

Page 3


Summary for Subcatchment S-1: Offsite Runoff

Runoff = 1.99 cfs @ 12.09 hrs, Volume= 0.143 af, Depth= 1.63"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 2Yr Rainfall=3.40"

_	Α	rea (sf)	CN I	Description		
		32,593	79	50-75% Gra	ass cover, F	Fair, HSG C
		13,410	86 ·	<50% Gras	s cover, Po	oor, HSG C
		46,003	81 \	Neighted A	verage	
	46,003 100.00% Pervious Area			100.00% Pe	ervious Are	a
	Тс	Length	Slope	,	Capacity	Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	3.5	50	0.1600	0.24		Sheet Flow, First 50'
						Grass: Dense n= 0.240 P2= 3.40"
	2.7	185	0.0127	1.13		Shallow Concentrated Flow, Final Run
_						Nearly Bare & Untilled Kv= 10.0 fps
	6.2	235	Total			

Subcatchment S-1: Offsite Runoff



Page 4


Summary for Subcatchment S-1: Offsite Runoff

Runoff = 3.45 cfs @ 12.09 hrs, Volume= 0.247 af, Depth= 2.81"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 10Yr Rainfall=4.80"

_	Α	rea (sf)	CN I	Description		
		32,593	79	50-75% Gra	ass cover, F	Fair, HSG C
_		13,410	86 ·	<50% Gras	s cover, Po	or, HSG C
		46,003	81 [\]	Neighted A	verage	
	46,003 100.00% Pervious Area			100.00% Pe	ervious Are	a
	Tc	Length	Slope	,	Capacity	Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	3.5	50	0.1600	0.24		Sheet Flow, First 50'
						Grass: Dense n= 0.240 P2= 3.40"
	2.7	185	0.0127	1.13		Shallow Concentrated Flow, Final Run
_						Nearly Bare & Untilled Kv= 10.0 fps
	6.2	235	Total			

Subcatchment S-1: Offsite Runoff



Page 5


Summary for Subcatchment S-1: Offsite Runoff


Runoff = 5.84 cfs @ 12.09 hrs, Volume= 0.423 af, Depth= 4.81"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100yr Rainfall=7.00"

_	Α	rea (sf)	CN I	Description		
		32,593	79	50-75% Gra	ass cover, F	Fair, HSG C
		13,410	86 ·	<50% Gras	s cover, Po	oor, HSG C
		46,003	81 \	Neighted A	verage	
	46,003 100.00% Pervious Area			100.00% Pe	ervious Are	a
	Тс	Length	Slope	,	Capacity	Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	3.5	50	0.1600	0.24		Sheet Flow, First 50'
						Grass: Dense n= 0.240 P2= 3.40"
	2.7	185	0.0127	1.13		Shallow Concentrated Flow, Final Run
_						Nearly Bare & Untilled Kv= 10.0 fps
	6.2	235	Total			

Subcatchment S-1: Offsite Runoff





Prepared by Farland Corp.

HydroCAD® 10.00-24 s/n 02085 © 2018 HydroCAD Software Solutions LLC

Page 2

Area Listing (all nodes)

Area	CN	Description
(acres)		(subcatchment-numbers)
0.121	74	>75% Grass cover, Good, HSG C (S-1, S-2, S-4)
0.704	98	Paved parking, HSG C (S-1, S-2)
0.230	98	Rooftop (S-3)
1.054	95	TOTAL AREA

Page 3


Summary for Subcatchment S-1: Tributary to WQI-1

Runoff = 1.20 cfs @ 12.08 hrs, Volume= 0.093 af, Depth= 3.06"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 2Yr Rainfall=3.40"

A	rea (sf)	CN	Description					
	15,329	98	Paved park	ing, HSG C				
	640	74	>75% Gras	>75% Grass cover, Good, HSG C				
	15,969	97	Weighted A	verage				
	640		4.01% Perv	ious Area				
	15,329		95.99% Imp	ervious Are	ea			
_								
Tc	Length	Slope	,	Capacity	Description			
(min)	(feet)	(ft/ft) (ft/sec)	(cfs)				
6.0					Direct Entry, Minimum Tc			

Subcatchment S-1: Tributary to WQI-1



Page 4


Summary for Subcatchment S-2: Tributary to WQI-2

Runoff = 1.24 cfs @ 12.08 hrs, Volume= 0.094 af, Depth= 2.84"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 2Yr Rainfall=3.40"

A	rea (sf)	CN	Description					
	1,892	74	>75% Grass	s cover, Go	ood, HSG C			
	15,317	98	Paved park	Paved parking, HSG C				
	17,209	95	Weighted A	verage				
	1,892		10.99% Per	vious Area				
	15,317		89.01% Imp	ervious Are	ea			
т.	1 41-	Ola II		0	Description			
Tc	Length	Slope	,	Capacity	Description			
(min)	(feet)	(ft/ft) (ft/sec)	(cfs)				
6.0					Direct Entry, Minimum Tc			

Subcatchment S-2: Tributary to WQI-2



Page 5


Summary for Subcatchment S-3: Rooftop Runoff

Runoff = 0.76 cfs @ 12.08 hrs, Volume= 0.061 af, Depth= 3.17"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 2Yr Rainfall=3.40"

	Α	rea (sf)	CN	Description		
*		10,000	98	Rooftop		
		10,000	100.00% Impervious A			rea
	Тс	Length	Slope	Velocity	Capacity	Description
	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	6.0					Direct Entry, Minimum Tc

Subcatchment S-3: Rooftop Runoff



Page 6


Summary for Subcatchment S-4: Offsite Runoff

Runoff = 0.07 cfs @ 12.17 hrs, Volume= 0.006 af, Depth= 1.17"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 2Yr Rainfall=3.40"

_	Α	rea (sf)	CN E	Description			
		2,740	74 >	75% Gras	s cover, Go	ood, HSG C	
		2,740	1	00.00% Pe	ervious Are	a	
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
-	5.5	50	0.0200	0.15	, ,	Sheet Flow, Grass: Short n= 0.150 P2= 3.40"	
	6.2	370	0.0200	0.99		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps	
	11.7	420	Total			•	

Subcatchment S-4: Offsite Runoff



Page 7

Summary for Reach P-1: 12" HDPE

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.230 ac,100.00% Impervious, Inflow Depth = 3.17" for 2Yr event

Inflow = 0.76 cfs @ 12.08 hrs, Volume= 0.061 af


Outflow = 0.76 cfs @ 12.08 hrs, Volume= 0.061 af, Atten= 0%, Lag= 0.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs


Max. Velocity= 8.03 fps, Min. Travel Time= 0.0 min Avg. Velocity = 2.62 fps, Avg. Travel Time= 0.1 min

Peak Storage= 2 cf @ 12.08 hrs Average Depth at Peak Storage= 0.18' Bank-Full Depth= 1.00' Flow Area= 0.8 sf, Capacity= 11.00 cfs

12.0" Round Pipe n= 0.013 Corrugated PE, smooth interior Length= 21.0' Slope= 0.0952 '/' Inlet Invert= 7.00', Outlet Invert= 5.00'



Reach P-1: 12" HDPE



Prepared by Farland Corp.

HydroCAD® 10.00-24 s/n 02085 © 2018 HydroCAD Software Solutions LLC

Page 8

Summary for Reach P-2: 12" HDPE

[52] Hint: Inlet/Outlet conditions not evaluated

[81] Warning: Exceeded Pond SRS-1 by 0.02' @ 25.27 hrs

Inflow Area = 0.230 ac,100.00% Impervious, Inflow Depth = 1.01" for 2Yr event

Inflow = 0.14 cfs @ 12.52 hrs, Volume= 0.019 af


Outflow = 0.14 cfs @ 12.53 hrs, Volume= 0.019 af, Atten= 0%, Lag= 0.5 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Max. Velocity= 3.25 fps, Min. Travel Time= 0.3 min Avg. Velocity = 1.58 fps, Avg. Travel Time= 0.5 min


Peak Storage= 2 cf @ 12.52 hrs Average Depth at Peak Storage= 0.10' Bank-Full Depth= 1.00' Flow Area= 0.8 sf, Capacity= 6.25 cfs

12.0" Round Pipe n= 0.013 Corrugated PE, smooth interior Length= 51.0' Slope= 0.0308 '/' Inlet Invert= 7.46', Outlet Invert= 5.89'



Page 9

Reach P-2: 12" HDPE



Prepared by Farland Corp.

HydroCAD® 10.00-24 s/n 02085 © 2018 HydroCAD Software Solutions LLC

Page 10

Inflow

Outflow

Summary for Reach P-3: 18" HDPE

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.991 ac, 94.14% Impervious, Inflow Depth = 2.50" for 2Yr event

Inflow = 2.37 cfs @ 12.10 hrs, Volume= 0.206 af


Outflow = 2.37 cfs @ 12.10 hrs, Volume= 0.206 af, Atten= 0%, Lag= 0.2 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs


Max. Velocity= 3.74 fps, Min. Travel Time= 0.1 min Avg. Velocity = 1.24 fps, Avg. Travel Time= 0.3 min

Peak Storage= 15 cf @ 12.10 hrs Average Depth at Peak Storage= 0.58' Bank-Full Depth= 1.50' Flow Area= 1.8 sf, Capacity= 7.43 cfs

18.0" Round Pipe n= 0.013 Length= 24.0' Slope= 0.0050 '/' Inlet Invert= 5.89', Outlet Invert= 5.77'



Reach P-3: 18" HDPE



Prepared by Farland Corp.

HydroCAD® 10.00-24 s/n 02085 © 2018 HydroCAD Software Solutions LLC

Page 11

Summary for Reach WQI-1: Water Quality Inlet

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.367 ac, 95.99% Impervious, Inflow Depth = 3.06" for 2Yr event

Inflow = 1.20 cfs @ 12.08 hrs, Volume= 0.093 af


Outflow = 1.19 cfs @ 12.09 hrs, Volume= 0.093 af, Atten= 0%, Lag= 0.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs


Max. Velocity= 6.04 fps, Min. Travel Time= 0.1 min Avg. Velocity = 1.97 fps, Avg. Travel Time= 0.2 min

Peak Storage= 4 cf @ 12.08 hrs Average Depth at Peak Storage= 0.30' Bank-Full Depth= 1.00' Flow Area= 0.8 sf, Capacity= 6.12 cfs

12.0" Round Pipe n= 0.013 Corrugated PE, smooth interior Length= 19.0' Slope= 0.0295 '/' Inlet Invert= 6.45', Outlet Invert= 5.89'



Reach WQI-1: Water Quality Inlet



Prepared by Farland Corp.

HydroCAD® 10.00-24 s/n 02085 © 2018 HydroCAD Software Solutions LLC

Page 12

Inflow

Summary for Reach WQI-2: Water Quality Inlet

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.395 ac, 89.01% Impervious, Inflow Depth = 2.84" for 2Yr event

1.24 cfs @ 12.08 hrs, Volume= Inflow 0.094 af


1.22 cfs @ 12.12 hrs, Volume= Outflow 0.094 af, Atten= 1%, Lag= 1.9 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs


Max. Velocity= 3.11 fps, Min. Travel Time= 1.1 min Avg. Velocity = 1.00 fps, Avg. Travel Time= 3.4 min

Peak Storage= 81 cf @ 12.10 hrs Average Depth at Peak Storage= 0.41' Bank-Full Depth= 1.50' Flow Area= 1.8 sf, Capacity= 7.43 cfs

18.0" Round Pipe n= 0.013 Corrugated PE, smooth interior Length= 206.0' Slope= 0.0050 '/' Inlet Invert= 6.92', Outlet Invert= 5.89'



Reach WQI-2: Water Quality Inlet



Page 13

Summary for Pond DMH-1: Drain Manhole

[40] Hint: Not Described (Outflow=Inflow)


Inflow Area = 0.991 ac, 94.14% Impervious, Inflow Depth = 2.50" for 2Yr event

Inflow = 2.37 cfs @ 12.10 hrs, Volume= 0.206 af

Primary = 2.37 cfs @ 12.10 hrs, Volume= 0.206 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Pond DMH-1: Drain Manhole



Page 14

Summary for Pond DMH-2: Existing Drain Manhole

[40] Hint: Not Described (Outflow=Inflow)


Inflow Area = 0.991 ac, 94.14% Impervious, Inflow Depth = 2.50" for 2Yr event

Inflow = 2.37 cfs @ 12.10 hrs, Volume= 0.206 af

Primary = 2.37 cfs @ 12.10 hrs, Volume= 0.206 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Pond DMH-2: Existing Drain Manhole



Page 15

Summary for Pond SRS-1: Subsurface Recharge System

[63] Warning: Exceeded Reach P-1 INLET depth by 0.59' @ 12.56 hrs

Inflow Area = 0.230 ac,100.00% Impervious, Inflow Depth = 3.17" for 2Yr event

Inflow = 0.76 cfs @ 12.08 hrs, Volume= 0.061 af

Outflow = 0.14 cfs @ 12.52 hrs, Volume= 0.044 af, Atten= 81%, Lag= 26.3 min

Discarded = 0.14 cfs @ 12.52 hrs, Volume= 0.014 af

Primary = 0.14 cfs @ 12.52 hrs, Volume= 0.019 af

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Peak Elev= 7.66' @ 12.52 hrs Surf.Area= 684 sf Storage= 1,559 cf

Plug-Flow detention time= 991.1 min calculated for 0.044 af (72% of inflow) Center-of-Mass det. time= 900.6 min (1,655.9 - 755.3)

Invert	Avail.Storage	Storage Description
4.25'	1,046 cf	16.68'W x 41.00'L x 5.75'H Prismatoid
		3,932 cf Overall - 1,317 cf Embedded = 2,616 cf x 40.0% Voids
5.00'	1,317 cf	Cultec R-902HD x 20 Inside #1
		Effective Size= 69.8"W x 48.0"H => 17.65 sf x 3.67'L = 64.7 cf
		Overall Size= 78.0"W x 48.0"H x 4.10'L with 0.44' Overlap
		20 Chambers in 4 Rows
		Cap Storage= +2.8 cf x 2 x 4 rows = 22.1 cf
	2,363 cf	Total Available Storage
	4.25'	4.25' 1,046 cf 5.00' 1,317 cf


Device	Routing	Invert	Outlet Devices
#1	Discarded	4.25'	0.270 in/hr Exfiltration over Surface area
#2	Primary	7.46'	12.0" Round Culvert
			L= 51.0' CPP, projecting, no headwall, Ke= 0.900
			Inlet / Outlet Invert= 7.46' / 5.89' S= 0.0308 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf

Discarded OutFlow Max=0.00 cfs @ 4.32 hrs HW=4.31' (Free Discharge) **1=Exfiltration** (Exfiltration Controls 0.00 cfs)

Primary OutFlow Max=0.14 cfs @ 12.52 hrs HW=7.66' (Free Discharge) 2=Culvert (Inlet Controls 0.14 cfs @ 1.21 fps)

Page 16

Pond SRS-1: Subsurface Recharge System



Page 17


Summary for Subcatchment S-1: Tributary to WQI-1

Runoff = 1.71 cfs @ 12.08 hrs, Volume= 0.136 af, Depth= 4.45"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 10Yr Rainfall=4.80"

	rea (sf)	CN	Description				
	15,329	98	Paved park	aved parking, HSG C			
	640	74	>75% Gras	s cover, Go	ood, HSG C		
	15,969	97	Weighted A	verage			
	640 4.01% Pervious Area						
	15,329		95.99% Imp	5.99% Impervious Area			
Τ.	1 41.	01		0	December 1999		
Тс	9	Slope	,	Capacity	Description		
<u>(min)</u>	(feet)	(ft/ft) (ft/sec)	(cfs)			
6.0					Direct Entry, Minimum Tc		

Subcatchment S-1: Tributary to WQI-1



Page 18


Summary for Subcatchment S-2: Tributary to WQI-2

Runoff = 1.80 cfs @ 12.08 hrs, Volume= 0.139 af, Depth= 4.22"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 10Yr Rainfall=4.80"

	Area (sf)	CN	Description				
	1,892	74	>75% Gras	75% Grass cover, Good, HSG C			
	15,317	98	Paved park	aved parking, HSG C			
	17,209	95	Weighted A	verage			
	1,892		10.99% Pervious Area				
	15,317		89.01% Imp	9.01% Impervious Area			
_		-			—		
T	9	Slope	,	Capacity	Description		
(min) (feet)	(ft/ft) (ft/sec)	(cfs)			
6.0	0				Direct Entry, Minimum Tc		

Subcatchment S-2: Tributary to WQI-2



Page 19


Summary for Subcatchment S-3: Rooftop Runoff

Runoff = 1.08 cfs @ 12.08 hrs, Volume= 0.087 af, Depth= 4.56"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 10Yr Rainfall=4.80"

_	Α	rea (sf)	CN	Description		
*		10,000	98	Rooftop		
_		10,000		100.00% Im	npervious A	rea
	Тс	Length		Velocity		Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	6.0					Direct Entry, Minimum Tc

Subcatchment S-3: Rooftop Runoff



Page 20


Summary for Subcatchment S-4: Offsite Runoff

Runoff = 0.13 cfs @ 12.16 hrs, Volume= 0.012 af, Depth= 2.21"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 10Yr Rainfall=4.80"

_	Α	rea (sf)	CN E	Description						
		2,740	74 >	74 >75% Grass cover, Good, HSG C						
		2,740	1	100.00% Pervious Area						
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description				
-	5.5	50	0.0200	0.15	, ,	Sheet Flow, Grass: Short n= 0.150 P2= 3.40"				
	6.2	370	0.0200	0.99		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps				
	11.7	420	Total							

Subcatchment S-4: Offsite Runoff



Page 21

Inflow

Outflow

Summary for Reach P-1: 12" HDPE

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.230 ac,100.00% Impervious, Inflow Depth = 4.56" for 10Yr event

Inflow = 1.08 cfs @ 12.08 hrs, Volume= 0.087 af


Outflow = 1.08 cfs @ 12.08 hrs, Volume= 0.087 af, Atten= 0%, Lag= 0.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs


Max. Velocity= 8.90 fps, Min. Travel Time= 0.0 min Avg. Velocity = 2.92 fps, Avg. Travel Time= 0.1 min

Peak Storage= 3 cf @ 12.08 hrs Average Depth at Peak Storage= 0.21' Bank-Full Depth= 1.00' Flow Area= 0.8 sf, Capacity= 11.00 cfs

12.0" Round Pipe n= 0.013 Corrugated PE, smooth interior Length= 21.0' Slope= 0.0952 '/' Inlet Invert= 7.00', Outlet Invert= 5.00'



Reach P-1: 12" HDPE



Prepared by Farland Corp.

HydroCAD® 10.00-24 s/n 02085 © 2018 HydroCAD Software Solutions LLC

Page 22

Summary for Reach P-2: 12" HDPE

[52] Hint: Inlet/Outlet conditions not evaluated

[81] Warning: Exceeded Pond SRS-1 by 0.02' @ 25.49 hrs

Inflow Area = 0.230 ac,100.00% Impervious, Inflow Depth = 2.39" for 10Yr event

Inflow = 0.77 cfs @ 12.16 hrs, Volume= 0.046 af


Outflow = 0.77 cfs @ 12.16 hrs, Volume= 0.046 af, Atten= 0%, Lag= 0.3 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Max. Velocity= 5.41 fps, Min. Travel Time= 0.2 min Avg. Velocity = 1.88 fps, Avg. Travel Time= 0.5 min


Peak Storage= 7 cf @ 12.16 hrs Average Depth at Peak Storage= 0.24' Bank-Full Depth= 1.00' Flow Area= 0.8 sf, Capacity= 6.25 cfs

12.0" Round Pipe n= 0.013 Corrugated PE, smooth interior Length= 51.0' Slope= 0.0308 '/' Inlet Invert= 7.46', Outlet Invert= 5.89'



Page 23

Reach P-2: 12" HDPE



Page 24

Inflow

Outflow

Summary for Reach P-3: 18" HDPE

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.991 ac, 94.14% Impervious, Inflow Depth = 3.88" for 10Yr event

Inflow = 3.95 cfs @ 12.12 hrs, Volume= 0.321 af


Outflow = 3.95 cfs @ 12.12 hrs, Volume= 0.321 af, Atten= 0%, Lag= 0.2 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs


Max. Velocity= 4.27 fps, Min. Travel Time= 0.1 min Avg. Velocity = 1.39 fps, Avg. Travel Time= 0.3 min

Peak Storage= 22 cf @ 12.12 hrs Average Depth at Peak Storage= 0.78' Bank-Full Depth= 1.50' Flow Area= 1.8 sf, Capacity= 7.43 cfs

18.0" Round Pipe n= 0.013 Length= 24.0' Slope= 0.0050 '/' Inlet Invert= 5.89', Outlet Invert= 5.77'



Reach P-3: 18" HDPE



Page 25

Summary for Reach WQI-1: Water Quality Inlet

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.367 ac, 95.99% Impervious, Inflow Depth = 4.45" for 10Yr event

Inflow = 1.71 cfs @ 12.08 hrs, Volume= 0.136 af


Outflow = 1.71 cfs @ 12.08 hrs, Volume= 0.136 af, Atten= 0%, Lag= 0.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs


Max. Velocity= 6.67 fps, Min. Travel Time= 0.0 min Avg. Velocity = 2.20 fps, Avg. Travel Time= 0.1 min

Peak Storage= 5 cf @ 12.08 hrs Average Depth at Peak Storage= 0.36' Bank-Full Depth= 1.00' Flow Area= 0.8 sf, Capacity= 6.12 cfs

12.0" Round Pipe n= 0.013 Corrugated PE, smooth interior Length= 19.0' Slope= 0.0295 '/' Inlet Invert= 6.45', Outlet Invert= 5.89'



Reach WQI-1: Water Quality Inlet



Page 26

Inflow

Summary for Reach WQI-2: Water Quality Inlet

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.395 ac, 89.01% Impervious, Inflow Depth = 4.22" for 10Yr event

1.80 cfs @ 12.08 hrs, Volume= Inflow 0.139 af


Outflow 1.78 cfs @ 12.11 hrs, Volume= 0.139 af, Atten= 1%, Lag= 1.7 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs


Max. Velocity= 3.45 fps, Min. Travel Time= 1.0 min Avg. Velocity = 1.12 fps, Avg. Travel Time= 3.1 min

Peak Storage= 106 cf @ 12.10 hrs Average Depth at Peak Storage= 0.50' Bank-Full Depth= 1.50' Flow Area= 1.8 sf, Capacity= 7.43 cfs

18.0" Round Pipe n= 0.013 Corrugated PE, smooth interior Length= 206.0' Slope= 0.0050 '/' Inlet Invert= 6.92', Outlet Invert= 5.89'



Reach WQI-2: Water Quality Inlet



Page 27

Summary for Pond DMH-1: Drain Manhole

[40] Hint: Not Described (Outflow=Inflow)


Inflow Area = 0.991 ac, 94.14% Impervious, Inflow Depth = 3.88" for 10Yr event

Inflow = 3.95 cfs @ 12.12 hrs, Volume= 0.321 af

Primary = 3.95 cfs @ 12.12 hrs, Volume= 0.321 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Pond DMH-1: Drain Manhole



Page 28

Summary for Pond DMH-2: Existing Drain Manhole

[40] Hint: Not Described (Outflow=Inflow)


Inflow Area = 0.991 ac, 94.14% Impervious, Inflow Depth = 3.88" for 10Yr event

Inflow = 3.95 cfs @ 12.12 hrs, Volume= 0.321 af

Primary = 3.95 cfs @ 12.12 hrs, Volume= 0.321 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Pond DMH-2: Existing Drain Manhole



Page 29

Summary for Pond SRS-1: Subsurface Recharge System

[63] Warning: Exceeded Reach P-1 INLET depth by 0.79' @ 12.18 hrs

Inflow Area = 0.230 ac,100.00% Impervious, Inflow Depth = 4.56" for 10Yr event

Inflow = 1.08 cfs @ 12.08 hrs, Volume= 0.087 af

Outflow = 0.78 cfs @ 12.16 hrs, Volume= 0.070 af, Atten= 28%, Lag= 4.5 min

Discarded = 0.77 cfs @ 3.04 hrs, Volume= 0.025 af

Primary = 0.77 cfs @ 12.16 hrs, Volume= 0.046 af

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Peak Elev= 7.97' @ 12.16 hrs Surf.Area= 684 sf Storage= 1,700 cf

Plug-Flow detention time= 658.6 min calculated for 0.070 af (81% of inflow) Center-of-Mass det. time= 582.7 min (1,331.5 - 748.8)

Volume	Invert	Avail.Storage	Storage Description
#1	4.25'	1,046 cf	16.68'W x 41.00'L x 5.75'H Prismatoid
			3,932 cf Overall - 1,317 cf Embedded = 2,616 cf x 40.0% Voids
#2	5.00'	1,317 cf	Cultec R-902HD x 20 Inside #1
			Effective Size= 69.8"W x 48.0"H => 17.65 sf x 3.67'L = 64.7 cf
			Overall Size= 78.0"W x 48.0"H x 4.10'L with 0.44' Overlap
			20 Chambers in 4 Rows
			Cap Storage= +2.8 cf x 2 x 4 rows = 22.1 cf
		2,363 cf	Total Available Storage


Device	Routing	Invert	Outlet Devices
#1	Discarded	4.25'	0.270 in/hr Exfiltration over Surface area
#2	Primary	7.46'	12.0" Round Culvert
			L= 51.0' CPP, projecting, no headwall, Ke= 0.900
			Inlet / Outlet Invert= 7.46' / 5.89' S= 0.0308 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf

Discarded OutFlow Max=0.00 cfs @ 3.04 hrs HW=4.31' (Free Discharge) **1=Exfiltration** (Exfiltration Controls 0.00 cfs)

Primary OutFlow Max=0.77 cfs @ 12.16 hrs HW=7.97' (Free Discharge) 2=Culvert (Inlet Controls 0.77 cfs @ 1.92 fps)

Page 30

Pond SRS-1: Subsurface Recharge System



Page 31


Summary for Subcatchment S-1: Tributary to WQI-1

Runoff = 2.51 cfs @ 12.08 hrs, Volume= 0.203 af, Depth= 6.64"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100yr Rainfall=7.00"

A	rea (sf)	CN	Description									
	15,329	98	Paved park	aved parking, HSG C								
	640	74	>75% Gras	75% Grass cover, Good, HSG C								
	15,969	97	Weighted A	eighted Average								
	640		4.01% Perv	01% Pervious Area								
	15,329		95.99% Imp	ervious Are	ea							
_												
Tc	Length	Slope	,	Capacity	Description							
(min)	(feet)	(ft/ft) (ft/sec)	(ft/sec) (cfs)								
6.0					Direct Entry, Minimum Tc							

Subcatchment S-1: Tributary to WQI-1



Page 32


Summary for Subcatchment S-2: Tributary to WQI-2

Runoff = 2.67 cfs @ 12.08 hrs, Volume= 0.211 af, Depth= 6.41"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100yr Rainfall=7.00"

	Area (sf)	CN	Description	Description								
	1,892	74	>75% Gras	75% Grass cover, Good, HSG C								
	15,317	98	Paved park	aved parking, HSG C								
	17,209	95	Weighted A	eighted Average								
	1,892		10.99% Per	0.99% Pervious Area								
	15,317		89.01% lmp	ervious Are	ea							
Tc	Length	Slope	Velocity	Capacity	Description							
(min)	(feet)	(ft/ft	,									
	(icci)	(IVIL	(11/360)									
6.0					Direct Entry, Minimum Tc							

Subcatchment S-2: Tributary to WQI-2



Page 33


Summary for Subcatchment S-3: Rooftop Runoff

Runoff = 1.58 cfs @ 12.08 hrs, Volume= 0.129 af, Depth= 6.76"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100yr Rainfall=7.00"

_	Α	rea (sf)	CN	Description		
*		10,000	98	Rooftop		
_		10,000		100.00% Im	npervious A	rea
	Тс	Length		Velocity		Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	6.0					Direct Entry, Minimum Tc

Subcatchment S-3: Rooftop Runoff



Page 34


Summary for Subcatchment S-4: Offsite Runoff

Runoff = 0.25 cfs @ 12.16 hrs, Volume= 0.021 af, Depth= 4.04"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100yr Rainfall=7.00"

_	Α	rea (sf)	CN E	escription						
		2,740	74 >	75% Grass	s cover, Go	od, HSG C				
		2,740	1	00.00% Pe	ervious Are	a				
	Tc Length Slope Velocity Capacity Description (min) (feet) (ft/ft) (ft/sec) (cfs)									
_	5.5	50	0.0200	0.15	, ,	Sheet Flow,				
_	6.2	370	0.0200	0.99		Grass: Short n= 0.150 P2= 3.40" Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps				
	11.7	420	Total							

Subcatchment S-4: Offsite Runoff



Page 35

Inflow

Summary for Reach P-1: 12" HDPE

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.230 ac,100.00% Impervious, Inflow Depth = 6.76" for 100yr event

Inflow 1.58 cfs @ 12.08 hrs, Volume= 0.129 af


Outflow 1.58 cfs @ 12.08 hrs, Volume= 0.129 af, Atten= 0%, Lag= 0.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs


Max. Velocity= 9.94 fps, Min. Travel Time= 0.0 min Avg. Velocity = 3.28 fps, Avg. Travel Time= 0.1 min

Peak Storage= 3 cf @ 12.08 hrs Average Depth at Peak Storage= 0.26' Bank-Full Depth= 1.00' Flow Area= 0.8 sf, Capacity= 11.00 cfs

12.0" Round Pipe n= 0.013 Corrugated PE, smooth interior Length= 21.0' Slope= 0.0952 '/' Inlet Invert= 7.00', Outlet Invert= 5.00'



Reach P-1: 12" HDPE



19210POST

Prepared by Farland Corp.

HydroCAD® 10.00-24 s/n 02085 © 2018 HydroCAD Software Solutions LLC

Page 36

Summary for Reach P-2: 12" HDPE

[52] Hint: Inlet/Outlet conditions not evaluated

[81] Warning: Exceeded Pond SRS-1 by 0.02' @ 25.63 hrs

Inflow Area = 0.230 ac,100.00% Impervious, Inflow Depth = 4.57" for 100yr event

Inflow = 1.45 cfs @ 12.12 hrs, Volume= 0.087 af

Outflow = 1.44 cfs @ 12.12 hrs, Volume= 0.087 af, Atten= 0%, Lag= 0.2 min


Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Max. Velocity= 6.47 fps, Min. Travel Time= 0.1 min Avg. Velocity = 2.19 fps, Avg. Travel Time= 0.4 min

Peak Storage= 11 cf @ 12.12 hrs Average Depth at Peak Storage= 0.33'


Bank-Full Depth= 1.00' Flow Area= 0.8 sf, Capacity= 6.25 cfs

12.0" Round Pipe n= 0.013 Corrugated PE, smooth interior Length= 51.0' Slope= 0.0308 '/' Inlet Invert= 7.46', Outlet Invert= 5.89'



Page 37

Reach P-2: 12" HDPE



Page 38

Inflow

Outflow

Summary for Reach P-3: 18" HDPE

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.991 ac, 94.14% Impervious, Inflow Depth = 6.07" for 100yr event

Inflow = 6.49 cfs @ 12.10 hrs, Volume= 0.501 af


Outflow = 6.49 cfs @ 12.10 hrs, Volume= 0.501 af, Atten= 0%, Lag= 0.2 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs


Max. Velocity= 4.74 fps, Min. Travel Time= 0.1 min Avg. Velocity = 1.58 fps, Avg. Travel Time= 0.3 min

Peak Storage= 33 cf @ 12.10 hrs Average Depth at Peak Storage= 1.09' Bank-Full Depth= 1.50' Flow Area= 1.8 sf, Capacity= 7.43 cfs

18.0" Round Pipe n= 0.013 Length= 24.0' Slope= 0.0050 '/' Inlet Invert= 5.89', Outlet Invert= 5.77'



Reach P-3: 18" HDPE



Page 39

Inflow

Outflow

Summary for Reach WQI-1: Water Quality Inlet

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.367 ac, 95.99% Impervious, Inflow Depth = 6.64" for 100yr event

Inflow = 2.51 cfs @ 12.08 hrs, Volume= 0.203 af


Outflow = 2.51 cfs @ 12.08 hrs, Volume= 0.203 af, Atten= 0%, Lag= 0.1 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs


Max. Velocity= 7.40 fps, Min. Travel Time= 0.0 min Avg. Velocity = 2.48 fps, Avg. Travel Time= 0.1 min

Peak Storage= 6 cf @ 12.08 hrs Average Depth at Peak Storage= 0.45' Bank-Full Depth= 1.00' Flow Area= 0.8 sf, Capacity= 6.12 cfs

12.0" Round Pipe n= 0.013 Corrugated PE, smooth interior Length= 19.0' Slope= 0.0295 '/' Inlet Invert= 6.45', Outlet Invert= 5.89'



Reach WQI-1: Water Quality Inlet



Page 40

Inflow

Outflow

Summary for Reach WQI-2: Water Quality Inlet

[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 0.395 ac, 89.01% Impervious, Inflow Depth = 6.41" for 100yr event

Inflow = 2.67 cfs @ 12.08 hrs, Volume= 0.211 af


Outflow = 2.64 cfs @ 12.11 hrs, Volume= 0.211 af, Atten= 1%, Lag= 1.6 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs


Max. Velocity= 3.85 fps, Min. Travel Time= 0.9 min Avg. Velocity = 1.26 fps, Avg. Travel Time= 2.7 min

Peak Storage= 142 cf @ 12.09 hrs Average Depth at Peak Storage= 0.62' Bank-Full Depth= 1.50' Flow Area= 1.8 sf, Capacity= 7.43 cfs

18.0" Round Pipe n= 0.013 Corrugated PE, smooth interior Length= 206.0' Slope= 0.0050 '/' Inlet Invert= 6.92', Outlet Invert= 5.89'



Reach WQI-2: Water Quality Inlet



Page 41

Summary for Pond DMH-1: Drain Manhole

[40] Hint: Not Described (Outflow=Inflow)


Inflow Area = 0.991 ac, 94.14% Impervious, Inflow Depth = 6.07" for 100yr event

Inflow = 6.49 cfs @ 12.10 hrs, Volume= 0.501 af

Primary = 6.49 cfs @ 12.10 hrs, Volume= 0.501 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Pond DMH-1: Drain Manhole



Page 42

Summary for Pond DMH-2: Existing Drain Manhole

[40] Hint: Not Described (Outflow=Inflow)


Inflow Area = 0.991 ac, 94.14% Impervious, Inflow Depth = 6.07" for 100yr event

Inflow = 6.49 cfs @ 12.10 hrs, Volume= 0.501 af

Primary = 6.49 cfs @ 12.10 hrs, Volume= 0.501 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Pond DMH-2: Existing Drain Manhole



Page 43

Summary for Pond SRS-1: Subsurface Recharge System

[63] Warning: Exceeded Reach P-1 INLET depth by 0.96' @ 12.13 hrs

Inflow Area = 0.230 ac,100.00% Impervious, Inflow Depth = 6.76" for 100yr event
Inflow = 1.58 cfs @ 12.08 hrs, Volume= 0.129 af

Outflow = 1.45 cfs @ 12.12 hrs, Volume= 0.112 af, Atten= 8%, Lag= 2.1 min
Discarded = 0.00 cfs @ 2.00 hrs, Volume= 0.025 af

Primary = 1.45 cfs @ 12.12 hrs, Volume= 0.087 af

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Peak Elev= 8.20' @ 12.12 hrs Surf.Area= 684 sf Storage= 1,801 cf

Plug-Flow detention time= 448.0 min calculated for 0.112 af (87% of inflow) Center-of-Mass det. time= 387.9 min (1,131.0 - 743.1)

Volume	Invert	Avail.Storage	Storage Description
#1	4.25'	1,046 cf	16.68'W x 41.00'L x 5.75'H Prismatoid
			3,932 cf Overall - 1,317 cf Embedded = 2,616 cf x 40.0% Voids
#2	5.00'	1,317 cf	Cultec R-902HD x 20 Inside #1
			Effective Size= 69.8"W x 48.0"H => 17.65 sf x 3.67'L = 64.7 cf
			Overall Size= 78.0"W x 48.0"H x 4.10'L with 0.44' Overlap
			20 Chambers in 4 Rows
			Cap Storage= +2.8 cf x 2 x 4 rows = 22.1 cf
·		2,363 cf	Total Available Storage

Device Routing Invert Outlet Devices

#1 Discarded #2 Primary 7.46' 12.0" Round Culvert
L= 51.0' CPP, projecting, no headwall, Ke= 0.900


Inlet / Outlet Invert= 7.46' / 5.89' S= 0.0308 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf

Discarded OutFlow Max=0.00 cfs @ 2.00 hrs HW=4.31' (Free Discharge) **1=Exfiltration** (Exfiltration Controls 0.00 cfs)

Primary OutFlow Max=1.44 cfs @ 12.12 hrs HW=8.20' (Free Discharge) —2=Culvert (Inlet Controls 1.44 cfs @ 2.31 fps)

Page 44

Pond SRS-1: Subsurface Recharge System



RECHARGE CALCULATIONS



ENGINEERING | SITE WORK | LAND SURVEYING

STANDARD 3: RECHARGE CALCULATIONS

REQUIRED:

Recharge Volume Required ("C" Soils) = [Impervious Area x (Recharge Depth

inches/12)]

= $[39,890 \text{ sf x } (0.25^{\circ}/12)]$ = 831 cf (Required Volume)

Total Required Recharge Volume = 831 cf

STATIC METHOD:

 Assume the entire Required Recharge Volume is discharged into the infiltration device before infiltration begins.

PROVIDED:

Subsurface Infiltration System #1:

• Cumulative Volume below the lowest outlet (Elev.=7.46) = 1,317 c.f.

Total = $\frac{1,317 \text{ c.f.}}{1,317 \text{ c.f.}}$

Recharge Volume Provided >>> Recharge Volume Required 1,317 c.f. >>> 831 c.f.

TSS REMOVAL CALCULATIONS

INSTRUCTIONS:

Version 1, Automated: Mar. 4, 2008

- 1. In BMP Column, click on Blue Cell to Activate Drop Down Menu
- 2. Select BMP from Drop Down Menu
- 3. After BMP is selected, TSS Removal and other Columns are automatically completed.

Location: Lisciotti Development - Orchard Street

	В	C TSS Removal	D Starting TSS	E	F
	BMP ¹	Rate ¹	Starting TSS Load*	Amount Removed (C*D)	Remaining Load (D-E)
neet	Street Sweeping - 10%	0.10	1.00	0.10	0.90
Removal on Worksheet	Subsurface Infiltration Structure	0.80	0.90	0.72	0.18
Rem on W		0.00	0.18	0.00	0.18
TSS ReCalculation		0.00	0.18	0.00	0.18
Calc		0.00	0.18	0.00	0.18
					Separate Form Needs to

Total TSS Removal =

82%

Outlet or BMP Train

Project: 19-210

Prepared By: Christian A. Farland, P.E.

Date: 6/5/2019

*Equals remaining load from previous BMP (E) which enters the BMP

Non-automated TSS Calculation Sheet must be used if Proprietary BMP Proposed 1. From MassDEP Stormwater Handbook Vol. 1

INSTRUCTIONS:

Version 1, Automated: Mar. 4, 2008

1. In BMP Column, click on Blue Cell to Activate Drop Down Menu

Project: 19-210

Date: 6/5/2019

- 2. Select BMP from Drop Down Menu
- 3. After BMP is selected, TSS Removal and other Columns are automatically completed.

Location: Lisciotti Development - Orchard Street

	В	С	D	E	F
		TSS Removal	Starting TSS	Amount	Remaining
	BMP ¹	Rate ¹	Load*	Removed (C*D)	Load (D-E)
¥					
Jee	Street Sweeping - 10%	0.10	1.00	0.10	0.90
Removal on Worksheet					
<u> </u>	Oil Grit Separator	0.25	0.90	0.23	0.68
E >					
R on		0.00	0.68	0.00	0.68
TSS ReCalculation		0.00	0.68	0.00	0.68
Cal		0.00	0.68	0.00	0.68
		Total T	SS Removal =	33%	Separate Form Needs to be Completed for Each Outlet or BMP Train

Prepared By: Christian A. Farland, P.E.

*Equals remaining load from previous BMP (E) which enters the BMP

Non-automated TSS Calculation Sheet must be used if Proprietary BMP Proposed 1. From MassDEP Stormwater Handbook Vol. 1

LONG TERM POLLUTION PREVENTION PLAN



Long Term Pollution Prevention Plan

Site Plan Map 25 Lots 154 & 298 WS Orchard Street New Bedford, MA 02744

June 5, 2019

Record Owner(s):

New Bedford Retail, LLC 83 Orchard Hill Park Drive Leominster, MA 01453

Prepared For:

Lisciotti Development Co. 83 Orchard Hill Park Drive Leominster, MA 01453

Prepared By:

Farland Corp. 401 County Street New Bedford, MA 02740

Long Term Pollution Prevention Plan

This Long Term Pollution Prevention Plan serves to outline good housekeeping practices in order to prevent pollution of the wetland resource areas and surrounding environment. The Long Term Operation & Maintenance Plan shall be taken as part of this document as it is a critical part of this plan and shall be adhered to. Proper operation and maintenance records shall be kept on file at all times.

Snow disposal shall be carried out by the owner. The owner should follow DEP guideline #BWR G2015-01 for all snow removal requirements. For this site, it is anticipated that snow will be plowed from the impervious parking and driveway areas and piled along the shoulders of the driveway areas. Snow along the building is anticipated to be removed by shovel or snow blower.

Snow disposal in the following areas are prohibited:

- Dumping snow in the bordering vegetated wetlands is prohibited.
- Dumping of snow on top of storm drain catch basins or in stormwater drainage basin is prohibited. Snow combined with sand and debris may block a storm drainage system, causing localized flooding. A high volume of sand, sediment, and litter released from melting snow also may be quickly transported through the system into surface water.

Illicit discharges to the stormwater management system are prohibited. Illicit discharges are those that are not entirely comprised of stormwater. Notwithstanding the foregoing, an illicit discharge does not include discharges from the following activities or facilities; firefighting, water line flushing, landscape irrigation, uncontaminated groundwater, potable water sources, foundation drains, air conditioning condensation, footing drains, individual residence car washing, flows from riparian habitats and wetlands, dechlorinated water from swimming pools, water used for street washing, and water used to clean residential buildings without detergents. Measures are provided below to prevent illicit discharges to the stormwater management system.

In order to prevent or minimize the potential for a spill of hazardous substances or oils to contaminate stormwater, a spill control and containment kit, including spill berm, absorbent materials, rags, gloves, and trash containers, shall be readily available. All product manufacturers recommended spill cleanup methods shall be known by maintenance personnel, who shall be trained regarding these procedures and the location of the cleanup procedure information and supplies. In the event of oil, gasoline or other hazardous waste spill on-site, the Norton Fire Department, DEP and the Conservation Agent shall be notified immediately. For spills of less than ¼ gallon, clean-up with absorbent materials or other appropriate means, unless circumstances dictate that the spill should be treated by a professional emergency response contractor. Spills which exceed the reportable quantities of substances mentioned in 40 CFR 110, 40 CFR 117, or 40 CFG 302 must be immediately reported to the EPA National Response Center (800) 242-8802. Any drainage inlet that may be affected by the spill shall be covered

immediately with a spill protector drain cover or similar product, or a spill berm placed around the perimeter of the opening to prevent any contamination into the drainage system. Proper cleanup and disposal of hazardous wastes must follow all applicable local and state regulations and must be carried out by a qualified contractor. Cumberland Farms spill response plan is attached to this document.

The maintenance of all lawns, gardens and landscaped areas shall be performed by the owner. Good housekeeping practices should include proper storage and minimal use of cleaning products and fertilizers. Facility owner should consult with a professional landscaper for proper maintenance of lawns and landscaped areas.

OPERATION & MAINTENANCE PLAN



Long Term Operation and Maintenance Plan

Site Plan Map 25 Lots 154 & 298 WS Orchard Street New Bedford, MA 02744

June 5, 2019

Record Owner(s):

New Bedford Retail, LLC 83 Orchard Hill Park Drive Leominster, MA 01453

Prepared For:

Lisciotti Development Co. 83 Orchard Hill Park Drive Leominster, MA 01453

Prepared By:

Farland Corp. 401 County Street New Bedford, MA 02740 The Operator, Owner, and Party Responsible for Operation and Maintenance of the Stormwater BMP's will be the landowner of the property on which the BMP is located. The responsible party shall:

 a) Maintain an operation and maintenance log for at least three years, including inspections, repairs, replacement and disposal (for disposal, the log shall indicate the type of material and disposal location)

Street Sweeping

It shall be the responsibility of the owner to:

Inspections:

Inspect sediment deposit accumulations on the parking lots quarterly.

Maintenance:

Sweep parking lots at least twice annually, during March or April before spring rains wash residual sand from winter applications into stormwater systems, and in the fall after leaf drop.

Dispose of the accumulated sediment and hydrocarbons in accordance with local, state, and federal guidelines and regulations.

Drain Manholes

The catch basins, trench grate, and manholes are to be inspected and maintained by the owner.

It shall be the responsibility of the owner to:

Inspections:

Inspect the catch basins and manholes quarterly.

Maintenance:

Remove accumulated sediment, trash, leaves and debris when the depth of deposits is greater than or equal to one half the depth from the bottom invert of the lowest pipe in the basin and/or manhole to the bottom elevation of the basin or manhole.

If upon inspection, evidence of hydrocarbons is observed, such material shall be immediately removed and disposed of in accordance with local, state, and federal guidelines and regulations.

To remove oil and other hydrocarbons that accumulate, it may be preferable to use adsorbent pads.

Dispose of the accumulated sediment and hydrocarbons in accordance with local, state, and federal guidelines and regulations.

CDS® Units

The units are to be inspected and maintained by the owner.

CDS Units are proprietary products and must comply with manufacturer's inspection and maintenance requirements. Refer to the attached CDS Inspection and Maintenance Guide.

In the event of a spill, refer to Long Term Pollution Prevention Plan for necessary procedures to prevent discharge of petroleum product into the infiltration system.

It shall be the responsibility of the owner to:

Inspections:

Inspect the units quarterly.

Prepare inspection reports as part of each inspection and include the following information:

- 1. Date of inspection
- 2. Maintenance personnel
- 3. Location of unit (GPS coordinates if possible)
- 4. Time since last rainfall
- 5. Installation deficiencies (missing parts, incorrect installation of parts)
- 6. Structural Deficiencies (concrete cracks, broken parts)
- 7. Operational deficiencies (leaks, blockages)
- 8. Presence of oil sheen of depth of oil layer
- 9. Estimate of depth/volume of floatables (trash, leaves) captured
- 10. Sediment depth measured
- 11. Recommendations for any repairs and/ or maintenance for the units
- 12. Estimation of time before maintenance is required if not required at time of inspection.

Maintenance:

Cleaning should be done during dry weather conditions when no flow is entering the system. The use of a vacuum truck is generally the most effective and convenient method for removing pollutants from the system. The screen should be power washed to ensure it is free of trash and debris.

The CDS® Unit shall be cleaned once the sediment depth reaches 75% of the storage capacity.

If upon inspection, evidence of hydrocarbons is observed, such material shall be immediately removed and disposed of in accordance with local, state, and federal guidelines and regulations.

To remove oil and other hydrocarbons that accumulate, it may be preferable to use adsorbent pads.

Dispose of the accumulated sediment and hydrocarbons in accordance with local, state, and federal guidelines and regulations.

Subsurface Infiltration Chambers

The subsurface infiltration chambers are to be inspected and maintained by the owner. Subsurface infiltration chambers do not rely on standing pool of water, and have been designed to dewater within 72 hours after precipitation. Therefore, mosquito control is not required for the drainage system.

It shall be the responsibility of the owner to:

Inspections:

Inspect subsurface structures at least twice annually.

Maintenance:

If inspection of infiltration system shows that it does not dewater completely within 72 hours of a storm event, the owner shall take immediate steps to restore the function of the system, based on the recommendations of a qualified stormwater professional. Notice shall be provided to the Town of any such corrective action.

Any debris which may clog the system must be removed. Cleaning may be done by either clamshell bucket or vacuum truck. All sediment and hydrocarbons shall be properly disposed of in accordance with local, state, and federal guidelines and regulations.

Drain Lines

After construction, the drain lines shall be inspected after every major storm for the first few months to ensure proper functions. Presence of accumulated sand and silt would indicate more frequent maintenance of the pre-treatment devices is required. Thereafter, the drain lines shall be inspected at least once per year. Accumulated silt shall be removed by a vactor truck or other method preferred.

Access Ways & Parking Areas

Inspections:

Inspect Daily

Clear any debris daily

Sweep bi-annually

Repair cracks and potholes as needed

Maintain painted lines as necessary for visibility

Fences/Walls

Inspections:

Inspect Monthly

Remove debris and litter daily

Repair as necessary

Landscaping

Inspections:

Inspect weekly

Remove debris and litter as necessary

Prune and fertilize bi-annually

Mow lawn as necessary

Fertilize quarterly

ILLICIT DISCHARGE STATEMENT



ENGINEERING | SITE WORK | LAND SURVEYING

June 5, 2019

New Bedford Planning Board City Hall, Rm 303 133 William Street New Bedford, MA 02740

RE: Site Plan – WS Orchard Street
Illicit Discharge Compliance Statement (IDCS)

To whom it concerns,

As required, we are submitting this Illicit Discharge Compliance Statement verifying that no illicit discharges exist on the site or are proposed. We have included in the pollution prevention plan measures to prevent illicit discharges to the stormwater management system, including wastewater discharges and discharges of stormwater contaminated by contact with process wastes, raw materials, toxic pollutants, hazardous substances, oil, or grease.

The site plan identifies the location of any systems for conveying wastewater and/or groundwater on the site and show that there are no connections between the stormwater and wastewater management systems and the location of any measures taken to prevent the entry of illicit discharges into the stormwater management system.

Please feel free to contact us if you should need any further information.

Very Truly Yours,

THOMPSON FARLAND, INC.

Christian A. Farland

Christian A. Farland, P.E., LEED AP

Principal Engineer and President

PIPE CAPACITY CALCULATIONS



ENGINEERING A BETTER TOMORROW


ENGINEERING | SITE WORK | LAND SURVEYING

PIPE CAPACITY CALCULATIONS


	10 YEAR STORM EVENT												
	Pipe D	escription		Drai	ange Area (A	cres)			Time of Concentration (min)				
Length #	DA#	From	То	Total	Imperv. C=0.90	Pervious C=0.30	Comp. C- Value	CA	Inlet	Drain	Total	(in./hr)	Qc=CIA (cfs)
						DRAINAG	E PIPES						
1		Roof	SRS	0.230	0.230	0.000	0.90	0.207	6	0.04	6.04	4.8	0.99
2		SRS	DHM-1	0.230	0.230	0.000	0.90	0.207	6	0.14	6.14	4.8	0.99
3		WQI-1	DMH-1	0.367	0.352	0.015	0.88	0.321	6	0.05	6.05	4.8	1.54
4		WQI-2	DMH-1	0.395	0.352	0.043	0.83	0.330	6	1.00	7.00	4.8	1.58
5		DMH-1	DMH-2	0.992	0.934	0.058	0.86	0.858	6	0.09	6.09	4.8	4.12

	Pipe Pipe				Full Flow			Current Flow				Pipe capacity
Length #	Diameter (in)	Material (n- value)	Slope (ft./ft.)	Length (ft)	Vf (ft/sec)	Qf (cfs)	Vc (ft/sec)	Qc (cfs)	Qc/Qf	d/D (in.)	Flow Depth in pipe (in)	
						DRAINAG	E PIPES					
1	12	0.013	0.0950	21	13.98	10.98	8.86	0.99	0.09	0.2	2.4	OK!
2	12	0.013	0.0310	51	7.99	6.27	6.03	0.99	0.16	0.3	3.3	OK!
3	12	0.013	0.0290	19	7.73	6.07	6.62	1.54	0.25	0.3	4.1	OK!
4	18	0.013	0.0050	206	4.20	7.43	3.44	1.58	0.21	0.3	5.6	OK!
5	18	0.013	0.0050	24	4.20	7.43	4.42	4.12	0.55	0.5	9.4	OK!

WATERSHED PLANS



REVISIONS





www.FarlandCorp.com

401 COUNTY STREET
NEW BEDFORD, MA 02740
P.508.717.3479
OFFICES IN:
•TAUNTON
•MARLBOROUGH
•WARWICK, RI

DRAWN BY: MJW

DESIGNED BY: MJW

CHECKED BY: CAF

SITE PLAN
ORCHARD STREET
MAP 23 LOTS 158 & 294
FORD, MASSACHUSETTS

NEW BEDFORD
PREPARED LISCIOTTI DEVELOPMENT
FOR: 83 ORCHARD HILL PARK DRIV

JUNE 7, 2019


SCALE: 1"=20'

JOB NO. 19-210

LATEST REVISION:

PRE-DEVELOPMENT

SHEET 4A OF 10







www.FarlandCorp.com

401 COUNTY STREET NEW BEDFORD, MA 02740 P.508.717.3479 OFFICES IN: TAUNTON •MARLBOROUGH WARWICK, RI

DRAWN BY: MJW DESIGNED BY: MJW

CHECKED BY: CAF

ASSESSORS MAP 23 LOTS 158 & 294 NEW BEDFORD, MASSACHUSETTS

JUNE 7, 2019 SCALE: 1"=20' JOB NO. 19-210 LATEST REVISION:

POST-DEVELOPMENT

SHEET 4B OF 10