

PATRICK J. SULLIVAN
DIRECTOR

City of New Bedford

Department of Planning, Housing & Community Development

608 Pleasant St, New Bedford, Massachusetts 02740 Telephone: (508) 979.1500 Facsimile: (508) 979.1575

STAFF REPORT

PLANNING BOARD MEETING December 14, 2016

Case #38-16: SITE PLAN REVIEW

Case #39-16: SPECIAL PERMIT FOR PARKING

REDUCTION

Case #40-16: SITE PLAN REVIEW FOR NEW

GROUND SIGN

SW Corner of Swift & Orchard Streets

Map 23, Lot 292

Owner: Clarke's Cove Development Co., LLC

651 Orchard Street, Suite 200 New Bedford, MA 02744

Applicant: Hunt Real Estate Services, Inc.

5100 W. Kennedy Blvd, Ste. 100

Tampa, FL 33609

Applicant's Prime Engineering, Inc.

Agent: P.O. Box 1088

Lakeville, MA 02347

Overview of Request

Request to consider applications under Chapter 9 Comprehensive Zoning for <u>Site Plan approval</u> for new construction of a commercial retail building, <u>Site Plan approval of New Ground Sign</u>, and <u>Special Permit for Parking Reduction located at the SW Corner of Swift</u>

LOOKING AT SITE FROM NORTH SIDE OF SWIFT STREET



& Orchard Streets (Map 23, Lot 292) on a 0.999+/- acre vacant and undeveloped site in the Mixed Use Business (MUB) zoning district.

The site is a former manufacturing location first developed as a textile mill in the 1890's. Subsequently, the mill was purchased by Goodyear Tire & Rubber Company in 1920's for the manufacturing of specialty rubber products and tires. The plant ceased production by the 1990's and decommissioning activities included the removal by demolition all structures at the property. During the decommissioning, site assessment indicated lead, petroleum hydrocarbons, polycyclic aromatic hydrocarbons and volatile organic compound residuals were


present in soil and groundwater. Additional studies conducted in 1999 found there was no migration of these hazardous materials from the site. Of additional note, no uncontrolled sources, such as PCBs, remain at the site. Concentrations of oil and/or hazardous material have been determined to be below S-2 (soil category) soil standards and below GW-2 groundwater standards and in certain locations below GW-1 standards. A current Activity and Use Limitation (AUL) is recorded on the site formerly known as 545 Orchard Street to provide notice to the public and future interested parties of the existence of contamination, and to stipulate permitted activities and uses allowed on this land parcel due to the past history of contamination.


The AUL Opinion provides that a condition of No Significant Risk to health, safety, public welfare or the environment exists for any foreseeable period of time so long as the requisite stipulations are followed. Permitted Activities and Uses Set Forth in the AUL Opinion may be reviewed in the Notice of Activity and Use Limitations (Attachment 10).

In 2008, the Southcoast's regional planning agency--SRPEDD (the Southeastern Regional Planning and Economic Development District), listed this area, shown as 201-07, as a City of New Bedford Priority Development/ Redevelopment Area. The former industrial site is a priority development site under MA Chapter 43D and benefits from certain provisions of the state law (i.e., guarantees local permitting decisions on priority development sites within 180 days).

WAIVER PETITIONS

The applicant has requested a waiver for stormwater detention in the letter to the Planning Board dated November 17, 2016, stating "the site was entirely covered by a building, that is, the lot was had complete impervious cover. Since the proposed development will have less impervious cover, the rate of stormwater will be less" (Attachment 6). However, applicant's agent states in the Development Impact Statement (see 5.0 Surface Water and Subsurface Conditions), "surface water will be collected in a deep sump catch basin and treated with Stormcepter brand storm treatment system and then discharged to a storm drain main which will be installed by the current






landowners from a drain manhole in front of the Portuguese Club toward the south end of Orchard Street. Due to the presence of impacted soil, on-site infiltration of stormwater is ill advised." (Attachment 5). The Planning Board may wish to note that DPI recommends, among its suggested conditions, that drainage design must comply with Phase II, MA Department Stormwater Management standards and that the applicant should show how the proposed 24 inch HDPE storm water pipe connects to the City System. (Attachment 14).

The applicant/owner submits six (6) waiver petitions from the Site Plan Review Application Checklist for the Planning Board's consideration (Attachment 7):

- Layout Plan: Showing proposed grading and spot shots.
- Layout Plan: Showing areas of cut & fill.
- Existing Conditions Plan: Topography.
- Plans in general on checklist: Electronic CAD and PDF.
- Plans in general on checklist: North Arrow pointing up the page.
- 5454 drainage calculations.

Parking requirements for the retail use stipulate one (1) space per each 200 sq. ft. of gross floor area, under ordinance. The applicant petitions the Planning Board for Special Permit for a parking reduction for on-site parking requirements from 46 to 32 spaces, two (2) of which meet the regulations under 521 CMR 23.00: Parking and Passenger Loading Zones.



Existing Conditions

The proposed development is located at the southwest corner of Orchard and Swift Streets in the city's South End adjacent to Ashley Park and the Devalles School zone.

The 43,500+/- SF proposed development area was created by parceling a lot from an area consisting of approximately eleven (11) acres, commonly known as the Goodyear Site. The parcel is shown on Approval Not Required Plan of Land (ANR) as Lot 1A (Attachment 9).

Evidence of monitoring wells is present at the site. The current Activity and Use Limitation (AUL) on the entire eleven acres requires that earthwork be done

under a soil management plan under the supervision of a Licensed Site Professional (LSP).

Other neighboring entities and businesses include: the Monte Pio Luzon American Club, Goulart Square, a number mom & pop local businesses and restaurants, and Our Lady of Mt. Carmel Catholic Church.

Proposed Conditions

The applicant seeks to construct a single-story retail store of Nichiha fiber cement panel and metal, with ancillary parking behind the building. The south elevation (the front of the building as identified by the applicant) will serve as the main entrance for patrons. The building mass of elevations addressing Orchard Street and Swift Street is solid with no provision for natural light. Wall mounted signage for the north, south and east elevations and a ground sign at Orchard Street are proposed.

It has been recommended by the applicant that requisite street trees be planted 10-15 feet off the street layout, thereby keeping street trees far enough from existing power lines to allow the trees to mature as tall shade trees. The applicant also suggests planting lilac trees in the grass ribbon strip.

The anticipated number of customers per day is 200, with hours of operation from 8:00 a.m. to 10:00 p.m. seven (7) days per week. Six (6) employees will staff the retail establishment and accept deliveries between the hours of 8:00 a.m. and 8:00 p.m.

The applicant has provided a project cost estimate of \$343,000.00 with undetermined date for completion in 2017 for the proposed project, as stipulated under §5452.

Site Plan Review

The submittal is named on the Title Sheet as Proposed Family Dollar Retail Store, Orchard Street, New Bedford, MA Issued for Special Permit, dated November 4, 2016, prepared for Hunt Realty Real Estate Services, Inc., 5100 W Kennedy Blvd, Ste. 100, Tampa, FL 33609, by Prime Engineering, P.O. Box 1088, 350 Bedford Street, Lakeville, MA 02347 consisting of ten (10) sheets.

and

Family Dollar, SW Corner Swift St & Orchard St, Bedford, MA, dated 11.03.16, prepared by FWH Architects, 3336 Grand Blvd., Ste. 201, Holiday, FL 34690, consisting of six (6) sheets.

Please correct typo to correctly read "New" Bedford on plans prepared by the architect.

Recommended modifications are noted as follow:

Cover Sheet -

Add "Site Plan" to "Issued for Special Permit"

Existing Conditions Plan - C1.0

Demolition Plan - C2.0

Plan to Accompany Zoning Variance Request - C3.0

- Correct Title Box to read "Site Plan"
- ➤ It appears from the angle of the dumpster pads that the waste removal trucks will enter the site from Orchard Street. For safety reasons, staff suggests the dumpster pads be angled toward Swift Street so waste removal truck may enter and exit the site via Swift Street.

Grading & Drainage Plan – C4.0

> Typos at Notes refer to Dartmouth and Wolfeboro, NH. These typos should be corrected.

Utilities Plan - C5.0

➤ If a satellite dish is to be installed, applicant shall note the location of this structure on plan sheets.

Landscape Plan - C6.0

- Applicant is to seek approval with the Department of Public Infrastructure for proposed two (2) lilac trees and eight (8) additional large trees as Noted.
- > There are discrepancies between plant schedule and number of plantings shown as noted. Applicant shall review plans and make corrections.

Erosion control Plan - C7.0

- Replace "Hay" & "Haybale" with "Straw".
- Note: All references to Hay shall be replaced with Straw in the Stormwater Report, and all other case submittal documents as prepared by the applicant.

Details - C8.0 and C9.0

Utility note shall include following March, 2012 the words, "as amended".

Photometric Site Plan - PH-1

Fixture Information -PH-2

Ext. Elevation Ext. Finish Schedule and Notes - R1.0

Ext. Elevation Ext. Finish Schedule and Notes - R2.0

- Applicant shall provide sample boards for the Planning Board's review.
- Outside vending machines are shown on plan. Applicant shall obtain necessary permits for accessory use.

Ext. Elevation - A2.1

102 X 90 Floor Plan - A1.0

> It appears the mirror plan has been presented for consideration. Please confirm.

Appendix C-Table of Parking & Loading Regulations

USE	PARKING REQUIREMENTS	LOADING REQUIREMENTS
Businesses engaged in retail sale of goods and services, not elsewhere enumerated herein.	One (1) space per each 200 sq. ft. of gross floor area, but not less than two (2) spaces for each business use intended to occupy the premises. After 20,000 sq. ft. gross floor area, one space per 400 sq. ft.	One loading space for each building containing more than 5,000 and less than 10,000 sq. ft. of gross floor area. Thereafter, one (1) additional loading space shall be required for each additional 25,000 sq. ft. of gross floor area.

Review Comments

Plans for modification were distributed to City Clerk, City Solicitor, Health Department, Inspectional Services, Engineering, Public Infrastructure, Conservation Commission, Fire Department and School Department offices.

- Department of Public Infrastructure comments have been provided and may be reviewed at Attachment
 14.
- No permit is required from the Conservation Commission for Map 23, Lot 292 because the site not located in or within 100' of State or Local Wetland Resource Areas. However, City of New Bedford Director of Environmental Stewardship Michele S.W. Paul, LSP, recommends the monitoring wells be decommissioned in accordance with State regulations prior to redevelopment unless the new owner wants to maintain them. Ms. Paul shares that there do not appear to be any significant groundwater issues, therefore the wells are not necessary, and if the wells are damaged during construction, this presents a potential pathway for new spills to reach groundwater.
- Mary Rapoza, Director of Department of Parks, Recreation and Beaches comments Ashley Park provides open space and recreation and hosts an active Community Center for seniors and children which offers a number of after school programs and summer month programmed activity. The Director expressed her concern for the safety of those using Ashley Park, specifically with product delivery and increased traffic volume at the proposed retail establishment.

Outside of this, no further comments from city offices were received in this matter.

Special Permit for Parking Reduction

When considering an application for Special Permit, the Board must take into account the characteristics of the site and of the proposal in relation to that site, in addition to any specific factors that may be set forth under Section 5300 of the zoning ordinance. As to those thresholds, staff offers the following considerations:

Social, economic, or community needs which are served by the proposal.

The vision of the City includes the creation of dynamic neighborhoods. This proposal allows the redevelopment of an existing property for the neighborhood through improvement.

Traffic flow and safety, including parking and loading.

The applicant stated the site will be accessed by a proposed driveway and ample parking will be provided. Customers will park near the building's main entrance, where a sidewalk will provide safe pedestrian access to the building. On-site walkways will be connected to the off-site sidewalks in order to achieve safe pedestrian access.

Staff notes issues of concern for the safety of those using Ashley Park, due to product delivery and increased traffic volume at the proposed retail establishment.

Adequacy of utilities and other public services.

The applicant has been provided with the Department of Infrastructure recommendations for the development. Staff recommends the applicant review the conditions for approval to meet performance standards set by DPI.

Neighborhood character and social structures.

The applicant proposes to construct the building at the corner of Swift and Orchard Streets with parking to be located to the rear of the building mass (as opposed to the more suburban style arrangement of a setback building with a parking lot in front). Given the strategic corner location, optimally an archetype model that addresses corner street fronts and is respectful of the historic, traditional style store-fronts along Rivet Street would extend the kind of retail architecture and spatial expectations of the established neighborhood. The Planning Board may wish to have a conversation with the applicant regarding other options of locating the building and/or its main entrance point in a way that more closely aligns with street-driven, pedestrian-friendly retail development.

Impacts on the natural environment

The AUL Opinion provides that a condition of No Significant Risk to health, safety, public welfare or the environment exists for any foreseeable period of time so long as the requisite stipulations are followed.

Potential fiscal impact, including impact on City services, tax base, and employment

Having this abandoned Brownfield property site improved will provide a positive fiscal impact on the city. Done in keeping with the context of the neighborhood setting, the Economic Development Council supports development of this Priority Development Site.

Master Plan Goal

This proposal is consistent with the master plan's goal (of establishing a sound foundation for future growth that builds upon its coastal location, preserves its historic legacy, and expands cultural and workforce opportunities) as it restores blighted property, improves the neighborhood and provides new jobs for the community in construction and ongoing.

Staff Recommendation

This site and the larger former Goodyear Site from which it has been created are significant to this part of the City for a number of reasons that include both its size and its undeveloped condition. As the first piece of the Goodyear Site to be developed, the plan to develop a Family Dollar building/business here is not without its challenges from a pure planning perspective.

The applicant is seeking a special permit for parking reduction as well as site plan approval for the overall project and for a proposed ground sign. In considering these three requests, staff offers the following considerations for the board:

1. **Special Permit.** The requested special permit would allow a retail parking lot of 32 vehicle spaces where 46 such spaces are required (given the proposed 9,180 SF retail business use). To deny this reduction would mean that the proposed building space would require reduction in square footage since there is no additional room on the site to increase proposed parking spaces. A reduction in the building size to 7,000



SF (a loss of roughly 24% of the building) would necessitate 35 spaces under the existing zoning ordinance. It would be difficult to achieve the parking standard as currently exists for a building of this size on a one acre lot as is the case here. The board may wish to consider, however, that the siting of this business close to a residential neighborhood may provide impetus for pedestrian and bike traffic to the site thereby reducing somewhat the demand for onsite parking.

- 2. Site Plan Approval. The architectural style exemplified by the proposed elevation drawings and construction specification materials will have an impact on the built environment of the City of New Bedford and the proposed Form Based Code Character Plan for Goulart Square. An element of consideration by the Planning Board when reviewing development proposals is how a building presents, or addresses, itself on the site. This presentation of the building determines the proposal's affect on the visual environment. In light of this and in keeping with comments made in the Section entitled "Special Permit for Parking Reduction" within this staff report the board may wish to have a conversation with the applicant regarding other options of locating the building and/or its main entrance point in a way that more closely aligns with street-driven, pedestrian-friendly retail development. Additionally, staff recommends the dumpster and transformer pads be screened, and landscaping plan conform to the stipulations of §3300 3360. Staff recommends the dumpster and transformer pads be relocated to the southwest corner of the site for improved circulation of waste management vehicles.
- 3. **Site Plan Approval for a Ground Sign.** By developing and constructing a building at the corner of two streets as is the proposed case here, the business would be able to strategically place wall signs on the faces of the building to provide the requisite advertising (in addition to directional entry signs, etc). Whether the building fronts on the street intersection or is placed there with its main opening to the south, the applicant may find that the need for their Ground Sign is precluded, as visibility of building mounted signage will be seen by approaching pedestrian and vehicular traffic. The proposed freestanding 13' 8" high, 24 SF red and orange graphic color ground sign is inconsistent within the existing neighborhood setting. As stipulated under §3201. of the city's ordinance to establish reasonable regulations for all exterior signs designed to attract the attention of persons located outdoors, the land use [for Ground Sign] must protect property values by ensuring the compatibility of property with that surrounding it; provide an attractive visual

environment throughout the city; protect the character and appearance of the various neighborhoods in the city; and protect the public health, safety, and general welfare.

In consideration of the following petitions for waiver:

Layout Plan: Showing proposed grading and spot shots.

Staff recommends site (layout) plan show spot grading at four building corners.

Layout Plan: Showing areas of cut & fill.

The applicant has not submitted plan and section views showing cut and fill areas of a site which is associated with an Activity and Use Limitation. These plans should be provided by the applicant.

Existing Conditions Plan: Topography

The Site Plan Review Application asks the following "Benchmark locations (Based on USGS NGVD – show year)"; this request for waiver does not apply to the Planning Division checklist, therefore the petition by applicant is unnecessary.

Plans in general on checklist: Electronic CAD and PDF.

The Planning division keeps electronic copies of plan submittals for historical reference. Applicant shall submit original digital plans in PDF format for historical reference.

Plans in general on checklist: North Arrow pointing up the page.

Plan sheets illustrate a north arrow; therefore the petition by applicant is unnecessary.

5454 drainage calculations.

Applicant describes the site as being totally impervious; site visit by staff finds the property overgrown with vegetation. Staff does not recommend waiver be granted for drainage calculations.

Attachments:

- 1. Site Plan Approval Application
- 2. Special Permit Application
- 3. Site Plan Approval Application for New Ground Sign
- 4. Development Impact Statement
- 5. Letter to the Planning Board dated November 17, 2016
- 6. Request for Waivers
- 7. Deed Bristol County (S.D) Registry of Deeds Book 7223, Page 263
- 8. ANR Plan of Land Book 159, Page14
- 9. Notice of Activity and Use Limitations Bristol County (S.D) Registry of Deeds Book 7863, Page 305
- 10. Plan Set Dated 11.04.2016
- 11. Sign Graphic
- 12. Building Department Application for Plan Examination and Building Permit
- 13. Department of Public Infrastructure Memorandum Dated 12/07/2016
- 14. Drainage Report

2016 NOV 18 P 2: 55



JONATHAN F. MITCHELL, MAYOR

PLANNING BOARD

CITY CLERK

SUBMIT TO: Planning Department 133 William Street Room 303 New Bedford, MA 0274

SITE PLAN REVIEW APPLICATION

The undersigned, being the entitled: See attached list of drawing	Applicant, seeks Site Pla	an Approval for me Engineering, Inc.	proper	ty depicte da	d on a	plan ovember 4, 2016
Application Informat Street Address:	*	SW corner of	Swift a	and Orcha	ard Sti	reets
Assessor's Map(s):	23	Lot(s)	292			
Registry of Deeds Book:	7223	Page:	263			and an Ariel Aries a
Zoning District:	Mixed Use Business					· · · · · · · · · · · · · · · · · · ·
Applicant's Name (printed):	Hunt Real Estate Serv	rices, Inc.				1 2000
Applicant's Name (printed). Mailing Address:	5100 W Kennedy Blvd., Suile 100	Tampa		FL		33609
	(Street) 727 458-4055	(City)	khess@	(State) huntresco.c	com	(Zip)
Contact Information: Applicant's Relationship to I	Telephone Number Property: ☐ Owner	□Contract Ve		Address Other	Propo	sed Buye
List all submitted materials (See attached letter	include document titles	s & volume nun	nbers w	here appli	icable)) below:
By signing below, I/we acknow knowledge. I/we further unde grounds for the revocation of Board Members the right to acupon reasonable notice for the	rstand that any false infor the approval (s). I/we also ccess the premises (both i e purpose of taking photo	mation intentio give Planning D nterior and exte	nally property Departmerior) at ducting	ovided or o ent staff ar reasonable	mitted nd Plar e times	a is nning and
Date	Digitation					

City Hall • 133 William Street • Room 303 • New Bedford, MA 02740 • <u>www.newbedford-ma.gov</u> PH: (508)979-1488 • FX: (508)979-1576

Case 38-16, 39-16 & 40-16 11/18/2016

2. Review Applicability (C	Check All That Apply	to Your Prop	osal)	
Category Residential Commercial Industrial Mixed (Check all categories that apply)	Expans	onstruction sion of Existing	> 2,00 3 or m residen 1 or m existin Drive Groun Reside	o gross sq feet o gross sq feet nore new ntial units ore new units in g res. multi-unit Thru Proposed ad Sign Proposed ential Driveway > 1 curbcut
3. Zoning Classifications				
Present Use of Premises:	Mixed Use Business	*		
Proposed Use of Premises:	Retail store			
Zoning Relief Previously Gr None	anted (Variances, Sp	pecial Permits,	with Dates Granted)):
4. Briefly Describe the Pr It is proposed to construct a 9,180 squa				
	2.			
5. Please complete the fo	llowing:			
	I	existing	Allowed/Required	Proposed
T . A (())		10 700	N1/A	40.500

	Existing	Allowed/Required	<u>Proposed</u>
Lot Area (sq ft)	43,500	N/A	43,500
Lot Width (ft)	217	N/A	217
Number of Dwelling Units	0	N/A	0
Total Gross Floor Area (sq ft)	0	N/A	9,180
Residential Gross Floor Area (sq ft)	0	N/A	0
Non-Residential Gross Floor Area (sq ft)	0	N/A	9,180
Building Height (ft)	0	100	25
Front Setback (ft)	0	0	15
Side Setback (ft)	0	0	15&83
Side Setback (ft)	0	0	15&83

Lot Coverage by Buildings (% of Lot Area)	0	N/A	21
Permeable Open Space (% of Lot Area)	100	N/A	N/A
Green Space (% of Lot Area)	100	0	Over 10
Off-Street Parking Spaces	0	46	32
Long-Term Bicycle Parking Spaces	0	0	0
Short-Term Bicycle Parking Spaces	0	0	0
Loading Bays	0	1	1
6. Please complete the following:		Existing	Proposed
a) Number of customers per day:		0	200
b) Number of employees:		0	6
c) Hours of operation:		0	8 am - 10 pm
d) Days of operation:		N/A	7
e) Hours of deliveries:		N/A	8 am - 8 pm
f) Frequency of deliveries:	ly 🛮 Weekly	□Monthly	☐ Other:
The applicant is also requesting a Specify the requested Special Perm Impact Statement how the request It is proposed to construct a 9,180 square foo	nit(s) below, and s meets approval	set forth within a	attached Development §5320 of the zoning code
46 spaces.	t store with 52 parking	Spaces Where the Zen	mig oramanos requires
- o opasses.			
8. ZBA Variances and Special Permits:			
NOTICE: Checking below does not constitu applicant must also file the proper applicat	te application for tion form and fee	a special permit with the Zoning	or a variance. The Board of Appeals.
The applicant is also requesting a sp			
Specify zoning code section & title			
The applicant is also requesting a va	riance from the 2	ZBA:	
Specify zoning code section & title			

0

Rear Setback (ft)

83&112

10

9. OWNERSHIP VERIFICATION

This section is to be completed & signed by the	e property owner: Hunt Real Estate Services, Inc.
I hereby authorize the following Applic	ant: Turk road Estate South 100 Towns El 22600
at the following address:	5100 W Kennedy Blvd., Suite 100, Tampa, FL 33609
to apply for:	Site Plan Review
on premises located at:	Site Plan Review SW corner of Swift and Orchard Streets
in annual armarchin aireas	October 11, 2004
whose address is:	SW corner of Swift and Orchard Streets
for which the record title stands in the name of:	Clark's Cove Development Co., LLC
whose address is:	651 Orchard Street, New Bedford, MA 02749
	County: Bristol Book: 2223 Page: 263 rtificate No.: Book: Page: Page:
further understand that any false information intrevocation of the approval(s). I/we also give Plant the right to access the premises (both interior annotice for the purpose of taking photographs and	ning Department staff and Planning Board Members d exterior) at reasonable times and upon reasonable

2016 NOV 18 P 2: 55



CITY OF NEW BEDFORD JONATHAN F. MITCHELL, MAYOR

PLANNING BOARD CITY CLERK

SUBMIT TO: Planning Department 133 William Street Room 303 New Bedford, MA 0274

SPECIAL PERMIT APPLICATION

1. Application Inform				
Street Address:	SW Corner of Swift ar	nd Orchard Str	eets	
Assessor's Map(s):	23	Lot(s)	292	
Registry of Deeds Book:	7223	Page:	263	
Zoning District:	Mixed Use Business	123		
Applicant's Name (printed	d): Hunt Real Estate Serv	/ices, Inc.		
Mailing Address:	5100 W Kennedy Blvd Suite 100	Tampa	FL	33609
Contact Information:	(Street) 727 458-4055	(City)	(State) khess@huntresco.c	(Zip) com
Contact information.	Telephone Number		Email Address	
Applicant's Relationship t	o Property: ☐Owner		ndee 🛮 Other <u>Pr</u>	
Refer to attached cove				

City Hall • 133 William Street • Room 303 • New Bedford, MA 02740 • <u>www.newbedford-ma.gov</u> PH: (508)979-1488 • FX: (508)979-1576

CAGE 39-16

Case 38-16, 39-16 & 40-16 11/18/2016

2. Zoning Classifications	
Present Use of Premises:	Mixed Use Business
Proposed Use of Premises:	Retail store
Zoning Relief Previously Gr None	anted (Variances, Special Permits, with Dates Granted):
3. Briefly Describe the Pi	roposed Project and Specify all Requested Special Permits:
It is proposed to construct a 9,180 squa	re foot store with 32 parking spaces where the zoning ordinance requires 46 spaces.

4. Please complete the following:

	Existing	Allowed/Required	Proposed
Lot Area (sq ft)	46,500	N/A	43,500
Lot Width (ft)	217	N/A	217
Number of Dwelling Units	0	N/A	0
Total Gross Floor Area (sq ft)	0	N/A	9,180
Residential Gross Floor Area (sq ft)	0	N/A	0
Non-Residential Gross Floor Area (sq ft)	0	N/A	9,180
Building Height (ft)	0	100	25
Front Setback (ft)	0	0	15
Side Setback (ft)	0	0	15&83
Side Setback (ft)	0	0	15&83
Rear Setback (ft)	0	10	83&112
Lot Coverage by Buildings (% of Lot Area)	0	N/A	21
Permeable Open Space (% of Lot Area)	100	N/A	N/A
Green Space (% of Lot Area)	100	0	over 10
Off-Street Parking Spaces	0	46	32
Long-Term Bicycle Parking Spaces	0	0	0
Short-Term Bicycle Parking Spaces	0	0	0
Loading Bays	0	1	1

5. Please complete the following	g:	¥	Existi	ng	Proposed
a) Number of customers per day:			0		200
b) Number of employees:			0	_	6
c) Hours of operation:			0		8 am - 10 pm
d) Days of operation:			N/A		7
e) Hours of deliveries:			N/A		8 am - 8 pm
f) Frequency of deliveries:	☐ Daily	☑ Weekly	☐ Monthly	— □Othe	er:
6. OWNERSHIP VERIFICATI	ION				
This section is to be completed	d & signed b	y the propert	y owner:		
I hereby authorize the follo	owing Appli	_{cant:} Hunt Re	al Estate Ser	vices, Ind	C.
at the follow	ring address	5100 W Ker	nedy Blvd., S	uite 100,	, Tampa, FL 33609
	to apply for:	Special Perr	mit		
on premise	s located at:	SW Corner	of Swift and O	rchard S	Streets
in current owne	ership since:	October 11,	2004		
whose	e address is:	SW Corner of	of Swift and O	rchard S	treets
for which the record title stand	s in the nam	ne of: Clark's	Cove Develop	ment Co	o, LLC
whose	address is:	651 Orchard	Street, New E	Bedford,	MA 02744
by a deed duly recorded in the:					
Registry of Dee	eds of Count	y: Bristol	Book: <u>22</u> 2	23 Pag	e: <u>263</u>
OR Registry District of the Land Cou	ırt, Certifica	te No.: -	Book:	Pag	e: -

I/we acknowledge that all information presented herein is true to the best of my/our knowledge. I/we further understand that any false information intentionally provided or omitted is grounds for the revocation of the approval(s). I/we also give Planning Department staff and Planning Board Members the right to access the premises (both interior and exterior) at reasonable times and upon reasonable notice for the purpose of taking photographs and conducting other visual inspections.

////3// Date

Signature of Land Owner (If authorized Trustee, Officer of Agent, so identify)



PLANNING BOARD

CITY OF NEW BEDFORD JONATHAN F. MITCHELL, MAYOR SUBMIT TO: Planning Department 133 William Street Room 303 New Bedford, MA 02740

SITE PLAN REVIEW APPLICATION FOR NEW GROUND SIGN

The undersigned, being the See attached list of drawings	ne Applicant, seeks Site Pla by: <u>Prime Eng</u>	n Approval for pineering, Inc.	property depicted	d on a plan entitled dated: 11/4/2016
ı. Application Informa	ation			
Street Address:	SW Corner of Swift an	d Orchard Str	eets	
Assessor's Map(s):	23	Lot(s)	292	
Registry of Deeds Book:	7223	Page:	263	
Zoning District:	Mixed Use Business			
Applicant's Name (printed	l): Hunt Real Estate Serv	ices, Inc.		
Mailing Address:	5100 W Kennedy Blvd. Suite 100	Tampa	FL	33609
Contact Information:	(Street) 727 458-4055	(City)	(State) khess@huntresc	(Zip) o.com
Contact information;	Telephone Number		Email Address	
List all submitted material Refer to attached Pylor	ls (include document titles n Sign Detail	: & volume nun	nbers where appli	cable) below:
knowledge. I/we further u grounds for the revocatior Board Members the right (knowledge that all informanderstand that any false in of the approval (s). I/we atto access the premises (both or the purpose of taking plants.	oformation intended in the last of give Planni the interior and of graphs and of the last	ntionally provide ng Department s exterior) at reaso conducting other	d or omitted is taff and Planning nable times and
Date	Signatu	are of Applican	t	

Case 40-16 11/22 '2016

Special Permits	s, with Dates Granted)	:				
3. Will sign be illuminated? Yes , How? Internally						
4. Will sign overhang a public sidewalk? No , If yes, an indemnification certificate must be obtained from the City Council Clerk's Office, City Hall Room 215						
Collar retail building wit	h ancillary parking.					
Johan Tetali bullung with	Transmary parking.					
Existing	Allowed/Required	Proposed				
N/A	25	24.16				
N/A	15	13' 8"				
N/A	1	1 Freestanding				
N/A	6	6				
N/A	6	40				
N/A	6	174				
I fee with the Zog a special perm	ning Board of Appeals it from the ZBA:	ariance. The applicant				
	Existing N/A	Existing Allowed/Required N/A 25 N/A 15 N/A 1 N/A 6 N/A 16 N/A				

8. OWNERSHIP VERIFICATION

This section is to be completed & signed by the property owner:
I hereby authorize the following Applicant: Hunt Real Estate Services, Inc.
at the following address: 5100 W Kennedy Blvd. Suite 100, Tampa, FL 33609
to apply for: Site Plan Review for New Ground Sign
on premises located at: SW Corner of Swift and Orchard Streets
for which the record title stands in the name of: Clark's Cove Development Co, LLC
whose address is: 651 Orchard Street, New Bedford, MA 02744
by a deed duly recorded in the: Registry of Deeds of County: Bristol Book: 2223 Page: 263
OR Registry District of the Land Court, Certificate No.: Book: Page:
I/we acknowledge that all information presented herein is true to the best of my/our knowledge. I/we further understand that any false information intentionally provided or omitted is grounds for the revocation of the approval(s). I/we also give Planning Department staff and Planning Board Members the right to access the premises (both interior and exterior) at reasonable times and upon reasonable notice for the purpose of taking photographs and conducting other visual inspections.

DEVELOPMENT IMPACT STATEMENT FOR PROPOSED FAMILY DOLLAR STORE AT THE SOUTHWEST CORNER OF SWIFT AND ORCHARD STREETS NEW BEDFORD, MA

PREPARED FOR:

HUNT REAL ESTATE SERVICES 5100 W KENNEDY BLVD. - SUITE 100 TAMPA, FL 33609

PREPARED BY:

PRIME ENGINEERING, INC. P.O. BOX 1088 LAKEVILLE, MA 02347

NOVEMBER 10, 2016

Case 38-16, 39-16 & 40-16 11/18/2016

ATTACHMENT 4

1.0	INTRODUCT	TION	I		
2.0	EXISTING C	ONDITIONS	1		
3.0	PROPOSED	DEVELOPMENT	1		
4.0	PHYSICAL E	ENVIRONMENT	2		
5.0	SURFACE W	ATER AND SUBSURFACE CONDITIONS	2		
6.0	CIRCULATIO	ON SYSTEM	3		
7.0	SUPPORT SY	YSTEMS	3		
8.0	COMPLIANCE WITH SITE PLAN REVIEW STANDARDS				
9.0 CONCLUSIO		N	5		
Attach	ment A:	Site Improvement Costs			
		Site improvement costs			
Attachment B:		Test Pit Logs (For locations, refer to the Existing Conditions Plan)			
Attach	ment C:	Photographs			
Attach	ment D:	Pylon Sign Detail			

1.0 INTRODUCTION

It is proposed to construct a retail store in New Bedford which requires Site Plan Review and a Special Permit from the Planning Board. One element of the submittal package is a Development Impact Statement. This document has been prepared to satisfy that requirement.

2.0 EXISTING CONDITIONS

The site is a vacant parcel on the south side of Swift Street and west side of Orchard Street. It is referenced as Lot 292 on Assessors Map 23. It contains 43,500 square feet of area. Historically, the site was covered with a large manufacturing building. The site slopes down from a high point at elevation 17 at the northeast end to elevation 10 at the southwest end of the site. The land surface is covered with grass with some shrubs.

3.0 PROPOSED DEVELOPMENT

It is proposed to construct a 9,180 square foot, single story, retail store with an ancillary parking lot with 30 standard spaces and 2 van accessible handicap spaces. The New Bedford zoning ordinance requires 46 parking spaces. A special permit is being requested to require fewer spaces because the Family Dollar operation does not need more than 30 spaces and there is ample available parking on Swift and Orchard Streets. Requiring fewer parking spaces will result in a greater amount of pervious landscaping.

The proposed wall mounted signs comply with the zoning standards. The standard Family Dollar internally lighted pylon sign, which is detailed in Attachment D of this report, complies with zoning standards as follows:

CRITERIA	REQUIRED	PROPOSED
Maximum height of top of sign	15 LF	13.7 LF
Maximum height of bottom of sign	10 LF	10 LF
Maximum area of sign	25 SF	24 SF

Other than the number of parking spaces, zoning standards will be met.

The sidewalks adjacent to the development on Orchard and Swift Streets will be reconstructed with a 5 foot wide grass ribbon strip and 5 foot wide concrete sidewalk on Orchard Street and a 4 foot wide grass ribbon strip and a 5 foot wide concrete sidewalk on Swift Street. Ordinarily, the

Department of Public Infrastructure requests shade trees be planted every 40 feet along the street in the grass ribbon strip. A review of the photographs presented in Attachment C demonstrate that the utility companies have been hacking away at the existing shade trees dooming them never to mature as functional or aesthetic shade trees. As an alternative, it is being proposed that the requisite shade trees be planted 10 to 15 feet off the street layout, thereby keeping them far away enough from the power lines to allow them to mature as tall shade trees. Several smaller trees (i.e. lilac) will still be planted in the grass ribbon strip and the existing trees will be preserved. The pear and lilac appear on the City's recommended street tree list but they will not be very effective as shade trees. The combination of on-site large shade trees and off-site small trees will combine to effect the desired street scape.

4.0 PHYSICAL ENVIRONMENT

The site is a listed Massachusetts Contingency Plan (MCP) site due to impacted soil from the former tire manufacturing operation. In addition, the soil is geotechnically unsuitable in its current condition. The soil from the entire site will be excavated down to the original slab elevation. Unsuitable debris will be removed and then the soil will be placed and compacted in one foot lifts. All solid waste will be transported to a licensed disposal facility. Other than the above, there are no unusual geologic, archeologic, scenic or historic features or structures. There are no stone walls, trails, open space links, or indigenous wildlife.

There is undeveloped land to the west and south. A city park is to the north and the John Devalles School and the Monte Pio Luzo American Club is to the east.

5.0 SURFACE WATER AND SUBSURFACE CONDITIONS

The site contains urban fill which, as in many areas of New Bedford, have been impacted by petroleum hydrocarbons, metals and poly nuclear aromatic hydrocarbons (PAHs). After development, these soils will be inaccessible since they will be beneath pavement and the concrete slab. During construction, they will be managed with a written soil management plan.

Historical releases of lubricating oils and other petroleum products (No. 6 fuel oil) have resulted in the detection of TPH and the following PAHs in soils; acenaphthene, anthracene, benzo(a)anthracene, benzo(b)fluoranthene, benzo(k)fluoranthene, benzo(g,h,i)perylene, benzo(a)pyrene, chrysene, dibenzo(a,h)anthracene, dibenzofuran, fluoranthene, fluorene, indeno(1,2,3-cd)pyrene, naphthalene, phenanthrene and pyrene. Lead, butyl benzl phthalate and the following VOCs were also detected in soils: xylenes, methylene chloride, chloroform, tetrachloroethene, 1,2 dichloroethene and styrene.

Historical releases of lubricating oils and other petroleum products (No. 6 fuel oil) have resulted in the detection of TPH, naphthalene, and benzene in groundwater. Creosols (2 methylphenol, 4 methylphenol), 2,4 dimethylphenol, benzoic acid, phenol, bis 2 ethyl hexyl phthalate and the following VOCs were also detected in groundwater: ethylbenzene, toluene, xylenes, methyl tertiary

butyl ether, isopropylbenzene, n-propylbenzene, 1,2,4, trimethylbenzene, methylene chloride, chloroform, 1,1 dichloroethene, 1,1 dichloroethene, 1,2 dichloroethene, trichloroethene, vinyl chloride, trichlorofluromethane, 1,4 dichlorobenzene and 4, methyl 2 pentanone.

Surface water will be collected in a deep sump catch basin and treated with a Stormceptor brand storm treatment system and then discharged to a storm drain main which will be installed by the current landowners from a drain manhole in front of the Portugese Club toward the south end of Orchard Street. Due to the presence of impacted soil, on site infiltration of stormwater is ill advised.

6.0 CIRCULATION SYSTEM

Orchard Street is a city street which runs from Cove Road on the south to Court Street to the north. It has a 36 foot pavement width with sidewalks on both sides. There is excellent site visibility in both directions from the subject site. Swift Road runs easterly from Dartmouth Street and terminates at Orchard Street. It has a 24 foot pavement width and sidewalks on both sides. There is good site visibility in both directions from the subject site.

Orchard Street experiences moderate traffic in the morning and evening rush hours and light traffic for the balance of the day. Swift Street experiences light traffic all day.

The Institute of Transportation Trip Generation Manual was used to project the volume of traffic. Land Use 815, free standing discount store, was used. The projected daily volume of weekday trip ends is 514. Saturday daily trip ends is projected to be 653 and Sunday daily vehicle trip ends is projected to be 504. The following six figures present projected peak hourly turning movements with 7-9 a.m. being the peak hour of the city streets, 10-11 a.m. is the store's morning peak hour, 12-3 p.m. is the store's afternoon peak hours and 4-6 p.m. is the city street's evening peak hours. The most severe traffic conflict is during the 4-6 p.m. rush hour, where 8 northbound vehicles on Orchard Street are turning left into the site. These vehicles must wait for a gap in the southbound traffic. Since the Rivet Street and Orchard Street intersection is controlled by a four way stop sign, a steady stream of southbound gaps occur. The combination of moderate traffic and well distributed turning movements results in a level of service A in all situations.

It is proposed that the existing sidewalk on Swift and Orchard Streets be reconstructed with the New Bedford standard grass ribbon along the street edge.

7.0 SUPPORT SYSTEMS

No fuel storage is proposed at the site. Fire Station #11 is less than one mile from the site, therefore emergency response should not be an issue.

The presence of a parking lot will not have any affect on recreation or schools.

8.0 COMPLIANCE WITH SITE PLAN REVIEW STANDARDS

Sections 5470 of the New Bedford Zoning Ordinance prescribes specific Site Plan Review design requirements. This section presents how each of these design standards are being met:

8.1 Earthworks

The proposed grading for the site requires importing approximately 950 cubic yards of gravel required to be placed immediately beneath the slab and pavement and approximately 350 cubic yards of ordinary earth for beneath the gravel layer.

8.2 Pedestrian and Vehicular Safety

The site will be accessed by a proposed driveway and ample parking will be provided. Visitors will park near the building's main entrance, where a sidewalk will provide safe pedestrian access to the building. The on-site sidewalks will be connected to the off-site sidewalks in order to achieve safe pedestrian access.

8.3 Scenic Views

The proposed building will not obstruct any scenic views from publicly accessible locations.

8.4 Visual Intrusion

The parking, storage areas and outdoor service areas have been layed out so as not to be visually intrusive to any public way and residentially used or zoned areas. All trash storage areas will be screened by enclosures. Landscaping will be provided throughout the site.

8.5 Off-Site Glare

The proposed parking has been designed so as to prevent glare. The parking lot lighting will be dark sky compliant and will shine downward in order to prevent off-site glare.

8.6 Character, Material and Scale of Building

The proposed building is similar in character, material and scale to the other buildings in the area.

8.7 Water Contamination

All materials that have a potential for causing higher stormwater pollution loads will be stored indoors. The stormwater will be passed through a Stormceptor brand stormwater treatment system, thereby assuring proper water quality.

8.8 Zoning Compliance

Except for the number of parking spaces, the site design complies with all the relevant zoning ordinance provisions in the mixed-use business district.

8.9 Public Ways

The proposed use will not damage Orchard Street, Swift Street or any other public ways.


8.10 Internal Vehicle Circulation


The proposed driveways have been layed out in order to promote orderly and reasonable internal circulation within the site so as to protect public safety.


9.0 CONCLUSION


The proposed store will add to the City's tax base and provide a convenient location for shopping in that area of New Bedford. The developed property will be privately owned and maintained. None of the property will become common or public land. Compliance with zoning standards is presented on the Zoning Summary Table which is presented on the cover sheet on the set of project plans

It is intended that construction will be completed in 2017. Attachment A presents the projected site costs.











PRIME ENGINEERING

ENVIRONMENTAL

ASSESSMENT

TEL: 508.947.0050 FAX: 508.947.2004





PRIME ENGINEERING

ASSESSMENT

ATTACHMENT A SITE IMPROVEMENT COSTS

Proposed Family Dollar Store Corner of Swift and Orchard Streets Site Improvement Costs

Earthwork	\$150,000
Erosion Control	\$ 6,000
Paving	\$ 85,000
Sidewalks	\$ 10,000
Dumpster Enclosure	\$ 10,000
Site Lighting	\$ 9,000
Landscaping/Irrigation	\$ 19,000
Water	\$ 10,000
Sewer	\$ 5,000
Storm	\$ 20,000
Power	\$ 13,000
Gas	\$ 5,000
Phone	\$ 1,000
Total	\$343,000

ATTACHMENT B TEST PIT LOGS



Consulting Engineers and Scientists

TEST PIT LOG

			IESI.	PIT LOG	
Project: Proposed Family Dollar, New Bedford			MA	Project #: 141.06058	
TEST PIT IDENT	IFICATION:	TP1			
Location: Swift Street & Orchard Street				Ground Elevation: NM	
Client: Hunt Real Estate				Datum: NA	
Contractor: Diversified Development				Operator: Troy	
Equipment: CAT 303.5E CR				Samples Collected	Yes <u>X</u> No
Capacity/Reach: 2.	5 cu. ft./9.5'			Time Started: 10:30	Time Completed: 11:30
Weather: Mostly su	ınny, breezy (N	E), 80s			
Logged by: CDD				Date: 9/5/14	
Checked by: JPJ				Date: 1/21/16	
		TEST	PIT IN	FORMATION	
Depth of Stratum Change Feet	Sample No. and Type	Sample Depth Feet		Soil De	scription
0 - 1			TOPSO	DIL	
1 - 3			fine to		own, fine to coarse SAND and bbles and Boulders, little Silt.
3 - 9.5			FILL MATERIALS: Dark brown, fine to coarse SAND, and fine to coarse GRAVEL with Cobbles and Boulders. Concrete slab at 4' to 5'. Debris estimate 25%.		
				Bottom of Ex	ccavation 9.5'
Pit Dimensions (Ft.) Length 10 Width 5 Depth 9.5			2) Wate 3) Debr	pit backfilled with excava er seepage at 9' bgs. ris noted: brick fragments	ated material. s, rebar, lumber, clay and steel s, tar paper, reinforced concrete



Consulting Engineers and Scientists

TEST PIT LOG

		3	ILOI.	PIT LOG		
Project: Proposed Family Dollar, New Bedford, MA			MA	Project #: 141.06058		
TEST PIT IDENT	IFICATION:	TP2				
Location: Swift Street & Orchard Street				Ground Elevation: NM		
Client: Hunt Real Estate				Datum: NA		
Contractor: Diversified Development				Operator: Troy		
Equipment: CAT 3	03.5E CR			Samples CollectedX_YesNo		
Capacity/Reach: 2.	5 cu. ft./9.5'			Time Started: 0900 Time Completed: 1020		
Weather: Mostly su	nny, breezy (N	E), 80s				
Logged by: CDD				Date: 9/5/14		
Checked by: JPJ				Date: 1/21/16		
		TEST	PIT IN	FORMATION		
Depth of Stratum Change Feet	Sample No. and Type	Sample Depth Feet	Soil Description			
0 - 1			TOPSOIL			
1 – 9	SI	6'-7'	FILL MATERIALS: Brown-Gray, fine to coarse SAND, and fine to coarse GRAVEL with Cobbles and Boulders, little Silt. Concrete slab at 3' to 4'. Debris estimate 25%.			
				Bottom of Excavation 9.0'		
Pit Dimensions (Ft.) Length 8 Width 3 Depth 9			2) Wate3) Debrmetal, r4) Sampof fill m	es: pit backfilled with excavated material. per seepage at 9' bgs. is noted: brick and concrete fragments, lumber, scrap ubber, rebar, steel pipes. ple TP2-S1-090514 collected from interval representative naterials encountered. Aliquots collected for metals and rith target PAHs) analyses. Sample held pending		



Project: Proposed l	Family Dollar, N			Project #: 141.06058	
TEST PIT IDENT	IFICATION:	TP3			
Location: Swift Str	reet & Orchard S	Street		Ground Elevation: NM	
Client: Hunt Real I	Estate			Datum: NA	
Contractor: Diversi	ified Developme	ent		Operator: Troy	
Equipment: CAT 3	03.5E CR			Samples CollectedYes <u>X</u> No	
Capacity/Reach: 2.	5 cu. ft./9.5'			Time Started: 0830 Completed: 0900	
Weather: Mostly su	ınny, breezy (Ni	E), 80s			
Logged by: CDD				Date: 9/5/14	
Checked by: JPJ				Date: 1/21/16	
		TEST	PIT INI	FORMATION	
Depth of Stratum Change Feet	Sample No. and Type	Sample Depth Feet		Soil Description	
0 - 1			TOPS	OIL.	
2 - 4		_		MATERIALS: Yellow, fine to coarse SAND and fine to eGRAVEL with Cobbles and Boulders. Debris estimate	
4 – 7.5			SAND & GRAVEL: Tan, fine to coarse SAND and fine to coarse GRAVEL with Cobbles and Boulders. Boulder at 6.5' - 7.5'		
				Bottom of Excavation 7.5' (Refusal)	
Pit Dimensions (Ft.) Length Width Depth	9 3 7.5		2) Gro	rks: t pit backfilled with excavated material. bundwater not encountered. bris noted: brick fragments, steel plate.	



			LEGI	III LOO		
Project: Proposed Family Dollar, New Bedford, MA				Project #: 141.06058		
TEST PIT IDENT	IFICATION:	TP4				
Location: Swift Str	eet & Orchard	Street		Ground Elevation: N	M	
Client: Hunt Real I	Estate			Datum: NA		
Contractor: Diversi	ified Developme	ent		Operator: Troy		
Equipment: CAT 3	03.5E CR			Samples Collected	Yes <u>X</u> No	
Capacity/Reach: 2.	5 cu. ft./9.5'			Time Started: 1140	Time Completed: 1230	
Weather: Mostly su	nny, breezy (N	E), 80s				
Logged by: CDD				Date: 9/5/14		
Checked by: JPJ				Date: 1/21/16		
		TEST	PIT IN	FORMATION		
Depth of Stratum Change Feet	Sample No. and Type	Sample Depth Feet	Soil Description			
0 - 1			TOPS	OIL		
1-8.5 fine to			fine to	LL MATERIALS: Yellow/brown, fine to coarse SAND and the to coarse GRAVEL with Cobbles and Boulders. Brick wall countered at 5'. Debris estimate 15%.		
				Bottom of Excavation 8.5' (Refusal)		
	-					
		*//				
Pit Dimensions (Ft.) Length Width Depth	8 4 8.5		2) Gro	t pit backfilled with exc undwater not encounter	red.	
	0.5		3) Debris noted: lumber, rebar, brick and concrete fragments, ash, cinders, glass.			



Project: Proposed Family Dollar, New Bedford, MA				Project #: 141.06058		
TEST PIT IDENT	TIFICATION:	TP5				
Location: Swift Str	reet & Orchard	Street		Ground Elevation: NM		
Client: Hunt Real	Estate			Datum: NA		
Contractor: Divers	ified Developm	ent		Operator: Troy		
Equipment: CAT 3	03.5E CR			Samples Collected	Yes <u>X</u> No	
Capacity/Reach: 2.	5 cu. ft./9.5'			Time Started: 1300 Time	e Completed: 1330	
Weather: Mostly su	ınny, breezy (N	E), 80s				
Logged by: CDD		E		Date: 9/5/14		
Checked by: JPJ	Checked by: JPJ			Date: 1/21/16		
		TEST	PIT IN	FORMATION		
Depth of Stratum Change Feet	Sample No. and Type	Sample Depth Feet	Soil Description			
0 – 1			TOPSOIL			
1 – 2			FILL M Stone.	MATERIALS: Tan, fine to coarse SAND and Crushed		
2 - 5			FILL M	L MATERIALS: Tan, fine to coarse SAND and fine to see GRAVEL. Debris estimate 15%.		
5 – 8.5 SAND				O & GRAVEL: Brown, fine to coarse SAND and fine to eGRAVEL with Cobbles and Boulders, little Silt.		
				Bottom of Excavation	8.5' (Refusal)	
Pit Dimensions (Ft.) Length Width Depth	8 3 8.5	7 1 Y	Ground	s: bit backfilled with excavated adwater not encountered. s noted: brick and concrete f		



			IESI.	PITLOG	
Project: Proposed l	Family Dollar, 1	New Bedford,	MA	Project #: 141.06058	3
TEST PIT IDENT	IFICATION:	TP6			
Location: Swift Str	eet & Orchard	Street		Ground Elevation: N	IM
Client: Hunt Real I	Estate			Datum: NA	
Contractor: Diversi	fied Developm	ent		Operator: Troy	
Equipment: CAT 3	03.5E CR			Samples Collected	_Yes <u>X</u> No
Capacity/Reach: 2.	5 cu. ft./9.5'			Time Started: 1330	Time Completed: 1350
Weather: Mostly su	nny, breezy (N	E), 80s			
Logged by: CDD				Date: 9/5/14	
Checked by: JPJ				Date: 1/21/16	
		TEST	PIT IN	FORMATION	
Depth of Stratum Change Feet	Sample No. and Type	Sample Depth Feet		Soil I	Description
0 - 1			TOPSC	DIL	
1 – 2			FILL M	ATERIALS: Brown, : GRAVEL, with Cobble	fine to coarse SAND and fine to s and Boulders.
2 - 3			FILL MATERIALS: Brown, fine to coarse SAND and fine to coarse GRAVEL, with Cobbles and Boulders Debris estimate 15%.		
3 - 5			FILL MATERIALS: Gray/Brown, fine to coarse SAND and fi to coarse GRAVEL. Concrete slab at 5'. Debris estimate 15%.		
				Bottom of Exca	avation 5' (Refusal)
Pit Dimensions (Ft.) Length Width Depth	9 7 5		2) Grou3) Debri	pit backfilled with exca ndwater not encountere	ed. alt, brick, and concrete fragments;



Desired D				rii LOG		
Project: Proposed Family Dollar, New Bedford, MA				Project #: 141.06058		
TEST PIT IDENT	IFICATION:	TP7				
Location: Swift Str	eet & Orchard	Street		Ground Elevation: NM		
Client: Hunt Real I	Estate			Datum: NA		
Contractor: Diversi	fied Developme	ent		Operator: Troy		
Equipment: CAT 3	03.5E CR			Samples Collected	Yes <u>X</u> No	
Capacity/Reach: 2.	5 cu. ft./9.5'			Time Started: 1350	Time Completed: 1410	
Weather: Mostly su	nny, breezy (N	E), 80s				
Logged by: CDD				Date: 9/5/14		
Checked by: JPJ				Date: 1/21/16		
		TEST	PIT IN	FORMATION		
Depth of Stratum Change Feet	Sample No. and Type	Sample Depth Feet		Soil Des	cription	
0 - 1			TOPSC	DIL		
1 – 2			FILL MATERIALS: Brown, fine to coarse SAND and fine to coarse GRAVEL with Cobbles and Boulders.			
2 – 4.5			FILL MATERIALS: Gray/Brown, fine to coarse SAND and fine to coarse GRAVEL. Debris estimate 15%. Concrete slab at 4.5'.			
			В	ottom of Excavation 4.5'	(Refusal on concrete slab)	
Pit Dimensions (Ft.) Length_ Width_ Depth_	10 7 4.5		2) Ground3) Debri	pit backfilled with excavated and water not encountered.	ted material. brick, and concrete fragments;	



			I LOI	III LOG	
Project: Proposed Family Dollar, New Bedford, MA			Project #: 141.06058		
TEST PIT IDENT	IFICATION:	TP201			
Location: Swift Str	reet & Orchard	Street		Ground Elevation: 1	4 +/-
Client: Hunt Real I	Estate			Datum: NA	
Contractor: N. Gor	nes			Operator: Nathan	
Equipment: CAT 3	20E			Samples Collected	Yes <u>X</u> No
Capacity/Reach: 16	5 ft	S.		Time Started: 9:00	Time Completed: 9:50
Weather: Overcast,	25 °F		7/		
Logged by: JPJ				Date: 1/12/16	
Checked by: JPJ				Date: 1/21/16	
		TEST	PIT IN	FORMATION	
Depth of Stratum Change Feet	Sample No. and Type	Sample Depth Feet	Soil Description		
0 - 1			TOPSO	DIL	
1 – 2.5			FILL M Silt, so	IATERIALS: Yellow- me Gravel.	brown, fine to coarse SAND, some
2.5 – 7.5			some G		fine to coarse SAND, some Silt, d boulders. Concrete slab at 7' to
7.5 – 12			FILL M	IATERIALS: Dark gra EL, with cobbles and b	ay, fine to coarse SAND and oulders. Debris estimate 15%.
12 – 14			SAND:	Brown fine to mediur	n SAND.
				Bottom of	Excavation 14'
Pit Dimensions (Ft.) Length Width Depth	20 8 14		2) Wa3) Del	et pit backfilled with exter seepage at 4 feet. pris noted: brick fragm	nents, brick, concrete fragments, tar paper, concrete slab.



TEST PIT LOG

			LLOI.	III LOG		
Project: Proposed Family Dollar, New Bedford, MA			Project #: 141.06058			
TEST PIT IDENT	IFICATION:	TP202				
Location: Swift Str	eet & Orchard	Street		Ground Elevation: 1	4 +/-	
Client: Hunt Real I	Estate			Datum: NA		
Contractor: N. Gor	nes			Operator: Nathan		
Equipment: CAT 3	20E			Samples Collected	Yes <u>X</u> No	
Capacity/Reach: 16	5 ft			Time Started: 9:50	Time Completed: 10:30	
Weather: Overcast,	25 °F					
Logged by: JPJ				Date: 1/12/16		
Checked by: JPJ				Date: 1/21/16		
		TEST	PIT IN	FORMATION		
Depth of Stratum Change Feet	Sample No. and Type	Sample Depth Feet		Soil	Description	
0 - 1			TOPSO	DIL		
1 – 3				MATERIALS: Yellow-me Gravel.	-brown, fine to coarse SAND, some	
3 – 12					fine to coarse SAND, some Silt, d boulders. Debris estimate 50%.	
				Bottom of Excavation 12'		
						
Pit Dimensions (Ft.) Length Width	10 10		2) Wate	pit backfilled with exc er seepage at 4' bgs.		
Depth	12		3) Debr foundat	ris noted: brick fragme tion blocks, scrap meta	ents, brick, concrete fragments,	

Y:\2014\141.06058\New Bedford MA FD\Geotech\Report\Revised Report 1-16\Appendix A\Test Pit Logs 1-12-16.docx



Project: Proposed Family Dollar, New Bedford, MA			Project #: 141.06058			
TEST PIT IDENT	IFICATION:	TP203				
Location: Swift Str	eet & Orchard S	Street		Ground Elevation: 14.5	+/-	
Client: Hunt Real I	Estate			Datum: NA		
Contractor: N. Gon	nes	\		Operator: Nathan		
Equipment: CAT 3	20E			Samples Collected	Yes <u>X</u> No	
Capacity/Reach: 16	5 ft			Time Started: 10:30	Time Completed: 11:00	
Weather: Overcast,	25 °F					
Logged by: JPJ				Date: 1/12/16		
Checked by: JPJ				Date: 1/21/16		
		TEST	PIT IN	FORMATION		
Depth of Stratum Change Feet	Sample No. and Type	Sample Depth Feet	Soil Description			
0 - 1			TOPS	OIL.		
1 – 2.5				MATERIALS: Yellow-brown, fine to coarse SAND, e Silt, some Gravel, with cobbles and boulders.		
2.5 – 4			some	MATERIALS: Yellow-brown, fine to coarse SAND, e Silt, some Gravel, with cobbles and boulders. Debris nate 20%		
4 - 6				O & GRAVEL: Brown, fine to coarse SAND, some Silt, gravel, with cobbles.		
				Bottom of Ex	scavation 6'	
Pit Dimensions (Ft.) Length Width Depth	6		 Wa Del 	rks: t pit backfilled with excava ter seepage at 5' bgs. oris noted: brick fragments trace plastic.		



				TI LOG	
Project: Proposed Family Dollar, New Bedford, MA			Project #: 141.06058		
TEST PIT IDENT	IFICATION:	ГР204			
Location: Swift Stre	eet & Orchard S	treet	22	Ground Elevation: 14.5	+/-
Client: Hunt Real E	Estate			Datum: NA	
Contractor: N. Gom	nes			Operator: Nathan	
Equipment: CAT 32	20E			Samples Collected	Yes <u>X</u> No
Capacity/Reach: 16	ft			Time Started: 11:00	Time Completed: 11:20
Weather: Overcast,	25 °F			a granding	
Logged by: JPJ				Date: 1/12/16	
Checked by: JPJ				Date: 1/21/16	
		TEST	PIT IN	FORMATION	
Depth of Stratum Change Feet	Sample No. and Type	Sample Depth Feet		Soil Des	cription
0 - 1			TOPS	OIL.	
1 – 4			FILL MATERIALS: Yellow-brown, fine to coarse SAND, some Silt, some Gravel, with cobbles and boulders. Debris estimate 5%.		
4 – 7			FILL MATERIALS: Dark brown, fine to coarse SAND, sor Silt, some Gravel, with cobbles and boulders. Debris estima 40%.		
7 - 10			SAND & GRAVEL: Gray, fine to coarse SAND, some Silt some Gravel.		
			В	ottom of Excavation 10' (F	Refusal, presumed bedrock)
Pit Dimensions (Ft.) Length Width Depth	23 6 10		2) Wa	st pit backfilled with excava ter seepage at 5.5' bgs. bris noted: rebar, brick and	



		<u>'</u>	LDII	II LOG			
Project: Proposed Family Dollar, New Bedford, MA				Project #: 141.06058			
TEST PIT IDENT	IFICATION:	TP205					
Location: Swift Stre	eet & Orchard S	Street		Ground Elevation: 13.5	+/-		
Client: Hunt Real E	Estate			Datum: NA			
Contractor: N. Gor	nes			Operator: Nathan			
Equipment: CAT 32	20E			Samples Collected	_Yes X No		
Capacity/Reach: 16	ft			Time Started: 11:20	Time Completed: 11:30		
Weather: Overcast,	25 °F						
Logged by: JPJ				Date: 1/12/16			
Checked by: JPJ				Date: 1/21/16			
		TEST	PIT INF	ORMATION			
Depth of Stratum Change Feet	Sample No. and Type	Sample Depth Feet		Soil Description			
0 – 1			TOPSO	IL			
1 – 6			FILL MATERIALS: Brown, fine to coarse SAND, some Silt, some Gravel, with cobbles and boulders. Debris estimate 5%.				
6 - 7			SAND & some Gi		e to coarse SAND, some Silt,		
				Bottom of Ex	xcavation 7'		
Pit Dimensions (Ft.) Length Width Depth	13 6 7		2) Wate	s: pit backfilled with excava r seepage at 6' bgs. is noted: brick, concrete,			



Project: Proposed Family Dollar, New Bedford, MA			Project #: 141.06058			
TEST PIT IDENT	IFICATION:	TP206				
Location: Swift Str	eet & Orchard	Street		Ground Elevation: 14 +/-	_ /*	
Client: Hunt Real I	Estate			Datum: NA		
Contractor: N. Gon	nes			Operator: Nathan		
Equipment: CAT 3	20E			Samples Collected	Yes <u>X</u> No	
Capacity/Reach: 16	5 ft			Time Started: 11:30	Time Completed: 12:00	
Weather: Overcast,	25 °F					
Logged by: JPJ				Date: 1/12/16		
Checked by: JPJ				Date: 1/21/16		
		TEST	PIT IN	FORMATION		
Depth of Stratum Change Feet	Sample No. and Type	Sample Depth Feet		Soil Desc	ription	
0 - 1			TOPSO	DIL		
1 – 2				MATERIALS: Yellow-brown, fine to coarse SAND, some ome Gravel.		
2 - 5			FILL MATERIALS: Brown, fine to coarse SAND, some Silt, some Gravel, with cobbles, boulders and Boulders. Debris estimate 20%.			
5 - 10			FILL M 75%.	MATERIALS: BRICK with	boulders. Debris estimate	
				Bottom of Excavati	on 10' (Refusal)	
					3	
Pit Dimensions (Ft.) Length_ Width_ Depth_	15 8 10		2) Wate	ss: pit backfilled with excavate er seepage at 6' bgs. ris noted: brick, scrap meta		



Project: Proposed Family Dollar, New Bedford, MA				Project #: 141.06058		
TEST PIT IDENT	IFICATION:	TP207				
Location: Swift Str	eet & Orchard	Street		Ground Elevation: 14 +/-		
Client: Hunt Real I	Estate			Datum: NA		
Contractor: N. Gon	nes			Operator: Nathan		
Equipment: CAT 3	20E			Samples Collected	Yes <u>X</u> No	
Capacity/Reach: 16	5 ft			Time Started: 12:00	Time Completed: 12:20	
Weather: Overcast,	25 °F					
Logged by: JPJ				Date: 1/12/16		
Checked by: JPJ			Z Fac	Date: 1/21/16		
		TEST	PIT IN	FORMATION		
Depth of Stratum Change Feet	Sample No. and Type	Sample Depth Feet		Soil Descr	ription	
0 – 1			TOPSO	DIL		
1 – 2.5				L MATERIALS: Brown, fine to coarse SAND, some Silt, ne Gravel, with cobbles.		
2.5 – 5			Silt, so		fine to coarse SAND, some d boulders. Debris estimate	
5 - 7			SAND some G	& GRAVEL: Brown, fine travel.	to coarse SAND, some Silt,	
				Bottom of Exc	eavation 7'	
Pit Dimensions (Ft.)			Remark	TS:		
Length Width Depth			1) Test 2) Wate 3) Debr	pit backfilled with excavate or seepage at 5' bgs. is noted: brick fragments, of teel pipe, tar paper.		



Soil Classification Terms

Grain Size			
Material	Fraction	Sieve Size	
Boulders		12" +	
Cobbles		3"-12"	
Gravel	coarse	3/4"-3"	
	fine	No. 4 to 3/4"	
Sand	coarse	No. 10 to No. 4	
	medium	No. 40 to No. 10	
	fine	No. 200 to No. 40	
Fines		Passing No. 200	
(Silt & Clay)			

Identification of soil type Is made on the basis of an estimate of particle sizes, and in the case of fine-grained soils, also on basis of plasticity.

Coarse and Fine Grained Soils		
Descriptive Adjective	*Percentage Requirement	
Trace	1–10%	
Little	10-20%	
Some	20-35%	
And	35-50%	

When sampling gravelly soils with a standard split spoon, the true percentage of gravel is often not recovered due to the relatively small sampler diameter.

Standard Penetration Value (N) & Undrained Shear Strength (Su) v. Relative Density & Consistency

GRANULAR SOILS			
N	Relative Density (%)		
0–4	Very Loose (0-15)		
4–10	Loose (15-35)		
10–30	Medium Dense (35-65)		
30–50	Dense (65-85)		
>50	Very Dense (>85)		

COHESIVE SOILS				
S _u (psf)	N	Consistency		
<250	<2	Very Soft		
250 to 500	2–4	Soft		
500 to 1,000	4–8	Medium		
1,000 to 2,000	8–15	Stiff		
2,000 to 4,000	15–30	Very Stiff		
>4,000	>30	Hard		

Consistency of cohesive soils is based upon undrained shear strength determined from field vane shear, pocket penetrometer, torvane, or laboratory tests. Consistency of cohesive soils is based upon the N-value when no other data is available.

^{*}Percentage measured by weight.



Rock Classification Terms

	Weathering Classification			
Grade	Symbol	Diagnostic Features		
Fresh	F	No visible sign of decomposition or discoloration. Rings under hammer impact.		
Slightly Weathered	WS	Slight discoloration inwards from open fracture, otherwise similar to F.		
Moderately Weathered	WM	Discoloration throughout. Weaker mineral such as feldspar decomposed. Strength somewhat less than fresh rock but cores can not be broken by hand or scraped by knife.		
Highly Weathered	WH	Most minerals somewhat decomposed. Specimens can be broken by hand with effort or shaved with knife. Core stones present in rock mass. Texture becoming distinct but fabric.		
Completely Weathered	WC	Minerals decomposed to soil but fabric and structure preserved (Saprolite). Specimens easily crumbled or penetrated.		
Residual Soil	RS	Advanced state of decomposition resulting in Plastic soils. Rock fabric and structure completely destroyed. Large volume change.		


	Rock	Descriptors		
Term		Meaning		
Hardness	Soft	Scratched by fingernail		
	Medium Hard	Scratched easily b	y penknife	
	Hard	Scratched with diff penknife	iculty by	
Very Hard		Cannot be scratched by penknife		
Jointing/	Slight	2 to 6 ft. spacing		
Fractures	Moderate	8in. to 2 ft.		
	High	2 in. to 8 in.		
	Intense	< 2in.		
Bedding	Laminated	(< 1")	Natural Break	
	Thin Bedded	(1" - 4")	in Rock	
	Bedded	(4" - 12")	Layers	
	Thick Bedded	(12" - 36")		
	Massive	(> 36")		




Unified System Classification of Soils (ASTM D 2487)

Major Divisions		Group Symbols	Typical Names	
sieve	Gravels 50% or more of coarse fracton retained on No. 4 sieve	Clean Gravels	GW	Well-graded gravels and gravel-sand mixtures, little or no fines.
			GP	Poorly graded gravels and gravel-sand mixtures little or no fines.
oils No. 200	Gravels or more of on retained 4 sieve	vels	GM	Silty gravels, gravel-sand-silt mixtures.
ined Si ed on I	50% fract	Gravels w/ Fines	GC	Clayey gravels, gravel-sand-clay mixtures.
Coarse-Grained Soils More than 50% retained on No. 200 sieve	arse 5. 4	an	SW	Well-graded sands and gravelly sands little or no fines.
Coa han 50%	ds 0% coa ses No	Clean Sands	SP	Poorly graded sands and gravelly sands little or no fines.
More t	Sands More than 50% coarse fraction passes No. 4	s w/	SM	Silty sands, gravel-sand-silt mixtures.
		Sands w/ Fines	sc	Clayey sands, sand-clay mixtures.
φ	Silts and Clays Liquid Limit 50% or less		ML	Inorganic silts, very fine sands, rock flour.
s 200 siev			CL	Inorganic clays of low plasticity, gravelly clays, sandy clays, silty clays.
ed Soils			OL	Organic silts and organic silty clays of low plasticity.
Fine-Grained Soils nore passes No. 20	Silts and Clays Liquid limit greater than 50%		МН	Inorganic silts, micaceous or diatomaceous fine sands or silts, elastic silts
Fine-Grained Soils 50% or more passes No. 200 sieve			СН	Inorganic clays of high plasticity, fat clays.
20%	Silts Liquid	≨	ОН	Organic clays of medium to high plasticity.
ighly Organic	Soils		Pt	Peat, mulch and other highly organic soils


ATTACHMENT C PHOTOS



Looking southwesterly into the site



Looking southerly on Orchard with the site to the right and Howland Place in the distance



Looking northwesterly into the site



CIVIL ENGINEERING • LAND SURVEYING ENVIRONMENTAL ASSESSMENT

November 17, 2016

New Bedford Planning Board 133 William Street New Bedford, MA 02740

RE: PROPOSED FAMILY DOLLAR STORE SW CORNER OF ORCHARD AND SWIFT STREETS

Dear Board Members,

On behalf of Hunt Real Estate Services, Inc., we hereby submit the enclosed package for Site Plan Review and Special Permit for a proposed retail store. The submittal package consists of the following:

- This letter;
- The executed application forms;
- The application checklists;
- A check for \$400 which is the submittal fee:
- A check for \$200 for South Coast Media Group;
- 4 sets of full size plans and twelve 11"x17" plans, folded;
- 17 copies of the Impact Report which includes the estimated cost of site work, Traffic Impact and Access Study;
- A CD disk of the drawings in PDF format (CAD format will be submitted after Planning input has been received);
- 5 certified abutters lists and a copy of the abutters notice;
- 5 copies of the deed (proof of ownership) and
- 17 copies of the Stormwater Report.

It is proposed that the facility will be constructed between March and September 2017. Historically, the site was entirely covered by a building, that is, the lot had complete impervious cover. Since the proposed development will have less impervious cover, the rate of storm runoff will be less. We hereby request that the need for stormwater detention be waived. We also request that we not be required to have the plans on NVGD 29 datum. A determination has been made that the plan as presented complies with ADA regulations.

Sincerely,

PRIME ENGINEERING, INC.

Richard J. Rheaume, P.E., LSP

Chief Engineer

ATTACHMENT 5



City of New Bedford REQUEST FOR WAIVER

Case 38-16, 39-16 & 40-16 11/18/2016

APPLICATION FOR WAIVER FROM SITE PLAN REVIEW REQUIREMENTS

In certain instances, after consulting with the City Planner, the applicant may submit, in writing, a request for walver for any of the submittal or technical requirements of Section 5430 and 5440 where the project involves relatively simple development plans. The Planning Board will take a separate vote on written walver requests by the applicant. Each request for walver must be submitted individually to be considered by the Board. Please provide one (1) original and fifteen (15) copies of the request.

Any granted waivers must be disclosed on the final submitted and approved site plan.

SUBJECT PROPERTY	计分钟记录	111111	1844 P. 1961	hi isil	经保险银度的	Dealth Ceangailte
ASSESSOR'S MAP PL	.OT#	23	LOT(S)#	292		
REGISTRY OF DEEDS	воок:	7223	PAGE #	263		
PROPERTY ADDRESS	SW corner	of Swift and	d Orchard St	reets		
ZONING DISTRICT: N	/lixed use bu	siness				
OWNER INFORMAT	ION					Barah ulbah abbah ubah
NAME: Clark's Cove	Developmen	nt Co., LLC				
MAILING ADDRESS:	651 Orchard	Street, New	Bedford, M.	A 0274	9	
APPLICANT/CONTAC					等书才等 等	
NAME (IF DIFFERENT	「): Hunt Real	Estate Serv	ices, Inc.			
APPLICANT'S RELATION Check one:	ONSHIP TO T	HE PROPER	TY: O\	VNER	CONTRACT VENDEE	OTHER Describe Proposed buye
MAILING ADDRESS (I	F DIFFERENT	^{*):} 5100 W K	ennedy Blvd	l., Suite	100, Tampa, F	L 33609
TELEPHONE #	727 458-40	55				
EMAIL ADDRESS:	khess@hun	tresco.com				
urther understand that pproval(s). If petition i	t any false in s granted, I/v	formation in we understar hat the waive	itentionally p nd the appro	rovided vals are noted o	or omitted is a specific to the	e best of my/our knowledge. I/v grounds for the revocation of t plans submitted, unless the Boa tite Plan and acted upon within o

If the applicant differs from the owner, this section must be completed/signed by the property owner/s:

I hereby authorize the applicant represented above and throughout this application to apply and to represent my/our interests on my/our behalf for the relief requested herein for the premises I/we own noted as "property address" above and presented throughout this application. Furthermore, by signing this application I/we acknowledge having read and understood this application and the accompanying instructions and information. If petition is granted, I/we understand the approvals are specific to the plans submitted, unless the Board states otherwise and that if granted, that the waiver(s) must be noted on the approved Site Plan and acted upon within one year.

Signature of Owner/s

Newsger

11/13/16

Date

		Ordinance Section	CLEARLY Describe why this request is being made.
		Example	***Example***
	1 .	5451. b. Topography and Drainage Plan	There currently exists a structure and pavement on the site. No excavation of the site is being proposed, therefore topography and drainage will not be altered.
PTION	2	Checklist for Layout Plan: Showing proposed grading and spot shots.	Not required by ordinance and it would make the plan too busy. The Grading Plan shows all grading information.
DESCRIPTION	3	Checklist for Layout Plan: Showing areas of cut and fill.	Not required by ordinance and it would make the plan too busy. The Grading Plan shows all cut and fill information.
	4	Checklist for Existing Conditions Plan: Topography based on NGVD 29	Not required by ordinance. Floodplain is based on NAVD 88 which is a different datum.

Additional pages describing the waiver request may be attached to this form following the same chart format, if necessary.

1	Please check here if additional pages are attached.	
1	Number of Waiver requests submitted for consideration:	6

If the applicant differs from the owner, this section must be completed/signed by the property owner/s:

I hereby authorize the applicant represented above and throughout this application to apply and to represent my/our interests on my/our behalf for the relief requested herein for the premises I/we own noted as "property address" above and presented throughout this application. Furthermore, by signing this application I/we acknowledge having read and understood this application and the accompanying instructions and information. If petition is granted, I/we understand the approvals are specific to the plans submitted, unless the Board states otherwise and that if granted, that the waiver(s) must be noted on the approved Site Plan and acted upon within one year.

Signature of Owner/s

The approved Site Plan and acted upon within one year.

11/13/14

Date

		Ordinance Section	CLEARLY Describe why this request is being made.
		Example	***Example***
1	1	5451. b. Topography and Drainage Plan	There currently exists a structure and pavement on the site. No excavation of the site is being proposed, therefore topography and drainage will not be altered.
-	2	Plans in general on checklist: Electronic CAD and PDF.	Not required by ordinance. It will be submitted once Planning Board input is received.
NOITAI	2		
DESCRIPTION	3	Plans in general on checklist: North arrow pointing up the page.	Not required by ordinance. Orchard Street is main throughfare.
	4	5454 drainage calculations	The site was totally impervious and will have 30% pervious cover so the runoff will be much less than before.

Additional pages describing the waiver request may be attached to this form following the same chart format, if necessary.

1	Please check here if additional pages are attached.	
1	Number of Waiver requests submitted for consideration:	6

OUITCLAIM DEED

THE GOODYEAR TIRE & RUBBER COMPANY., a corporation organized and existing under the laws of the State of Ohio, with a principal place of business in Akron, Ohio,

for consideration paid, and in full consideration of ONE MILLION FIVE HUNDRED FIFTY THOUSAND AND NO/100 (\$1,550,000.00),

grants to CLARK'S COVE DEVELOPMENT CO., LLC, a Massachusetts Limited Liability Company with a usual place of business located at 651 Orchard Street, Suite 200, New Bedford, MA 02744,

land in New Bedford,

Beginning at the northwesterly corner thereof at the intersection of Bolton Road and Swift Street; thence running easterly by said Swift Street four hundred forty-five (445) feet, more or less, to Orchard Street; thence running southerly by said Orchard Street nine hundred eighty and eighty one-hundredths (980.80) feet to property now or formerly of the Gosnold Mills; thence running westerly at an interior angle of eighty-nine degrees fifty-one minutes (89° 51') by said Gosnold Mills land in part through the center of a brick wall five hundred forty-one and eighty-three one-hundredths (541.83) feet, more or less, to said Bolton Road; and thence running northerly by said Bolton Road about nine hundred eighty-five (985) feet to the point of beginning.

Together with all the right, title and interest of the Grantor in, to and concerning a certain twenty-four inch (24") pipe, commencing at the dividing line between the above-described parcel and said land of the Gosnold Mills property and running through said land of the Gosnold Mills property through Orchard and Cove Streets; thence through a twenty (20) foot strip of land to and into the water of Clark's Cove to a certain well or structure therein situated, particularly including herein all the right, title and interest of the Grantor in and to said twenty (20) foot strip of land and said well or structure and all other rights included or specified in, and subject to the obligations contained in, two certain instruments from the New England Cotton Yarn Company to and with Lawrence A. Ford, both dated August 14, 1902 and respectively recorded with said Bristol County, South District Registry of Deeds, Book 228, Pages 286 and following and Book 228, Pages 294 and following.

Subject to and with the benefit of easements and restrictions of record insofar as they may be in full force and effect.

Being the same premises conveyed Grantor by deed dated December 31, 1956 and recorded in the Bristol County (S.D.) Registry of Deeds in Book 1209, Page 100.

This sale does not constitute substantially all of the assets of said Corporation.

217.50 13500

217.509

363.76

IN WITNESS WHEREOF, the said GOODYEAR TIRE & RUBBER COMPANY, has caused its corporate seal to be hereto affixed and these presents to be signed, acknowledged, and delivered in its name and behalf by AJDELGUYD its DIRECTOR - REAL ESTATE, hereto duly authorized, this LITL day of October 2004.

Signed and sealed in presence of

THE GOODYEAR TIRE & RUBBER COMPANY


By: A J DEI GUYD

DIRECTOR - REAL ESTATE

THE COMMONWEALTH OF MASSACHUSETTS

STATE OF OHIO COUNTY OF SUMMIT BRISTOL, SS.

October 11, 2004



REG OF DEEDS REG #07 BRISTOL S

10/15/04 10:20AM 01 000000 #1428

FEE

\$7068.00

CASH \$7068_00

Official Signature of Notary
My commission expires:
May

JOYCE LEE GOROG, Notary Public Residence - Summit County State Wide Jurisdiction, Ohio My Commission Expires May 22, 2007

CERTIFICATION

I, the undersigned, Bertram Bell, Assistant Secretary of The Goodyear Tire & Rubber Company, a corporation organized and existing under the laws of the State of Ohio, do hereby certify that the attached is a full, true and correct copy of the Delegation of Authority to the Director Real Estate and to the Manager Real Estate Services dated July 1, 2004 signed by Robert J Keegan, Chairman of the Board, Chief Executive Officer and President, and attested by Bertram Bell, Assistant Secretary, of said corporation.

And I further certify that the attached Delegation of Authority has been neither revoked nor modified and is in full force and effect at the date hereof.

And I further certify that my examination of the applicable records of said corporation on the date hereof reveals that Anthony J Delguyd is the Director, Real Estate and that Steve A Mikolay is the Manager, Real Estate Services of The Goodyear Tire & Rubber Company and is authorized to sign documents specified in the attached Delegation of Authority.

IN WITNESS WHEREOF, I have hereunto set my hand and caused the corporate seal of said The Goodyear Tire & Rubber Company to be affixed this 22nd day of September, 2004.

Assistant Secretary

THE GOODYEAR TIRE & RUBBER CO

The Goodyear Tire & Rubber Company

Akron, Ohio 44316-0001

July 1, 2004

DELEGATION OF AUTHORITY

TO WHOM IT MAY CONCERN:

Pursuant to authority vested in me by resolution adopted by the Board of Directors of The Goodyear Tire & Rubber Company (hereinafter referred to as the "Company"), on August 3, 1999, I hereby authorize the

DIRECTOR REAL ESTATE MANAGER REAL ESTATE SERVICES

of the Company to execute for and on behalf and in the name of the Company, without attestation and without affixation of the corporate seal, any lease or sublease of real property (including oil, gas and mineral rights) or agreements (including deeds and related instruments) for the purchase or sale of real property for use and operation as or incidental to a distribution or production facility of The Goodyear Tire & Rubber Company, including easements, access and license agreements, and amendments to any of the foregoing, provided that such shall fall within the following categories:

- Subleases of lease-controlled vacant properties, and including subleases to dealers and franchisees and leases of Company-owned properties.
- Leases and subleases where the base term does not exceed twenty (20) years and base rental does not exceed \$500,000.00 per lease year (net to lessor).
- 3. Office leases where the base term does not exceed ten (10) years and the base rental does not exceed \$500,000.00 per lease year.
- 4. Lease and sublease assignments.
- 5. Listing Agreements with brokers to sell, lease or sublease properties at a commission rate not to exceed 10 percent.
- 6. Recreational area (baseball fields, Goodyear Theater, etc), farm land and/or pasture land leases and license agreements on plant sites wherein the term does not exceed five (5) years (cancelable by Goodyear at any time upon 30 days' notice to tenant) at the highest rental reasonably obtainable.

- 7. Oil, gas or mineral leases wherein the total expenditure does not exceed \$50,000.00.
- 8. Purchase of individual properties in an amount not to exceed \$3,000,000.00.
- 9. Sale or leasing of surplus property.
- 10. Real Estate License Agreements.
- 11. Easement Agreements.
- 12. Certification of lease terms, conditions and status to lessors or third parties.
- 13. Agreements for the subordination of leases and subleases.
- 14. Settlement and release agreements relating to Goodyear leased and fee-owned property.

In exercising the authority granted within this letter, they are directed to observe such instructions as to prior approvals, including, approval by the Law Department and, where commitments are involved, have an approved budget as shall have been prescribed by the executive officer of the Company having cognizance of the subject matter

The documents listed above will be retained in the Contract Records Department of the Secretary's Office.

This Delegation shall be in full force and effect from July 1, 2004 to and including June 30, 2006 unless theretofore revoked, and cancels and supersedes a similar delegation dated July 1, 2002.

IN WITNESS WHEREOF, I have hereunto set my hand and caused the official corporate seal of said Company to be affixed.


Chairman of the Board,

Chief Executive Officer and President


THE GOODYEAR TIRE & RUBBER COMPANY

Attest:

Assistant Secretary







NOTICE OF ACTIVITY AND USE LIMITATION M.G.L. c. 21E, § 6 and 310 CMR 40.0000

Disposal Site Name: 545 Orchard Street, New Bedford, MA

DEP Release Tracking No.(s): 4-00688

This Notice of Activity and Use Limitation ("Notice") is made as of this 774 day of ____, 2005, by Clarks Cove Development Company, LLC, 651 Orchard Stree;, Suite 200, New Bedford, MA 02744, together with his/her/its/thei: successors and assigns (collectively "Owner").

WITNESSETH:

WHEREAS, Clarks Cove Development Company, LLC, is the owner in fee simple of that certain parcel of vacant land located in New Bedford, Bristol (South) County, Massachusetts, pursuant to a deed recorded with the Bristol (South) County Registry of Deeds in Book 7223, Page 263;

WHEREAS, said parcel(s) of land, which is more particularly bounded and described in Exhibit A, attached hereto and made a part hereof ("Property") is subject to this Notice of Activity and Use Limitation. The Property is shown on [a plan recorded in the Bristol County Registry of Deeds in Plan Book Arrached 19, Plan 2;

WHEREAS, the Property comprises all of a disposal site as the result of a release of oil and/or hazardous material. Exhibit B is a sketch plan showing the relationship of the Property subject to this Notice of Activity and Use Limitation to the boundaries of said disposal site existing within the limits of the Property and to the extent such boundaries have been established. Exhibit B is attached hereto and made a part hereof; and

WHEREAS, one or more response actions have been selected for the Disposal Site in accordance with M.G.L. c. 21E ("Chapter 21E") and the Massachusetts Contingency Plan, 31) CMR 40.0000 ("MCP"). Said response actions are based upon (a) the restriction of human access to and contact with oil and/or hazardous material in soil and/or (b) the restriction of certain activities occurring in, on, through, over or under the Property. The basis for such restrictions is set forth in an Activity and Use Limitation Opinion ("AUL Opinion"), dated 8/25/2005, (which is attached hereto as Exhibit C and made a part hereof);

NOW, THEREFORE, notice is hereby given that the activity and use limitations set forth in said AUL Opinion are as follows:

1. Activities and Uses Consistent with the AUL Opinion. The AUL Opinion provides that a condition of No Significant Risk to health, safety, public welfare or the environment exists for any foreseeable period of time (pursuant to 310 CMR 40.0000) so long as any of the following activities and uses occur on the Property:

PLEASE RETURN TO:

The language in these forms are part of promulgated regulations and cannot be modified The Way noted (within brackets) in the form itself. BOSTON, MA 02110 ATW FILE NO.

- (i) Maintenance of the property as an unpaved, vacant lot. The permitted use of the Property as an unpaved vacant lot is contingent upon the Property being enclosed with a secure fence or wall which will prevent access to the Property by all persons with the exception of the Owner and his/her/its agents for inspection or maintenance activities at the Property;
- (ii) Construction activities and underground utility repair, including soil excavation and regarding activities, provided a Soils Management Plan and Health and Safety Plan is implemented prior to the commencement of such activities;
- (iii) Commercial and industrial activities and uses provided that the Property remains entirely covered with any of the following structures or materials or any combination of the following structures or materials; (1) a building foundation with a concrete floor, (2) an impervious surface such as concrete or asphalt pavement, (3) greater then three (3) feet of clean fill placed upon the ground surface at the existing ground elevation with landscaped vegetation
- (iv) Such other activities or uses which, in the Opinion of an LSP, shall present no greater risk of harm to health, safety, public welfare or the environment than the activities and uses set forth in this Paragraph; and
- (v) Such other activities and uses not identified in Paragraph 2 as being Activities and Uses Inconsistent with the AUL.
- 2. Activities and Uses Inconsistent with the AUL Opinion. Activities and uses which are inconsistent with the objectives of this Notice of Activity and Use Limitation, and which, if implemented at the [Property] [Portion of the Property], may result in a significant risk of harm to health, safety, public welfare or the environment or in a substantial hazard, are as follows:
 - (i) Residential, agricultural, outdoor and indoor recreational or institutional activities and uses (institutional activities and uses inconsistent with the AUL Opinion are specifically associated with daycare centers, schools, orphanages and educational facilities);
 - (ii) Commercial/industrial use in the absence of barriers identified in 1(iii); and
 - (iii) Excavation of and exposure to Property soils with the exception of future construction/site development activities and short duration excavation for the purposes of underground utility repairs or installation.
 - 3. Obligations and Conditions Set Forth in the AUL Opinion. If applicable, obligations and/or conditions to be undertaken and/or maintained at the Property to maintain a condition of No Significant Risk as set forth in the AUL Opinion shall include the following:
 - (i) As an unpaved, vacant lot, obligations and conditions set forth in the AUL Opinion to

The language in these forms are part of promulgated regulations and cannot be modified in any way unless so noted (within brackets) in the form itself.

be undertaken and/or maintained at the Property include indefinite maintenance of a secure fence or wall which will prevent access to the Property by all persons with the exception of the Owner and his/her/its agents for inspection or maintenance activities at the property;

- (ii) During any construction/site development activities, obligations and conditions set forth in the AUL Opinion to be undertaken and/or maintained at the Property include: maintenance of a secure fence or wall which will prevent access to Property soils by all persons with the exception of the Owner and his/her/its agents and construction/site development workers; the implementation of a Soil Management Plan under the direction of a Licensed Site Professional; and implementation of a Health and Safety Plan prepared by a certified industrial hygienist.; and
- (iii) During any commercial and industrial activities and uses at the Property, the Property must remain entirely covered with the structures or materials identified in a (iii) indefinitely except to conduct construction/site development activities or short term utility repairs.
- 4. Proposed Changes in Activities and Uses. Any proposed changes in activities and uses at the Property which may result in higher levels of exposure to oil and/or hazardous material than currently exist shall be evaluated by an LSP who shall render an Opinion, in accordance with 310 CMR 40.1080 et seq., as to whether the proposed changes will present a significant risk of harm to health, safety, public welfare or the environment. Any and all requirements set forth in the Opinion to meet the objective of this Notice shall be satisfied before any such activity or use is commenced.
- 5. <u>Violation of a Response Action Outcome</u>. The activities, uses and/or exposures upon which this Notice is based shall not change at any time to cause a significant risk of narm to health, safety, public welfare, or the environment or to create substantial hazards due to exposure to oil and/or hazardous material without the prior evaluation by an LSP in accordance with 310 CMR 40.1080 et seq., and without additional response actions, if necessary, to achieve or maintain a condition of No Significant Risk or to eliminate substantial hazards.

If the activities, uses, and/or exposures upon which this Notice is based change without the prior evaluation and additional response actions determined to be necessary by an LSP in accordance with 310 CMR 40.1080 et seq., the owner or operator of the Property subject to this Notice at the time that the activities, uses and/or exposures change, shall comply with the requirements set forth in 310 CMR 40.0020.

6. <u>Incorporation Into Deeds, Mortgages, Leases, and Instruments of Transfer.</u> This Notice shall be incorporated either in full or by reference into all future deeds, easements, mortgages, leases, licenses, occupancy agreements or any other instrument of transfer, whereby an interest in and/or a right to use the Property or a portion thereof is conveyed.

Owner hereby authorizes and consents to the filing and recordation and or registration of this Notice, said Notice to become effective when executed under sexi by the under signed LSP, and recorded and/or registered with the appropriate Registry(ies) of Deeds and/or Land Registration Office(s).

The language in these forms are part of promulgated regulations and cannot be modified τ any way unless so noted (within brackets) in the form itself.

	, .						
WITNESS	the executi	on hereof under	seal this	704	day of	July	, 2005.
MATTITOD	CITO . STATE TO THE						

Clarks Cove Development Company, LLC

John E. Williams, Manager

[COMMONWEALTH OF MASSACHUSETTS] [STATE OF____]

	_					
i.		•		July 7	, 2005	
Bristol, ss		*				
			Williams Mone	ger and acknow	ledged the	
Then personally	appeared the above	-named John E.	Williams, Ivialia	ny hefore me		
Then personally foregoing instrument to be the	ne free act and deed	of said Limited	Liability Compa	iny octors inc,	E) lasta	
1010601118 111111			>	ma .D.	C Comy	1
•	· :'.	william EA	RY	700C	D O'LOSTY	,
	Ŗ	WIND SON EXP	IRES . NO	tary Public: Sar	a B. O'Leary	205
		Z 7 200	My	Commission E	xpires: 12-02-20	303
		A SO W	W SS		. 1 77	
mi danaian o	d LSP hereby certif	ies that the sh	kecinted the a	foresaid Activi	ty and Use	
The undersigned	harata as Evhibit (and made a Da	attered and tha	t in [his][her] O	pinion this	
Limitation Opinion attached	Limitation is con	cictent with the	Herms set forth	in said Activit	y and Use	
The undersigned Limitation Opinion attached Notice of Activity and Use	Limitation is con	NO	TARmin	ř		
Limitation Opinion.						(e*
	,			t Hus	CONTRADADAMA	
Date:	•		Jober	1 1000	CHIHOFMASC	1
	# X		Name of LSF	07	ROBERT	SE VE
			Mame or res	J	W.	1818
790			[LSP SEA	י נינו	8 NICOLORO	छ
	1%	;,			No. 4290	
	[COMMONWEAL	LTH OF MASS	ACHUSETTS	*1	CA CISTER	
	ISTATE OF	hew-Ha	upslike	:	SITE PROFE	
,				S 1 2	2006	
	CKOLKEL	ghan C		Jept 50	, 2005	
, SS		0	\mathcal{O}			
	y appeared the ab	ove named	and ac	knowiedged th	e foregoing.	
Then personal	y appeared the de	foré me		C est		an
instrument to be [his][her] f	ree act and deed of	10101110,			~ C	X
T.				No ary Public	Soro Di O	77
				My Cominiss	on axpires 12-9	2-200
1	**			1 2	1.5000	7 = 20
Upon recording, return to:	<u>;</u> v	¥	*			きの機能
; ~						S. Comment
Clarks Cove Development	Company, LLC				WHEN HE	AND THE
c/o John E. Williams, Man	ager			*	The state of the s	ä.
651 Orchard Street, Suite 2	: 00	261		Ø 5 0	25. 250.	
New Bedford, MA 02744	95 g	•				
New Bediord, Will 627	``		(*)		•	
	1 - 1 -	w.		*		
	17,					
	•			10		20
•						
	: 1				g#c	
	i Ex					

The language in these forms are part of promulgated regulations and cannot be modified in any way unless so noted (within brackets) in the form itself.

EXHIBIT A

Legal Description of the Property

The following Metes & Bounds are to describe the Property located at 545 Orchard Street

Beginning at the northwesterly corner thereof at the intersection of Bolton Road and Swift Street; thence running easterly by said Swift Street four hundred forty-five (445) feet, more or less, to Orchard Street; thence running southerly by said Orchard Street nine hundred eighty and eighty one-hundredths (980.80) feet to property now or formerly of the Gosnold Mills; thence running westerly at an interior angle of eighty-nine degrees fifty-one minutes (89° 51') by said Gosnold Mills land in part through the center of a brick wall five hundred forty-one and eighty-three one-hundredths (541.83) feet, more or less, to said Bolton Road; and thence running northerly by said Bolton Road about nine hundred eighty-five (985) feet to the point of beginning.

EXHIBIT B

EXHIBIT C

EXHIBIT C

ACTIVITY AND USE LIMITATION OPINION

In accordance with the requirements of 310 CMR 40.0174, this Activity and Use Limitation Opinion has been prepared for a parcel of land owned by Clarks Cove Development, LLC, and located at 545 Orchard Street, New Bedford, Bristol County, Massachusetts. The Site is approximately 11 acres with no structures and is situated approximately 1,500 feet northwest of Clarks Cove within a high density, mixed urban residential/commercial/industrial zone. The property is graded as an open field lot and is completely fenced.

Site History

The Site is a former manufacturing location first developed as a textile mill in the early 1890's by American Cotton Fabric Corporation. The Goodyear Tire & Rubber Company (Goodyear) purchased the mill in the 1920s for the manufacture of rubber tires and specialty rubber products. The property is located in New Bedford, Massachusetts and is bordered to the north by Swift Street, to the east by Orchard Street, to the west by Bolton. Street, and to the south by Howland Place Retail Mall complex. Goodyear conducted facility decommissioning activities following the closure of the plant and removal of v. operations and equipment. Decommissioning activities included the removal by demolition of all structures on the property and preparation of the property for sale and future redevelopment. During the course of decommissioning activities, it was discovered that lubricating oils from machinery had been released to soil and groundwater at the Site. Short Term measures were conducted at the site and Phase II Activities were initiated. The assessment activities completed at the Site indicated that lead, petroleum hydrocarbons, polycyclic aromatic hydrocarbons and volatile organic compound residuals were present in the soil and groundwater at the Site. Furthermore, based on the results of additional Phase II activities conducted in 1999, oil and/or hazardous materials were determined not to be migrating from the Site. Furthermore, it was concluded that no uncontrolled sources remain at the Site. Concentrations of OHM on-site were determined to be below S-2 soil standards and below GW-2 groundwater standards and in certain location on-site below GW-1 standards.

Reason for Activity and Use Limitation

An AUL is required to achieve and maintain a condition of No Significant Risk on the subject Property. In addition, the implementation of the AUL is being used to provide notice of the existence of contamination to future holders of an interest(s) in the subject Property, and to place additional conditions on Site uses.


Permitted Activities and Uses Set Forth in the AUL Opinion

- (i) Maintenance of the property as an unpaved, vacant lot. The permitted use of the Property as an unpaved vacant lot is contingent upon the Property being enclosed with a secure fence or wall which will prevent access to the Property by all persons with the exception of the Owner and his/her/its agents for inspection or maintenance activities at the Property.
- (ii) Construction activities and underground utility repair, including soil excavation and regarding activities, provided a Soils Management Plan and Health and Safety Plan is implemented prior to the commencement of such activities;
- (iii) Commercial and industrial activities and uses provided that the Property remains entirely covered with any of the following structures or materials or any combination of the following structures or materials; (1) a building foundation with a concrete floor, (2) an impervious surface such as concrete or asphalt pavement, (3) greater then three (3) feet of clean fill placed upon the ground surface at the existing ground elevation with landscaped vegetation; and
- (iv) Such other activities or uses which, in the Opinion of an LSP, shall present no greater risk of harm to health, safety, public welfare or the environment than the activities and uses set forth in this Paragraph.

Activities and Uses Inconsistent with the AUL Opinion

- (i) Residential, agricultural, outdoor and indoor recreational or institutional activities and uses (institutional activities and uses inconsistent with the AUL Opinion are specifically associated with daycare centers, schools, orphanages and educational facilities);
- (ii) Commercial/industrial use in the absence of barriers identified above; and
- (iii) Excavation of and exposure to Property soils with the exception of future construction/site development activities and short duration excavation for the purposes of underground utility repairs or installation.

LSP Signature: Plus Mederce	LSP Seal ROBERT
Date: 8-27-2005	W. NICOLORO No. 4290
License Number: 4290	SITE PROTES




,			

PROPOSED FAMILY DOLLAR RETAIL STORE

ORCHARD STREET NEW BEDFORD, MASSACHUSETTS

CRITERIA	EXISTING	REQUIRED	PROVIDED
LOT AREA (SF)	43,500		43,500
LOT WIDTH (FT)	217.5	0	217.5
# OF DWELLING UNITS	0	0	0
TOTAL GROSS FLOOR AREA (SF)	0	N/A	9180
RESIDENTIAL GROSS FLOOR AREA (SF)	0	N/A	0
NON-RES GROSS FLOOR AREA (SF)	0	N/A	9180
BUILDING HEIGHT (FT)	0	100	25
FRONT SETBACK (FT)	0	0	15
SIDE SETBACK (FT)	0	10	112
SIDE SETBACK (FT)	0	12	83
REAR SETBACK (FT)	0	10	N/A
LOT COVERAGE BY BLDG (% OF LOT)	0	100	21.1
PERMEABLE OPEN SPACE (% OF LOT)	100	0	26
GREEN SPACE (% OF LOT)	100	0	26
OFF-STREET PARKING SPACES	0	46	32
VAN ACCESSIBLE HC SPACES	0	1	2
HANDICAP SPACES	0	2	2
LONG TERM BICYCLE PARKING SPACES	0	0	0
SHORT TERM BICYCLE PARKING SPACES	0	0	0
LOADING BAYS	0	1	1

ISSUED FOR SPECIAL PERMIT



SHEET NUMBER	PLAN TITLE
1. 2. 3. 4. 5. 6. 7. 8. 9. PH-1 PH-2 A1.0 A2.0	TITLE SHEET EXISTING CONDITIONS PLAN DEMOLITION PLAN SITE LAYOUT GRADING & DRAINAGE PLAN UTILITIES PLAN LANDSCAPE PLAN EROSION CONTROL PLAN DETAILS 1 DETAILS 2 LIGHTING PLAN LIGHTING FIXTURE PLAN FRONT ELEVATION
A2.1 R1.0	SIDE AND REAR ELEVATIONS COLOR ELEVATIONS

SCHEDULE OF DRAWINGS

DEVELOPMENT TEAM

	A TARMER OF B SHIP-FIAB
FUNCTION	TEAM MEMBER
DEVELOPER	HUNT REAL ESTATE SERVICES INC. 5100W KENNEDY BLVD, SUITE 100 TAMPA, FL 33609
ARCHITECT	FWH ARCHITECTS 3336 GRAND BLVD, SUITE 201 HOLIDAY, FL 34690
SITE DESIGN ENGINEER	PRIME ENGINEERING, INC. P.O. BOX 1088 LAKEVILLE, MA 02347
CURRENT OWNER	CLARK COVE DEVELOPMENT CO, LLC 651 ORCHARD ST, SUITE 200

NEW BEDFORD, MA 02744


PREPARED BY:





CIVIL ENGINEERING—LAND SURVEYING—ENVIRONMENTAL ASSESSMENT P.O. BOX 1088, 350 BEDFORD STREET, LAKEVILLE, MA 02347 TEL: 508.947.0050 FAX: 508.947.2004


SITE LOCUS IS REFERENCED AS NEW BEDFORD ASSESSOR'S


NEIGHBORHOOD LOCUS PLAN SCALE: 1"=80" NOVEMBER 4, 2016














PLANTING SCHEDULE


	U	ECIDUOUS TREES		
SYMBOL	BOTANICAL NAME	COMMON NAME	SIZE	QUANTITY
BN	BETULA NIGRA HERITAGE CLUMP	HERITAGE RIVER CLUMP BIRCH	6'	2
UA	ULMUS AMERICANA VALLEY FORGE	VALLEY FORGE ELM	2" CAL	1
SR	SYRINGA RECTICULATA	LILAC TREE	2.5" CAL	2
OP	OUERCUS PALUSTRIS	PINOAK	2" CAL	2
AR	ACER RUBRUM RED SUNSET	RED SUNSET SWAMP MAPLE	2" CAL	2
PY	PRUNUS YEDOENSIS	YASHINO CHERRY	2.5" CAL	4
GT	GLEDITSIA TRIACANTHOS INER SHADEMASTER	SHADEMASTER LOCUS	2.5" CAL	1
<i>25</i>	ZELKOVA SERRATA VILLAGE GREEN	ZELKOVA	2,5" CAL	2
11.7		SHRUBS	•	
JP	JUNIPERUS PROCUMBENS 'NANA'	DWARF JAPANESE GARDEN JUNIPER	15"	10
16	ILEX GLABA COMPACTA	INKBERRY	15"	5
JH	LLEX CRENATA JERGEY PINNACLE	JAPANESE HOLLY JERSEY PINNACLE	31-41	2
MP	MYRICAPENSYLVANICA	NORTHERN BAYBERRY	18"	5
<i>5</i> J	JUNIPERUS CHINENSIS	SEAGREEN JUNIPER	18"	3
5M	SPRIAEA MIXED V ARIETY:	MIXED SPRIAEA		
	SPRIAEA BULMALDA ANTHONY WATERER	ANTHONY WATERER	18"	2
	SPRIAEA FLAMING MOUND	FLAMING MOUND	18"	. 3
	SPRIAEA BULMALDA GOLD FLAME	GOLD FLAME	18"	3
	SPRIAEA JAPONICA LITTLE PRINCESS	LITTLE PRINCESS	18"	2




EXISTING TREE - TO BE PRESERVED

NOTE:

OVERHEAD POWER POLES RESTRICT THE ABILITY FOR LARGE TREES TO PROPERLY MATURE WITHIN THE CITY ROAD LAYOUT. THE FOUR TREES THAT EXIST WITHIN THE LAYOUTWILL BE PRESERVED AND SUPPLEMENTED WITH TWO LILAC TREES (NOT INCLUDED IN THE ABOVE SCHEDULE). EIGHT ADDITIONAL LARGE TREES ARE PROPOSED JUST OUTSIDE THE ROAD LAYOUT FOR A TOTAL OF FOURTEEN TREES THAT WILL LINE THE STREETS.




NOT TO SCALE



B&B TREE AND SHRUB
PLANTING DETAIL
NOT TO SCALE

							1	
					LANDSCAPE PLAN	SCALE: 1" = 20'	PELLIN OF MICE	
					PROJECT FAMILY DOLLAR	DATE: 11/4/2016	RICHARD	
					NEW BEDFORD, MASSACHUSETTS	DRAWN BY:	S RHEAUMS RICESTS CIVIL	
					HUNT REAL ESTATE SERVICES, INC.	DESIGNED BY:		
					TAMPA, FLORIDA	RMF (John Thea	e
					P.O. BOX 1088 SLAND SURVEYING P.O. BOX 1088 350 BEDFORD ST. LAKEVILLE, MA 023	CHECKED BY: RJR	SHEET NO. C6.0	
					ENVIRONMENTAL PRIME ENGINEERING TEL: 508.947.003	400001 mo 01/	PROJECT NO.	
REV.	DATE	DESCRIPTION	BY	APP.	ASSESSMENT FAX: 508.947.20		17210303	



CITY OF NEW BEDFORD PLANNING BOARD

ENDORSED_

APPROVED _____

EROSION & SEDIMENT CONTROL NOTES:

IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTROL EROSION AND PREVENT SEDIMENTATION WITHIN 25' OF RESOURCE AREAS OR OFFSITE PROPERTIES. IT IS INTENDED THAT THE IMPLEMENTATION OF THE FOLLOWING MEASURES WILL MEET THIS GOAL. WHEN IT IS CLEAR TO THE DESIGNER THAT EROSION AND SEDIMENTATION HAVE BEEN ADEQUATELY CONTROLLED WITHOUT THE IMPLEMENTATION OF EVERY MEASURE, ADDITIONAL MEASURES NEED NOT BE IMPLEMENTED. ALTERNATIVELY, IF ALL OF THE FOLLOWING MEASURES HAVE BEEN IMPLEMENTED AND THE CONTROL OF EROSION AND SEDIMENTATION IS INADEQUATE, THE CONTRACTOR MUST EMPLOY SUFFICIENT SUPPLEMENTAL MEASURES BEYOND THE SCOPE OF THIS PLAN.

1. EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED PRIOR TO CONSTRUCTION. STABILIZATION OF ALL REGRADED AND SOIL STOCKPILE AREAS WILL BE INITIATED AND MAINTAINED DURING ALL PHASES OF CONSTRUCTION.

2. ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE CONSTRUCTED IN ACCORDANCE WITH LOCAL MUNICIPAL REGULATIONS. ALL EROSION CONTROL MEASURES ARE TO BE MAINTAINED AND UPGRADED AS REQUIRED TO ACHIEVE PROPER SEDIMENT CONTROL DURING CONSTRUCTION

3. ADDITIONAL CONTROL MEASURES WILL BE INSTALLED DURING THE CONSTRUCTION PERIOD, IF DEEMED NECESSARY BY THE OWNER OR AGENTS OF THE OWNER.

4. CATCH BASINS WILL BE PROTECTED WITH HAYBALE FILTERS THROUGHOUT THE CONSTRUCTION PERIOD UNTIL ALL DISTURBED AREAS ARE THOROUGHLY STABILIZED. SILT SOCKS SHOULD BE INSTALLED UNDER GRATE OPENING UNTIL PAVEMENT IS IN PLACE AND GROUND SURFACE IS STABILIZED.

5. SEEDING MIXTURE FOR FINISHED GRASSED AREAS WILL BE AS FOLLOWS:

KENTUCKY BLUE GRASS CREEPING RED FESCUE PERENNIAL RYEGRASS

UE 45% 10%

SEED TO BE APPLIED AT A RATE OF 4 LBS./1000 SQ. FT.
PLANTING SEASONS SHALL BE APRIL 1 TO JUNE 1 AND AUGUST 1 TO OCTOBER 15. AFTER
OCTOBER 15, AREAS WILL BE STABILIZED WITH HAYBALE CHECK, FILTER FABRIC, OR
WOODCHIP MULCH, AS REQUIRED, TO CONTROL EROSION.

6. AREAS THAT ARE NOT THE LOCATION OF ACTIVE CONSTRUCTION WHICH ARE TO BE LEFT BARE FOR OVER ONE MONTH BEFORE FINISHED GRADING AND SEEDING IS ACHIEVED, SHALL BE MULCHED OR RECEIVE TEMPORARY STABILIZATION SUCH AS JUTE NETTING OR SHALL RECEIVE A TEMPORARY SEEDING OF PERENNIAL RYEGRASS APPLIED TO A RATE OF 2 LBS./1,000 SQ. FT. LIMESTONE (EQUIVALENT TO BE 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDE) SHALL BE APPLIED AS SEEDBED PREPARATION AT A RATE OF 90 LBS./1,000 SQ. FT. PLANTING SEASONS SHALL BE APRIL 1 TO JUNE 1 AND AUGUST 1 TO OCTOBER 1. AREAS TO BE LEFT BARE BEFORE FINISH GRADING AND SEEDING OUTSIDE OF PLANTING SEASONS SHALL RECEIVE AN AIR——DRIED WOOD CHIP MULCH, FREE OF COARSE MATTER.

7. AT ALL PROPOSED FILL AREAS WHICH ARE NOT CURRENTLY SHOWN ON THESE PLANS, THE CONTRACTOR SHALL ESTABLISH AN EROSION CONTROL LINE (HAYBALE CHECK OR FILTER FABRIC) ABOUT TEN (10') FEET FROM TOE TO SLOPE OF PROPOSED FILL AREAS PRIOR TO BEGINNING FILL INSTALLATION. STABILIZATION OF SLOPES IN FILL AREAS (USING MULCH OR GRASS) SHALL BE INITIATED WITHIN THIRTY (30) DAYS OF COMMENCEMENT OF FILL INSTALLATION.

8. STABILIZATION OF SLOPES IN CUT AREAS (USING MULCH OR GRASS) AND THE INSTALLATION OF CONTROL LINE (HAYBALE CHECK OR FILTER FABRIC) AT THE TOE OF SLOPE SHALL BE INITIATED WITHIN THIRTY (30) DAYS OF COMPLETION.

9. SEDIMENT REMOVED FROM CONTROL STRUCTURES WILL BE DISPOSED IN A MANNER WHICH IS CONSISTENT WITH THE INTENT OF THE PLAN. ALL HAYBALES OR SILT FENCE RETAINING SEDIMENT OVER 1/2 THEIR HEIGHT SHALL HAVE THE SEDIMENT REMOVED AND ALL DAMAGED EROSION CONTROLS SHALL BE REPAIRED OR REPLACED.

10. CONTRACTOR WILL BE ASSIGNED THE RESPONSIBILITY FOR IMPLEMENTING THIS EROSION AND SEDIMENT CONTROL PLAN. THIS RESPONSIBILITY INCLUDES THE INSTALLATION AND MAINTENANCE OF CONTROL MEASURES, INFORMING ALL PARTIES ENGAGED ON THE CONSTRUCTION SITE OF THE REQUIREMENTS AND OBJECTIVES OF THE PLAN, AND NOTIFYING THE PLANNING BOARD OF ANY TRANSFER OF THIS RESPONSIBILITY. THE OWNER SHALL BE RESPONSIBLE FOR CONVEYING A COPY OF THE EROSION AND SEDIMENT CONTROL PLAN IF THE TITLE TO THE LAND IS TRANSFERRED.

11. THE CONTRACTOR SHALL VERIFY IN THE FIELD THAT THE CONTROLS REQUIRED BY THIS PLAN ARE PROPERLY INSTALLED, SHALL MAKE INSPECTION OF SUCH FACILITIES NOT LESS FREQUENTLY THAN EVERY 14 DAYS OR AFTER A RAINFALL IN EXCESS OF 1/2 INCH, WHICHEVER OCCURS FIRST. THE INSPECTION REPORTS SHALL BE SUBMITTED TO THE PLANNING DEPARTMENT AND CONSERVATION COMMISSION OFFICE ON A MONTHLY BASIS.

12. STOCKPILES OF SOIL SHALL BE SURROUNDED BY A SEDIMENT BARRIER. SOIL STOCKPILES TO BE LEFT BARE FOR MORE THAN THIRTY (30) DAYS SHALL BE STABILIZED WITH TEMPORARY VEGETATION OR MULCH. IF SOIL STOCKPILES ARE TO REMAIN FOR MORE THAN SIXTY (60) DAYS, FILTER FABRIC SHALL BE USED IN PLACE OF HAYBALES. SIDE SLOPES SHALL NOT EXCEED 2:1.

13. THE CONTRACTOR SHALL BE RESPONSIBLE TO CONTROL DUST AND WIND EROSION THROUGHOUT THE LIFE OF HIS CONTRACT. DUST CONTROL SHALL INCLUDE, BUT IS NOT LIMITED TO SPRINKLING OF WATER ON EXPOSED SOILS AND HAUL ROADS. CONTRACTOR SHALL CONTROL DUST TO PREVENT A HAZARD TO TRAFFIC.


14. WHERE DEWATERING IS NECESSARY, THERE SHALL NOT BE A DISCHARGE DIRECTLY INTO WETLANDS OR WATERCOURSES. PROPER METHODS AND DEVICES SHALL BE UTILIZED TO THE EXTENT PERMITTED BY LAW, SUCH AS PUMPING WATER INTO A TEMPORARY SEDIMENTATION BOWL, PROVIDING SURGE PROTECTION AT THE INLET AND THE OUTLET OF PUMPS, OR FLOATING THE INTAKE OF THE PUMP, OR OTHER METHODS TO MINIMIZE AND RETAIN THE SUSPENDED SOLIDS. IF A PUMPING OPERATION IS CAUSING TURBIDITY PROBLEMS, SAID OPERATION SHALL CEASE UNTIL SUCH TIME AS FEASIBLE MEANS OF CONTROLLING TURBIDITY ARE DETERMINED AND IMPLEMENTED. SAID DISCHARGE POINTS SHALL BE LOCATED OVER 100 FEET FROM THE DELINEATED WETLANDS AS INDICATED ON THIS PLAN.

15. SILT SACKS OR OTHER EQUIVALENT ARE TO BE PLACED IN THE FIRST DOWNSTREAM CATCH BASINS FROM THE SITE.


16. ALL BMP EROSION CONTROL MEASURES SHALL BE IN PLACE PRIOR TO DEMOLITION OR ANY SITE WORK.

17. EROSION CONTROL BMPS SHALL CONFORM TO US EPA, NPDES, MA DEP AND MASSACHUSETTS EROSION AND SEDIMENTATION CONTROL GUIDELINES FOR URBAN AND SUBURBAN AREAS.


18. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE MAINTAINED THROUGHOUT THE CONSTRUCTION PROCESS UNTIL THE SITE HAS BEEN FULLY STABILIZED. THE MAINTENANCE SHALL INCLUDE REPLACEMENT OF THE BMP IF NECESSARY.



CONSTRUCTION ENTRANCE NOT TO SCALE





SEDIMENT AND EROSION CONTROL AT CATCH BASINS TO BE INSTALLED IF SPECIFIED BY FIELD ENGINEER NOT TO SCALE




O:\PROJECTS\DARTMOUTH\Faunce Corner Rd\CHMB\baseplan.dwg


				•				
						EROSION CONTROL PLAN	SCALE: 1" = 20'	THO OF MICE
						PROJECT FAMILY DOLLAR	DATE: 11/4/2016	RICHARO
ŀ	-					NEW BEDFORD, MASSACHUSETTS	DRAWN BY: EKW	18 No 28378
ļ						HUNT REAL ESTATE SERVICES, INC. TAMPA, FLORIDA	DESIGNED BY:	when the
ļ	\rightrightarrows	· · · · · · · · · · · · · · · · · · ·				• CIVIL ENGINEERING • LAND SURVEYING P.O. BOX 1088 350 BEDFORD ST. LAKEVILLE, MA 02347	D. ID	SHEET M. C7.0
	REV.	DATE	DESCRIPTION	BY	APP.	*ENVIRONMENTAL ASSESSMENT PRIME ENGINEERING TEL: 508.947.0050 FAX: 508.947.2004	APPROVED BY: RJR	PROJECT NO. 17210303







NOT TO SCALE
TO BE USED ONLY WHERE SPECIFIED ON THE PLAN VIEW



Notes:


- 1. The Use Of Flexible Connection is Recommended at The Inlet and Outlet Where Applicable.
- 2. The Cover Should be Positioned Over The Outlet Drop Pipe and The Oil Port.
- 3. The Stormceptor System is protected by one or more of the following U.S. Patents: #4985148, #5498331, #5725760, #5753115, #5849181, #6068765, #6371690.
- 4. Contact a Concrete Pipe Division representative for further details not listed on this drawing.

STC 900 Precast Concrete Stormceptor (900 U.S. Gallon Capacity)

ENDORSED

APPROVED BY THE CITY OF NEW BEDFORD PLANNING BOARD


CITY OF NEW BEDFORD PLANNING BOARD




1. MASSACHUSETTS STANDARD CATCH BASIN HOOD SHALL BE INSTALLED ON OUTLET PIPE.


TYPICAL FLAT TOP CATCH BASIN

NOT TO SCALE







CEMENT CONCRETE WHEELCHAIR RAMP



STANDARD SEWER SERVICE
CLEANOUT DETAIL



SECTION A - A




SANITARY SEWER SERVICE CONNECTION

NOT TO SCALE

ALL UTILITY WORK SHALL BE DONE IN CONFORMANCE
WITH NEW BEDFORD DEPARTMENT OF PUBLIC
INFRASTRUCTURE CONSTRUCTION STANDARDS AND
SPECIFICATIONS DATED MARCH, 2012

O:\PROJECTS\DARTMOUTH\Faunce Corner Rd\CHMB\baseplan.dwg

					DRAWING TITLE DETAILS		SCALE: AS NOTED	
					PROJECT FAMILY DOLLAR		DATE: 11/4/2016	15 RICHARD
					NEW BEDFORD, MASSACHUSETTS		DRAWN BY: EKW	E RHEAUME No 28373 CVIL
					TAMPA, FLORIDA	INC.	DESIGNED BY:	Shad Chla
					· CIVIL ENGINEERING · LAND SURVEYING	P.O. BOX 1088 350 BEDFORD ST. LAKEVILLE, MA 02347	CHECKED BY:	SHEET NO. C9.0
REV.	DATE	DESCRIPTION	BY	APP.	ASSESSMENT PRIME ENGINEERING	TEL: 508.947.0050 FAX: 508.947.2004	APPROVED BY: RJR	PROJECT NO. 17210303





LIGHT POLE SHOP DRAWINGS

INCLUDED WITH THE POLE SHOP DRAWING SUBMITTAL SHALL BE A SIGNED AND SEALED DRAWING OF THE SITE LIGHTING POLE BASE DESIGN SHOWING MINIMUM BASE DEPTH. CALCULATION SHALL BE PERFORMED BY A REGISTERED PROFESSIONAL ENGINEER WITH AN ACTIVE LICENSE IN THE STATE OF MASSACHUSETTS. CALCULATION SHALL BE BASED ON SOIL INFORMATION AT ACTUAL SITE.

STATISTICS						
Description	Symbol	Avg	Max	Min	Max/Min	Avg/Min
OVERALL SITE	+	2.8 fc	6.1 fc	0.2 fc	30.5:1	14.0:1
PARKING AREA	ж	3.3 fc	5.7 fc	1.9 fc	3.0:1	1.7:1
SPILL LIGHT	+	0.4 fc	1.1 fc	0.0 fc	N/A	N/A

SURFACE SC	HEDULE					
	Reflec	tances		Normai		
Name	Front	Back	Х	Υ	Z	Area (ft²)
Structure	0%	0%			······································	





			Location						Aim	
No.	Label	X	Y	Z	MH	Orientation	Tilt	X	Υ	Z
1	WA	440.2	227.7	10.5	10.5	0.0	0.0	440.2	227.7	0.0
2	WA	489.1	227.7	10.5	10.5	0.0	0.0	489.1	227.7	0.0
3	WB	514.9	203.0	10.5	10.5	90.0	0.0	514.9	203.0	0.0
4	WB	514.9	141.5	10.5	10.5	90.0	0.0	514.9	141.5	0.0
5	WA	422.6	212.7	15.0	15.0	-90.0	0.0	422.6	212.7	0.0
6	WA	422.2	135.9	15.0	15.0	-90.0	0.0	422.2	135.9	0.0
7	WB	444.3	123.4	- 10.5	10.5	180.0	0.0	444.3	123.4	0.0
8	WB	497.7	123.0	10.5	10.5	180.0	0.0	497.7	123.0	0.0
9	SA	334.5	259.0	25.0	25.0	90.0	0.0	336.7	259.0	0.0
10	SA	335.8	187.3	25.0	25.0	90.0	0.0	338.0	187.3	0.0
11	SA	355.9	128.4	25.0	25.0	90.0	0.0	358.1	128.4	0.0
12	SA	494.4	288.5	25.0	25.0	180.0	0.0	494.4	286.2	0.0



ALL SITE AND BUILDING LIGHTS PROPOSED ON THIS PROJECT ARE DESIGNED AS FULL CUTOFF CLASSIFICATION WITH ZERO UP LIGHT COMPONENTS.

THESE PHOTOMETRICS ARE INTENDED FOR DESIGN AND EVALUATION PURPOSES ONLY. THE POINT-BY-POINT SHOWN IS BASED ON A COMPUTER LIGHTING PROGRAM WITH APPROXIMATED PARAMETERS. THEREFORE, THESE PHOTOMETRICS MAY VARY FROM ACTUAL FIELD CONDITIONS.

CON	SULTING PROFESSIONAL E.	NGINEER
3702 AZEELI TAMPA, FL 3		(813) 876-1415 (fax) 876-0913
LIC #39553	SOUHEIL CHEHAYEB	16-163

REVIEWED"
DISAPPROVED - RESUBMIT"
All Site and Building Plan Requirements, including but limited to, all Interior Dimensions, Materials, Hardware, Equipment & Specifications, are to be designed and built per the Family Dollar Prototype Plan #: as indicated in the lease, unless a deviation is

approved by Family Dollar's Plan Reviewer, next to each specific deviation. The initials indicate approval of only the one deviation being initialed. Any deviation from designated Prototype Plan that is not

Lic.# AA 0003300

3336 Grand Blvd. Suite 201

Holiday, Florida 34690

Ph. 727. 815. 3336

Fax 727. 815. 3337

TO THE BEST OF THE KNOWLEDGE OF

THE ARCHITECTS AND ENGINEERS, PLANS AND SPECIFICATIONS COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES

AND THE APPLICABLE MINIMUM FIRE

SAFETY STANDARDS

SOUHEIL CHEHAYEB, P.E.

MA License No. 39553

& ORCHARD (ACHUSETTS)

CORNER SW BEDFORD,


11.03.16 date


16085 comm. no.


PHOTOMETRIC

SITE PLAN

initialed by Family Dollar is disapproved and void. (Approval to plan deviation will be indicated with the following circled initials:







LIC #39553

(Approval to plan deviation will be indicated with the following circled initials:_____)

☐ "REVIEWED"

cell, button type ⁴

180° motion/

ambient light sensor, <15' mtg ht ^s

ambient light sensor, 15-30 mtg ht ⁵

PIRH 180° motion/

ELCW Emergency battery backup (includes exter-

enclosure)6

ming driver (no controls)

shield ⁸

surge protection ⁹

SPD Separate

BSW Bird-deter-

WG Wire guard

VG Vandal guard

DDL Diffused

DSXWBSW U Bird-deterrent spikes

DSXW1WG U Wire guard accessory

DSXW1VG U Vandal guard accessory

DMG 0-10V dim-

DNAXD Natural

DWHXD White

DDBTXD Textured

DBLBXD Textured

DNATXD Textured

DWHGXD Textured

DSSTXD Textured

House-side shield (one per light engine)

DSSXD Sandstone

INFORMATION

Lic.# AA 0003300

3336 Grand Blvd. Suite 201

Holiday, Florida 34690

Ph. 727. 815. 3336

Fax 727. 815. 3337

TO THE BEST OF THE KNOWLEDGE OF

THE ARCHITECTS AND ENGINEERS, PLANS

AND SPECIFICATIONS COMPLY WITH THE

APPLICABLE MINIMUM BUILDING CODES

AND THE APPLICABLE MINIMUM FIRE

SAFETY STANDARDS

SOUHEIL CHEHAYEB, P.E.

MA License No. 39553

ST

ORCHARD HUSETTS

CORNER BEDFOR


11.03.16

date

16085

comm. no.

FIXTURE



CERTIFICATE OF OCCUPANCY NOTE

G.C. IS RESPONSIBLE FOR THE "CERTIFICATE OF OCCUPANCY". CERTIFICATE TO BE FRAMED AND MOUNTED IN THE MANAGERS OFFICE OVER THE DOOR. IF MUNICIPALITY DOES NOT ISSUE A CofO, IT IS THE RESPONSIBILITY OF THE G.C. TO GET A LETTER FROM THE MUNICIPALITY STATING AS SUCH ON CITY/ COUNTY LETTERHEAD AND THAT LETTER IS TO BE FRAMED AND MOUNTED IN MANAGER'S OFFICE

THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING THAT ALL CONSTRUCTION IS IN COMPLIANCE WITH ALL LOCAL, STATE AND NATIONAL CODES GOVERNING THE JURISDICTION, AND WITH THE AMERICAN'S WITH DISABILITIES ACT. THE GC SHALL COORDINATE THE VARIOUS CONSTRUCTION DOCUMENTS FOR THE PROJECT. IF CONFLICT OF INFORMATION IS FOUND, THE GC SHALL RESOLVE THE CONFLICTS PRIOR TO PROCEEDING.

WHERE NECESSARY AT SIDE AND REAR WALLS, SITE CONTRACTOR TO TRANSITION DOWN FROM DOORWAYS TO A MIN. OF 4" BELOW SLAB, WHERE APPLICABLE, TO AVOID CONFLICT W/FINISH OVERLAP AT SLAB, TERMINATING AT THRESHOLDS TO ACCOMMODATE ADA COMPLIANT LANDINGS AT EGRESS DOORS. THIS WILL ALLOW A CONCRETE FINISHING TOOL OR PLATE COMPACTOR UNDER THE BUILDING FINISH TO COMPLETE THE CONCRETE AND ASPHALT WORK NECESSARY. REFER TO CIVIL PLANS FOR EXACT GRADE HEIGHTS AND TRANSITIONS.

THE ELEVATION OF THE FLOOR SURFACE ON BOTH SIDES OF ANY DOOR SHALL NOT VARY BY MORE THAN 1/2" INCH FOR A DISTANCE NOT LESS THAN THE WIDTH OF THE WIDEST LEAF. PER NFPA 101, SECTION 7.2.1.3.1 \$ 7.2.1.3.2.

BUILDING COLUMNS MUST BE LOCATED AS NOT TO INTERFERE WITH DOOR LOCATIONS INDICATED ON

COLUMN LOCATIONS SHALL BE VERIFIED BY THE PEMB MANUF. GENERAL CONTRACTOR SHALL COORDINATE DOOR LOCATIONS WITH THE PEMB MANUFACTURER'S COLUMN LAYOUT. COLUMN LOCATIONS THAT DIFFER FROM LAYOUT CURRENTLY SHOWN IN THE CONSTRUCTION DRAWINGS MUST BE SUBMITTED TO FAMILY DOLLAR STORE'S CONSTRUCTION DEPT. FOR APPROVAL.

- GENERAL CONTRACTOR TO PROVIDE AND INSTALL (MASTER LOCK 5400D OR EQ) LOCK BOX.
- THE LOCK BOX SHALL BE SET TO THE LAST 4 DIGITS OF THE STORE NUMBER. ON GROUND UP LOCATIONS, THE LOCK BOX SHALL BE INSTALLED PRIOR TO THE DELIVERY
- NOTICE BEING ISSUED TO FAMILY DOLLAR TO PROVIDE ACCESS DURING PUNCHOUT \$ TURNOVER. ON EXISTING SPACE RETROFITS, THE LOCK BOX SHALL BE INSTALLED AT THE START OF CONSTRUCTION.
- THE LOCK BOX SHALL CONTAIN THE FRONT DOOR KEY.
- THE LOCK BOX SHALL BE PLACED ON THE FRONT DOOR HANDLE. FOR STORES WHERE THE FRONT DOOR DOES NOT HAVE A HANDLE, THE LOCK BOX WILL BE INSTALLED ON AN EYEBOLT INSERTED IN THE TOP OF THE RECEIVING DOOR BOLLARD.

PER FAMILY DOLLAR CRITERIA, GC IS TO PROVIDE AND INSTALL ONE POSTAL APPROVED MAILBOX IF REQUIRED BY CODE.


AUTOMATIC DOOR SIGNAGE NOTE

A READILY VISIBLE, DURABLE SIGN IN LETTERS NOT LESS THAN I IN. HIGH ON A CONTRASTING BACKGROUND THAT READS AS FOLLOWS SHALL BE LOCATED ON THE EGRESS SIDE OF EACH DOOR OPENING: IN EMERGENCY, PUSH TO OPEN

CONSTRUCTION CAMERAS

ALL PROJECTS: (BTS & FEE DEVELOPMENT) ARE REQUIRED TO HAVE A JOBSITE MONITORING SYSTEM FROM OXBLUE CORPORATION WITH NECESSARY POWER FOR THE DURATION OF THE CONSTRUCTION, INCLUDING ANY SITE WORK. REFER TO SHEET TI.O FOR CONTACT INFORMATION.

ALLOW 4 WEEKS FOR ORDERING AND DELIVERY OF CAMERAS.



ENLARGED FLOOR PLAN A1.0 SCALE = 1/4" = 1'-0"



@ ENTRY VESTIBULE

- RESUBMI

		"REVIEWED"
Г	1	"DISAPPROVED

SUBMITTAL TO FAMILY DOLLAR AS REQUIRED FOR MILESTONE SUBMITTALS.

All Site and Building Plan Requirements, including but limited to, all Interior Dimensions, Materials, Hardware, Equipment & Specifications, are to be designed and built per the Family Dollar Prototype Plan as indicated in the lease, unless a deviation is approved by Family Dollar's Plan Reviewer, next to each specific deviation. The initials indicate approval of only the one deviation being

initialed. Any deviation from designated Prototype Plan that is not

Approval to plan deviation will be indicated with the following circled initials :_

initialed by Family Dollar is disapproved and void.

Architects

LIC.# AA 0003300

Holiday, Florida 34690 Ph. 727. 815. 3336 Fax 727. 815. 3337

3336 Grand Blvd. Suite 201

TO THE BEST OF THE KNOWLEDGE O THE ARCHITECTS AND ENGINEERS, PLANS AND SPECIFICATIONS COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES AND THE APPLICABLE MINIMUM FIRE

SAFETY STANDARDS


GUY F. FABER MA License No. 31856

ORCHARD (\Box)

11.03.16

16085 comm. no. 102 X 90

FLOOR PLAN & NOTES



SOUTH ELEVATION (PARKING LOT) A2.0 SCALE = 1/4'' = 1'-0''

0.	AREA	TYPE	COATS	COLOR
1	'NICHIHA' FIBER CEMENT WALL PANEL	TUFFBLOCK LARGE BLOCK (18"X72") PANEL W/TEXTURED FIN.	PRE-FINISHED	MATCH BENJAMIN MOORE COLOR 'FD BM LIGHT SAND'
2	METAL AWNING	VP - PANEL RIB NUCOR - CLASSIC WALL	PRE-FINISHED	MATCH VP COLOR "COOL BRIGHT RED" OR MATCH BENJAMIN MOORE COLOR 'FD BM SAFETY RED'
3	'NICHIHA' FIBER CEMENT WALL PANEL	EDA62IE CINDERBLOCK - BROWN (18"X72") PANEL	PRE-FINISHED	
4	DOORS, GUTTERS, DOWNSPOUTS, MTL. TRIM, RAKE TRIM, RECEIVING CANOPY, ARCHED PARAPET CAP	METAL BUILDING MANUFACTURER	PRE-FINISHED	VP COLOR "TAN" NUCOR COLOR "SAGEBRUSH TAN" MID-WEST COLOR "SADDLE TAN" BENJAMIN MOORE COLOR 'FD BM DARK SAND'
5	'NICHIHA' FIBER CEMENT WALL PANEL	ARCHITECTURAL BLOCK SERIES-COLOR TUSCAN	PRE-FINISHED	BENJAMIN MOORE COLOR 'FD BM KHAKI'
6	STEEL BOLLARDS	EXTERIOR LATEX	2	BENJAMIN MOORE COLOR 'FD BM SAFETY RED'
7	METAL ROOF	STANDING SEAM ROOF	PRE-FINISHED	COOL ARCTIC WHITE
8	METAL PANELS	MID-WEST - PBA PANEL NUCOR - ACCENT PANEL VP - VEE RIB PANEL	PRE-FINISHED	MID-WEST COLOR "SADDLE TAN" NUCOR COLOR "SAGEBRUSH TAN" VP COLOR "TAN" BENJAMIN MOORE COLOR 'FD BM DARK SAND'
9	'NICHIHA' FIBER CEMENT WALL PANEL (RED BAND)	ILLUMINATIONS LARGE BLOCK (18"X72") PANEL	PRE-FINISHED	MATCH BENJAMIN MOORE COLOR 'FD BM SAFETY RED'

EXTERIOR FINISH NOTES

- APPLY MASONRY BLOCK FILLER TO CONCRETE BLOCK PRIOR TO FINISH PAINTING. (AT DUMPSTER ENCLOSURE ONLY)
- IF METAL BUILDING IS USED, G.C. TO SUBMIT MANUFACTURER'S STANDARD COLORS TO FAMILY DOLLAR FOR APPROVAL.
- REFER TO PAINT ORDERING INSTRUCTIONS ON SHEET TI.O
- 4. EXTERIOR PAINT (OTHER THAN TRAFFIC PAINT) -BENJAMIN MOORE: ULTRA SPEC HP DTM ACRYLIC SEMI-GLOSS ENAMEL HP29
- 5. TRAFFIC PAINT-BENJAMIN MOORE LATEX TRAFFIC PAINT TD58

METAL PANEL NOTES

- THIS SYSTEM USES STANDING SEAM ROOF SYSTEM THERMAL BLOCKS. G.C. TO PROVIDE 20 YEAR WEATHER TIGHTNESS WARRANTY.
- 2. THE WALL PANELS ARE ATTACHED W/ SELF-DRILLING CORROSION RESISTANT TYPE LONG LIFE CARBON STEEL FASTENERS WITH HEX HEAD AND SEALING WASHER (OR EQUAL) FOR ALL EXTERIOR METAL WALL PANELS. FASTENER COLOR TO MATCH PANEL BEING FASTENED.
- 3. METAL BUILDING EAVE HT. TO BE ADJUSTED AS REQUIRED TO MAINTAIN FAMILY DOLLAR STANDARD CEILING HEIGHT.

VERIFY W/ SPECIFIC METAL BLDG. CO.

FEE DEVELOPMENT PROJECTS

INSTALLATION OF ROAD AND BUILDING SIGN MUST BE INCLUDED IN GENERAL CONTRACTOR'S BID AND SCOPE OF WORK.

ROOF WARRANTY NOTE

CONTRACTOR MUST PROVIDE A 20-YEAR, WEATHERTIGHT WARRANTY THAT HAS BEEN PRE-APPROVED BY FAMILY DOLLAR. NO EXCEPTIONS.

BLOCKING NOTE

GC TO PROVIDE AND INSTALL BLOCKING AT SIGNAGE, AWNING/CANOPY AND EXTERIOR LIGHT FIXTURE LOCATIONS AS NEC. TO ENSURE ADEQUATE SUPPORT IS PRESENT FOR A SECURE CONNECTION TO THE FACE OF THE BUILDING.

FOR THE EXTERIOR WALL PACKS WHEN MOUNTED TO CORRUGATED WALL PANELS, GC SHALL CUT A PIECE OF WOOD AS A MOUNTING BLOCK, PAINTED TO MATCH PANEL COLOR, SCREW THROUGH TO BLOCKING ON INSIDE PRIOR TO MOUNTING FIXTURE TO THE WOOD MOUNTING BLOCK.

ALL DIMENSIONS SHOWN ARE TAKEN FROM SLAB HEIGHT, NOT SURROUNDING GRADE ELEVATION, TYPICAL.

METAL TRIM NOTE

ALL METAL TRIM TO BE FURNISHED BY BUILDING VENDOR.

'J' TRIM NOTE

PEMB SHALL FURNISH ALL 'J' TRIMS OR JAMB EXTENSIONS FOR NICHIHA PANEL TERMINATION, SEE FINISH SCHEDULE FOR ADDITIONAL INFORMATION.

ALL GLAZING TO BE TEMPERED, U.N.O.

GENERAL EXTERIOR NOTE

PROVIDE SLEEVE, BOOT, OR OTHER APPROPRIATE PENETRATION MATERIAL FOR A CLEAN TRANSITION FROM EXTERIOR TO INTERIOR FOR ALL CONDUIT WIRE, PIPE ETC. OWNER MUST APPROVE METHOD AND FINISH BEFORE BUILDING COMPLETION.

EAVE HEIGHTS

METAL FRAME BUILDINGS SHALL HAVE AN MIN. EAVE HEIGHT OF 15'-0". EAVE HEIGHT DEPENDANT ON MIN. INTERIOR REQUIREMENTS. SEE A3.0 BOXED NOTE.

DOWNSPOUT NOTE

OF THREE STRAPS PER DOWNSPOUT, TYP.

DOWNSPOUTS SPACING T.B.D. BY CIVIL ENGINEER, BASED ON LOCAL TYPICAL AND MAXIMUM RAINFALL AMOUNTS, WITH DOWNSPOUTS PLACED EQUALLY APART TYP. NO DOWNSPOUT MAY BE PLACED WITHIN 12" OF A DOOR FRAME. USE A MINIMUM

IF SPLASH BLOCKS ARE USED, G.C. SHALL ENSURE THAT NO SAFETY HAZARDS ARE CREATED BY THE DISCHARGE OF WATER FROM THE DOWNSPOUTS OR BY ICE WHICH MAY FORM AS A RESULT OF THE WATER DISCHARGE FROM THE DOWNSPOUTS. COORDINATE ROOF STORM WATER DRAINAGE WITH PROJECT CIVIL ENGINEER.

PROVIDE FLUSH TRENCH DRAINS ACROSS SIDEWALKS TO PARKING AREAS IF DOWNSPOUTS DO NOT TIE TO UNDERGROUND STORM SYSTEM.

CANOPY/AWNING NOTE

STOREFRONT & FREIGHT DOORS MUST BE SHIELDED OVERHEAD FROM THE WEATHER. IF THE PROTOTYPE CANOPY IS NOT USED, AN AWNING, VESTIBULE OR OTHER FORM OF PROTECTION MUST BE USED. FINAL APPROVAL FROM FAMILY DOLLAR STORES.

SIGNAGE NOTE

- GENERAL CONTRACTOR SHALL INSTALL SIGNAGE. FAMILY DOLLAR STORE SIGNAGE VENDOR SHALL FURNISH SIGNAGE AND METAL SUPPORTS AS REQUIRED FOR SIGNAGE INSTALLATION. GENERAL CONTRACTOR SHALL COORDINATE INSTALLATION AND BACKING FOR METAL SUPPORTS.
- GENERAL CONTRACTOR SHALL PROVIDE ELECTRICAL SERVICE AND CONNECTIONS FOR SIGNAGE, VERIFY ELECTRICAL DEMAND OF SIGNAGE WITH FAMILY DOLLAR STORE.
- COORDINATE ACCESS PANEL LOCATION FOR SIGNAGE MOUNTED ON SIDES OR REAR OF BUILDING FAMILY DOLLAR STORE.

SECONDARY SIGNAGE NOTE

WALL MOUNTED LIGHT FIXTURES AT SIGNAGE LOCATIONS SHALL BE RECENTERED ABOVE SIGNAGE IF SECONDARY SIGNAGE IS PROVIDED. CONFIRM MOUNTING HEIGHT OF SECONDARY SIGNAGE WITH FAMILY DOLLAR STORE.

SIGNAGE APPROVAL

SIGNAGE WILL BE REVIEWED UNDER A SEPARATE SUBMITTAL AND PERMIT. SIGN VENDOR TO SUBMIT NECESSARY DRAWINGS AND APPLICATIONS AS NEC. TO OBTAINED ALL APPROVALS AND PERMITS ASSOCIATED WITH THE PROJECT'S SIGNAGE.

NOTE

IF SITE POLE LIGHTING IS PROVIDED THAT FACES THE FRONT ELEVATION, THEN THE PROTOTYPICAL SURFACE MOUNTED LED FLOOD LIGHTS ARE NOT REQUIRED.

REFER TO SECTIONS FOR TYPICAL METAL BUILDING TRIM/PARAPET DETAILS.

PARAPET CAP NOTE

ARCHED METAL COPING SHALL HAVE A SMOOTH RADIUS AND CAN BE MADE UP OF MULTIPLE LENGTHS. MIN. 10' LONG. NO SEAM AT PEAK \$ SPACE SEAMS EQUALLY FROM PEAK CENTER LINE.

NOTE

PROVIDE CONT. WEEP SCREED AT NICHIHA BASE.

SIDEWALK NOTE

SLOPE SIDEWALK TO PROVIDE A MINIMUM OF 2" OF CLEARANCE BETWEEN THE SIDEWALK SURFACE AND THE BOTTOM OF THE NICHIHA PANELS. SLOPE SHALL COMPLY WITH APPLICABLE HANDICAPPED ACCESSIBILITY REQUIREMENTS.

REFER TO SHEET A4.0 FOR STOREFRONT DIMENSIONS AND ADDITIONAL

"REVIEWED" "DISAPPROVED - RESUBMIT" All Site and Building Plan Requirements, include	
All Site and Building Plan Requirements, include	
Interior Dimensions, Materials, Hardware, Equipare to be designed and built per the Family Dol #: as indicated in the lease, unle	pment & Specifications,

approved by Family Dollar's Plan Reviewer, next to each specific deviation. The initials indicate approval of only the one deviation being initialed. Any deviation from designated Prototype Plan that is not initialed by Family Dollar is disapproved and void.

(Approval to plan deviation will be indicated with the following circled initials:___



LIC.# AA 0003300 * 3336 Grand Blvd. Suite 201 Holiday, Florida 34690

Ph. 727. 815. 3336

Fax 727. 815. 3337

TO THE BEST OF THE KNOWLEDGE OF THE ARCHITECTS AND ENGINEERS, PLAN AND SPECIFICATIONS COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES AND THE APPLICABLE MINIMUM FIRE

SAFETY STANDARDS

GUY F. FABER MA License No. 31856


ARD TTS

Om


11.03.16

16085 comm. no.

EXT. ELEVATION EXT. FINISH SCHED. AND NOTES




EAST ELEVATION (ORCHARD STREET) A2.1 SCALE = 1/8' = 1'-0'



NORTH ELEVATION (SWIFT STREET) A2.1 SCALE = 1/8' = 1'-0'

A2.1 SCALE = 1/8" = 1'-0"



1. VERIFY LOCATION OF ALL UNDER-GROUND UTILITIES BEFORE EXCAVATION. 2. GRIND ALL EXPOSED EDGES SMOOTH. BEVELED CONC. CAP SMOOTH FINISH 6" DIA. SCHED. 40 STL. PIPE FILLED WITH CONC AND PAINTED "SAFETY RED" U.O.N. ---CONC. WASH /-- 1/2" EXP. JT. FILLER -6" CONC. SLAB W/3000 PSI CONC. W/6x6 - W2.9xW2.9 WWF OVER COMPACTED SOIL. (TYP., U.N.O.) MIN. 3000 PSI CONCRETE FOUNDATION W/#5 VERTICAL #3 TIES @ 12" O.C. PROVIDE (2) TIES W/IN FIRST 6" OF CONC.

BOLLARD DETAIL

A2.1 SCALE = 1/2' = 1'-0'

NOTE	•	
REFE	R TO SHEET	A2.0 FOR
EXTE	RIOR FINISH	SCHEDULE
AND	ADDITIONAL	A2.0 FOR SCHEDULE INFORMATION.

	"REVIEWEI
--	-----------

☐ "DISAPPROVED - RESUBMIT"

All Site and Building Plan Requirements, including but limited to, all Interior Dimensions, Materials, Hardware, Equipment & Specifications, are to be designed and built per the Family Dollar Prototype Plan #:_____ as indicated in the lease, unless a deviation is approved by Family Dollar's Plan Reviewer, next to each specific deviation. The initials indicate approval of only the one deviation being initialed. Any deviation from designated Prototype Plan that is not

(Approval to plan deviation will be indicated with the following circled initials :____

initialed by Family Dollar is disapproved and void.

Accitects

LIC.# AA 0003300

3336 Grand Blvd. Suite 201
Holiday, Florida 34690
Ph. 727. 815. 3336
Fax 727. 815. 3337

TO THE BEST OF THE KNOWLEDGE OF THE ARCHITECTS AND ENGINEERS, PLANS AND SPECIFICATIONS COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES AND THE APPLICABLE MINIMUM FIRE SAFETY STANDARDS

GUY F. FABER MA License No. 31856

ST.

oldon

date

revision descriptions

SW CORNER SWIFT ST. & ORCHARD SEDFORD, MASSACHUSETTS


11.03.16 date


16085

comm. no.

EXT. ELEVATIONS

A 2 1





GENERAL SPECIFICATIONS:

Materials: Extruded aluminum

Face: 150 SG polycarbonate vacuum formed

Face Decoration: 2nd surface

Access: Remove face

Area Squared: 24 Sq. Ft.

Area Actual: 24 Sq. Ft.

Weight (Est.):

Wind Load: 120psf TBE (uncrated)

ELECTRICAL

Illumination:

• (18) GEDS 71 -1 Power Strip LED

Ballast/Power Supply:
• (2) GEPS24-100V

Line Load:

2.2 Amps @ 100-240 VAC

• (1) 20 Amp Circuit, 60 Hz UL 48 & NEC Compliant

COLORS:

Interior: Ptd. white

NOBEL (GRIP GUARD PLUS) "Sign20134"

Exterior: BASE, CABINET & RETAINERS - Ptd. AKSO

Raceway: NA

Face Graphics Color Specifications:

"FAMILY" - AKSO NOBEL (GRIP FLEX) "Sign 10399"

WHITE, "SIGN 0208 RED"

"DOLLAR" - AKSO NOBEL (GRIP FLEX) "Sign 10399" White, "Sign 0209" ORANGE

SYMBOL - AKSO NOBEL (GRIP FLEX) "Sign 10399"

Everbrite

hese product sheets are the exclusive property of Everbrite LLC. Use of this property in any manner

4949 S 110th Street, Greenfield, WI 53220 Phone: 414-529-3500 • Fax: 414-529-7191 Website: www.everbrite.com **Everbrite LLC**

Description: 24 Sq Ft PylonCabinet Date: 9/18/15

Part No:

Project No: 335537 Drawn By: DB

City of New Bedford, Massachusetts Building Department Application for Plan Examination

DATE RECEIVE	D
RECEIVED BY	
ISSUED BY:	

	Applicati an	on for Plan Exa d Building Peri	amination nit	ISSUED BY:	
IMPORTANT — CO	MPLETE ALĻ ITE	EMS — MARK BO	(ES WHERE APPLICA	ABLE — PRINT	
ON THE PROPERTY OF THE PROPERT	(CROSS STREET) LOT ZE YES NO	nner OR	- AND - ICHO	SS STAEET) ACCEPTED STREET	Yes
II. TYPE AND COST OF BUILDIN	NG - all applicants	s complete parts A	through D - PRINT		
A TYPE OF IMPROVEMENT 1 New Building 2 Addition (Il residential, enter numb units added, if any, in Part D, 14) 3 Alteration (if residential, enter num housing units added, if any, in Part D, 14) 4 Repair, replacement 5 Demolition (If multifamily residential units in building in Part D, 14, if no indicate most recent use checking 6 Moving (relocation) 7 Foundation only B OWNERSHIP 8 Private (individual, corporation, nonprofit institution, etc.)	ber of new t D. 14) al. enter number of on-residential.	Residential 13 One lamily 14 Two or more number of the domition of the domit	otel, motel, or Enter number Decity RETAIL	Nonresidential 19 Amuseme 20 Church, o 21 Industrial 22 Přarking gi 23 Service st 24 Hospital, i 25 Office, bai 26 Public util 27 School, iòr 28 Stores, me 29 Tanks, tow 30 Funeral ho	ation, repair garage institutional nk, professional play, other educational ercantife ers
9 Public (Federal, State, or local government) 10 Cost of construction To be installed but not included in the above cost a. Electrical b. Plumbing c. Heating, air conditioning d. Other (elevalor, etc.) 11 TOTAL VALUE OF CONSTRUCTION 12 TOTAL ASSESSED BLOG, VALUE	(Omn cents)	State Dept. of Labor sample analysis after D3 Non-residential — C machine shop, laun parochial school, pi at industrial plant. 1	modele part Ethmush L. For de	rmolition, complete onl	processing plant, r school, college, ng, office building losed use.
III. SELECTED CHARACTERISTIC		- For all others, (additi	ons, alterations, repair, moving J. DIMENSIONS	, foundation), complete	E through L.
E PRINCIPAL TYPE OF FRAME 33		private company ptic tank, etc.) UPPLY private company etf, cistern) CAL tkier system? 48 \(\bigcup \) NO	53 Number of stories 54 Height 55 Total square feet of floo all floors based on exte 56 Building length 57 Building width 58 Total sq. ft. of bldg. foor 59 Front lot line width 60 Rear lot line width 61 Depth of lot 62 Total sq. ft. of lot size 63 % of lot occupied by bl 64 Distance from lot line (fi	print dg. (58+62) port) ear)	ONE 25' 9180 90 102 9180 217 217 200 43,500 21 15
40		50 No		ear) eft)	93 15 112

Department of Public Infrastructure



Euzebio Arruda Commissioner

Water
Wastewater
Highways
Engineering
Cemeteries
Park Maintenance

MEMORANDUM

TO:

City of New Bedford Planning Board

FROM:

Euzebio Arruda, Commissioner, D.P.I

DATE:

December 7, 2016

RE:

Site Plan – Family Dollar Retail Store

Orchard St. P.23 L.292

The Department of Public Infrastructure has reviewed the proposed site plan referenced above and recommends approval with the following conditions:

- 1. Driveway permits are subject to Traffic Commission approval.
- 2. Driveways to be built in accordance with City of New Bedford regulations and with 4 foot transition curb on both side (No radius curb thru sidewalk area)
- 3. Permits for sidewalk, driveways, water, sewer and storm drain must be obtained from the Department of Public Infrastructure Engineering Division.
- 4. Drainage design must comply with Phase II, Mass Department Stormwater Management standards.
- 5. Show how the proposed 24 inch HDPE Storm water pipe connects to the City System.
- 6. What type of curb is proposed around the perimeter of the Parking Lot?
- 7. All utilities to be installed in accordance with City of New Bedford Standards.
- 8. Owner to explore the possibility of running a water main on Swift St and then connect the Fire Supply and domestic services to it.
- 9. A 10 foot minimum separation between the Water and Sewer services is required.
- 10. Developer to plant 2 more trees (one on the Orchard St. west sidewalks and the other on the Swift St. south side)
- 11. Owner must contact DPI to assign address for the proposed building.
- 12. An easement must be recorded for the proposed 24 inch Stormwater pipe, south of the proposed site.
- 13. The Department of Public Infrastructure requires a final set of approval plans to be submitted that reflects all revisions made prior to the start of construction.
- 14. Developer and site Contractor must schedule a pre-construction meeting with the Department of Public Infrastructure prior to the start of Construction.

DEC 07 2016

15. Upon Completion, Engineer must submit "As Built Drawings" in CADD format prior to the Certificate of Occupancy being issued.

/ct

Cc: Department of Inspectional Services
Environmental Stewardship
Prime Engineering
Hunt Real Estate Services, Inc.
Clark Cove Development Co, LLC.

STORMWATER REPORT

FAMILY DOLLAR STORE SW CORNER OF ORCHARD AND SWIFT STREETS NEW BEDFORD, MA

PREPARED FOR:

HUNT REAL ESTATE SERVICES, INC.

PREPARED BY:

PRIME ENGINEERING, INC. P.O. BOX 1088 LAKEVILLE, MA

NOVEMBER 11, 2016

TABLE OF CONTENTS

INTRODUCTION				1
EXISTING CONDITIONS	• • •	• • •		1
PROPOSED DEVELOPMENT				1
PHYSICAL ENVIRONMENT				1
SURFACE WATER AND SUBSURFACE CONDITIONS			• • •	1
6.4 Standard 4 - Water Quality		• • •		3
6.5 Standard 5 - Land And Uses With Higher Pollution Loads		• • •		2
6.7 Standard 7 - Redevelopment Project		• • • •		?
6.8 Standard 8 - Construction Period Controls				1
6.10 Standard 10 - Prohibition of Illicit Discharges	• • •	· · · ·		1
	• • •	,	• • •	
CONCLUSION		 	4	1
TREE				
e I - Locus Plan	•			
ENDICES				
, -				
ndix E - Hydrologic Computations				
	EXISTING CONDITIONS PROPOSED DEVELOPMENT PHYSICAL ENVIRONMENT SURFACE WATER AND SUBSURFACE CONDITIONS COMPLIANCE WITH STORMWATER MANAGEMENT STANDARDS 6.1 Standard 1 - No Untreated Discharges 6.2 Standard 2 - Peak Rate Attenuation 6.3 Standard 3 - Stormwater Recharge 6.4 Standard 4 - Water Quality 6.5 Standard 5 - Land And Uses With Higher Pollution Loads 6.6 Standard 6 - Critical Areas 6.7 Standard 7 - Redevelopment Project 6.8 Standard 8 - Construction Period Controls 6.9 Standard 9 - Long Term Operation and Maintenance Program 6.10 Standard 10 - Prohibition of Illicit Discharges CONCLUSION RES CONCLUSION RES dix A - Site Construction Controls For The Proposed Family Dollar Facility dix B - Permanent Stormwater System Operation and Maintenance Program dix C - Interim Illicit Discharge Statement dix D - Checklist For Stormwater Report	EXISTING CONDITIONS PROPOSED DEVELOPMENT PHYSICAL ENVIRONMENT SURFACE WATER AND SUBSURFACE CONDITIONS COMPLIANCE WITH STORMWATER MANAGEMENT STANDARDS 6.1 Standard 1 - No Untreated Discharges 6.2 Standard 2 - Peak Rate Attenuation 6.3 Standard 3 - Stormwater Recharge 6.4 Standard 4 - Water Quality 6.5 Standard 5 - Land And Uses With Higher Pollution Loads 6.6 Standard 6 - Critical Areas 6.7 Standard 7 - Redevelopment Project 6.8 Standard 8 - Construction Period Controls 6.9 Standard 9 - Long Term Operation and Maintenance Program 6.10 Standard 10 - Prohibition of Illicit Discharges CONCLUSION RES al - Locus Plan INDICES adix A - Site Construction Controls For The Proposed Family Dollar Facility dix B - Permanent Stormwater System Operation and Maintenance Program adix C - Interim Illicit Discharge Statement adix D - Checklist For Stormwater Report	EXISTING CONDITIONS PROPOSED DEVELOPMENT PHYSICAL ENVIRONMENT SURFACE WATER AND SUBSURFACE CONDITIONS COMPLIANCE WITH STORMWATER MANAGEMENT STANDARDS 6.1 Standard 1 - No Untreated Discharges 6.2 Standard 2 - Peak Rate Attenuation 6.3 Standard 3 - Stormwater Recharge 6.4 Standard 4 - Water Quality 6.5 Standard 5 - Land And Uses With Higher Pollution Loads 6.6 Standard 6 - Critical Areas 6.7 Standard 7 - Redevelopment Project 6.8 Standard 8 - Construction Period Controls 6.9 Standard 9 - Long Term Operation and Maintenance Program 6.10 Standard 10 - Prohibition of Illicit Discharges CONCLUSION RES 1 - Locus Plan ENDICES addix A - Site Construction Controls For The Proposed Family Dollar Facility addix B - Permanent Stormwater System Operation and Maintenance Program addix C - Interim Illicit Discharge Statement addix D - Checklist For Stormwater Report	6.2 Standard 2 - Peak Rate Attenuation 6.3 Standard 3 - Stormwater Recharge 6.4 Standard 4 - Water Quality 6.5 Standard 5 - Land And Uses With Higher Pollution Loads 6.6 Standard 6 - Critical Areas 6.7 Standard 7 - Redevelopment Project 6.8 Standard 8 - Construction Period Controls 6.9 Standard 9 - Long Term Operation and Maintenance Program 6.10 Standard 10 - Prohibition of Illicit Discharges CONCLUSION RES 1 - Locus Plan CNDICES adix A - Site Construction Controls For The Proposed Family Dollar Facility adix B - Permanent Stormwater System Operation and Maintenance Program adix C - Interim Illicit Discharge Statement adix D - Checklist For Stormwater Report

1.0 INTRODUCTION

It is proposed to construct a retail store in New Bedford which requires Site Plan Review and a Special Permit from the Planning Board. One element of the submittal package is a Stormwater Report. This document has been prepared to satisfy that requirement.

2.0 EXISTING CONDITIONS

The site is a vacant parcel on the south side of Swift Street and west side of Orchard Street. It is referenced as Lot 292 on Assessors Map 23. It contains 43,500 square feet of area. Historically, the site was covered with a large manufacturing building. The site slopes down from a high point at elevation 17 at the northeast end to elevation 10 at the southwest end of the site. The land surface is covered with grass with some shrubs.

3.0 PROPOSED DEVELOPMENT

It is proposed to construct a 9,180 square foot, single story, retail store with an ancillary parking lot with 30 standard spaces and 2 van accessible handicap spaces. The New Bedford zoning ordinance requires 46 parking spaces. A special permit is being requested to require fewer spaces because the Family Dollar operation does not need more than 30 spaces and there is ample available parking on Swift and Orchard Streets. Requiring fewer parking spaces will result in a greater amount of pervious landscaping.

4.0 PHYSICAL ENVIRONMENT

The site is a listed Massachusetts Contingency Plan (MCP) site due to impacted soil from the former tire manufacturing operation. In addition, the soil is geotechnically unsuitable in its current condition. The soil from the entire site will be excavated down to the original slab elevation. Unsuitable debris will be removed and then the soil will be placed and compacted in one foot lifts. All solid waste will be transported to a licensed disposal facility. Other than the above, there are no unusual geologic, archeologic, scenic or historic features or structures. There are no stone walls, trails, open space links, or indigenous wildlife.

There is undeveloped land to the west and south. A city park is to the north and the John Devalles School and the Monte Pio Luzo American Club is to the east.

5.0 SURFACE WATER AND SUBSURFACE CONDITIONS

The site contains urban fill which, as in many areas of New Bedford, have been impacted by petroleum hydrocarbons, metals and poly nuclear aromatic hydrocarbons (PAHs). After

development, these soils will be inaccessible since they will be beneath pavement and the concrete slab. During construction, they will be managed with a written soil management plan.

Historical releases of lubricating oils and other petroleum products (No. 6 fuel oil) have resulted in the detection of TPH and the following PAHs in soils; acenaphthene, anthracene, benzo(a)anthracene, benzo(b)fluoranthene, benzo(k)fluoranthene, benzo(g,h,i)perylene, benzo(a)pyrene, chrysene, dibenzo(a,h)anthracene, dibenzofuran, fluoranthene, fluorene, indeno(1,2,3-cd)pyrene, naphthalene, phenanthrene and pyrene. Lead, butyl benzl phthalate and the following VOCs were also detected in soils: xylenes, methylene chloride, chloroform, tetrachloroethene, 1,2 dichloroethene and styrene.

Historical releases of lubricating oils and other petroleum products (No. 6 fuel oil) have resulted in the detection of TPH, naphthalene, and benzene in groundwater. Creosols (2 methylphenol, 4 methylphenol), 2,4 dimethylphenol, benzoic acid, phenol, bis 2 ethyl hexyl phthalate and the following VOCs were also detected in groundwater: ethylbenzene, toluene, xylenes, methyl tertiary butyl ether, isopropylbenzene, n-propylbenzene, 1,2,4, trimethylbenzene, methylene chloride, chloroform, 1,1 dichloroethene, 1,1 dichloroethene, 1,2 dichloroethene, trichloroethene, vinyl chloride, trichlorofluromethane, 1,4 dichlorobenzene and 4, methyl 2 pentanone.

Surface water will be collected in a deep sump catch basin and treated with a Stormceptor brand storm treatment system and then discharged to a storm drain main which will be installed by the current landowners from a drain manhole in front of the Portugese Club toward the south end of Orchard Street. Due to the presence of impacted soil, on site infiltration of stormwater is ill advised.

6.0 COMPLIANCE WITH STORMWATER MANAGEMENT STANDARDS

This section of the report provides the requisite documentation that each of the Stormwater Management Standards are being met in accordance with Volume 3 of the Stormwater Manual.

6.1 Standard 1 - No Untreated Discharges

Standard 1 requires that there be no untreated storm discharges and that there be no erosion to wetlands. As shown on the site plans, the site's stormwater will be conveyed by pipe to a Stormceptor treatment system. Therefore, Standard 1 will be met.

6.2 Standard 2 - Peak Rate Attenuation

Standard 2 requires that for inland wetland systems there be no increase in the peak stormflow. As presented in Appendix E, the stormwater computations demonstrate that there will be a decrease in the peak rate of runoff for all design storms. Therefore, this standard will be met.

6.3 Standard 3 - Stormwater Recharge

Standard 3 requires that post-development groundwater recharge approximate current groundwater recharge. As presented in Section 5, the soil at the site has contaminants that make it inadvisable to infiltrate. The DEP stormwater manual acknowledges this. Therefore, standard 3 will be met.

6.4 Standard 4 - Water Quality

Standard 4 requires removal of 80% of total suspended solids from the storm runoff. Under developed conditions, the runoff will be passed through Stormceptor treatment system which has been approved by the STEP process. It is listed in Table LUHPPL of the Stormwater Manual as being acceptable for sites with higher pollution loads.

ВМР	TSS Removal Rate	Initial Pollution Load	Amount Removed	Remaining Load
Stormceptor	.80	1.0	.80	.10
Total Removal			.80	

Since 80% of the TSS will be removed, Standard 4 will be met.

6.5 Standard 5 - Land And Uses With Higher Pollution Loads

Since the proposed development is a retail facility, it is not considered to be a land use with higher pollution loads. Proposed source controls are presented in Appendix B - Stormwater System Operation and Maintenance Plan. The storm system has been designed to, at a minimum, pass the first one inch of runoff through this BMP. Therefore, Standard 5 will be met.

6.6 Standard 6 - Critical Areas

The site does not discharge to critical areas. However, as detailed in the preceding subsection, all standards for discharge to critical areas in the Stormwater Manual are being met by this storm system BMP design. Therefore, Standard 6 will be met.

6.7 Standard 7 - Redevelopment Project

Qualified redevelopment projects are allowed to only meet Standards 1 to 6 to the "maximum extent practicable". This proposed development does qualify as a redevelopment project. However, all standards will be met.

6.8 Standard 8 - Construction Period Controls

Standard 8 requires the preparation and implementation of an erosion and sediment control program for the site construction phase. Appendix A and Sheet 7 of the site plans present this program which is in full compliance with Standard 8.

6.9 Standard 9 - Long Term Operation and Maintenance Program


Standard 9 requires the preparation of an ongoing program to maintain the stormwater quality and quantity controls in optimal operating condition. Appendix B presents a long term Operation and Maintenance Program which is in full compliance with Standard 9. Therefore, Standard 9 will be met.

6.10 Standard 10 - Prohibition of Illicit Discharges

Standard 10 prohibits illicit discharges to Stormwater Management systems. Appendix C presents an interim illicit discharge statement which is in compliance with Standard 10. The approval should include the requirement that a final illicit discharge statement be provided when construction is complete.

7.0 CONCLUSION

The proposed project will convert a vacant lot to a retail facility. All stormwater standards will be met.



APPENDICES

SITE CONSTRUCTION CONTROLS FOR THE PROPOSED FAMILY DOLLAR RETAIL FACILITY

SITE CONSTRUCTION CONTROLS FOR THE PROPOSED FAMILY DOLLAR FACILITY

1.0 INTRODUCTION

It is proposed to construct a retail facility. Surrounding areas must be protected from any impacts from the proposed construction activities. The following erosion and sediment control program material management practices and spill control program have been developed to that end.

2.0 PRECONSTRUCTION MEASURES

Prior to the initiation of any construction, silt fencing shall be installed as shown on the plans. A preconstruction conference shall then be held with the New Bedford Department of Public Infrastructure in order to confirm that sediment control conditions are adequate for construction to start.

3.0 CONSTRUCTION PERIOD MEASURES

The following are the minimal measures required for erosion and sediment control, material handling and for spill control.

3.1 EROSION AND SEDIMENTATION CONTROL

The following measures shall be maintained throughout the site construction phase of the project.

Catch Basin Protection

Proposed catch basins shall be protected with haybale barriers or filters prior to the completion of paving.

Drainage Swale Haybale Check Dams

Haybales shall also be placed across construction ditches during construction to limit the transport of sediment into drainage systems and waterways.

Stabilized Construction Entrance

A temporary stabilized construction entrance shall be installed at both Orchard and Swift Streets. The purpose of the construction entrance is to remove sediment attached to vehicle tires and minimize its transport and deposition onto public road surfaces. The construction entrance shall be composed of a 6-inch thick (minimum) bed of 2-inch diameter crushed stone that extends a minimum of 50 feet. The construction entrance shall be a minimum of 25 feet wide, and shall flare to a minimum width of 45 feet wide at the junction with the roadway. The crushed stone bed shall be replenished as necessary to maintain the proper function.

Silt Fences

Silt fences shall be placed at the limits of work where the slope is less than 4:1. Typically, they shall be installed adjacent to resource areas, where soil shall be exposed due to construction related activities, as depicted on the plans. They shall be placed in a sturdy, upright position and supported/anchored to withstand the forces of the elements and the circumstances of construction activities. The fences shall be installed in a manner that shall prevent runoff from passing over, under, or around the fence (i.e. all of the runoff shall pass through the fence). They shall be attached to posts (either steel or wood) in sufficient number to support the fence. The posts shall typically be placed 4 to 8 feet apart. It shall be the construction contractor's responsibility to maintain the fence in a functional condition throughout the duration of construction activities. The contractor shall also remove any large accumulations of sediment in a timely manner and dispose the material appropriately.

Haybales

Haybales shall be placed in conjunction with silt fences, at the limit of work on steep slopes only. Steep slopes for this project are those which are 4:1 or steeper. They shall be staked with metal or wood stakes to anchor them to the ground. The contractor is responsible for maintaining the haybales in good condition and replacing them as necessary. Bales that deteriorate and are no longer intact or that become plugged with sediment shall be removed and disposed. They shall be replaced with new haybales installed as described above.

Permanent Erosion Control Measures

Distinguished from temporary erosion control measures, the following permanent erosion control measures shall remain in place after the completion of the project.

Erosion Control Matting

Control matting shall be used on slopes 4:1 or steeper and in sloped planted areas subject to high wind exposure. This matting shall serve to stabilize these steeper slopes and prevent erosion prior to the slope stabilization. The matting shall also assist in maintaining the soil moisture necessary to support dense vegetative plantings proposed for some of the steeper slopes.

Erosion and Sediment Control - Maintenance

The project general contractor shall have primary responsibility for implementing temporary and permanent controls described in the plan and shall be responsible for assuring contractor compliance with contract documents including all erosion and sediment control measures.

- Damaged or deteriorated items shall be repaired or replaced immediately after identification.
- The underside of haybales should be kept in close contact with the earth and reset as necessary.

- Silt fence and haybales shall be inspected after every major rainfall runoff event (over ½" depth of precipitation) or every 14 days, whichever occurs first. All damaged or misaligned fences shall be immediately repaired. Silt shall be immediately removed from all areas of the silt fence when depth of accumulation exceeds 9 inches. Each report shall be documented on the form enclosed in Attachment A-1.
- Sumps shall be inspected after every major rainfall runoff event (over ½" depth of precipitation) or every 14 days, whichever occurs first. Silt shall be immediately removed from all sumps where the depth of accumulation exceeds 9 inches.
- All exposed construction areas shall be stabilized upon completion in order to minimize the time that these areas are unstabilized.

3.2 MATERIALS MANAGEMENT PRACTICES

The following are the material management practices that shall be used to reduce the risk of spills or other accidental exposure of materials and substances to stormwater runoff. The Contractor's Superintendent shall be responsible for ensuring that these procedures are followed:

1. Good Housekeeping

The following good housekeeping practices shall be followed on-site during construction:

- a. An effort shall be made to store only enough products required to do the job.
- b. All materials stored on-site shall be stored in a neat, orderly manner and, if possible, under a roof or in a containment area. At a minimum, all containers shall be stored with their lids on when not in use. Drip pans shall be provided under all dispensers.
- c. Products shall be kept in their original containers with the original manufacturer's label in legible condition.
- d. Substances shall not be mixed with one another unless recommended by the manufacturer.
- e. Whenever possible, the product shall be used up before disposing the container.
- f. Manufacturer's recommendations for proper use and disposal shall be followed.
- g. The Contractor's Superintendent shall be responsible for daily inspections to ensure proper use and disposal of materials.

2. Hazardous Substances

These practices shall be used to reduce the risks associated with hazardous substances. Material Safety Data Sheets (MSDSs) for each product with hazardous properties that is used at the project shall be obtained and used for the proper management of potential wastes that may result from these products. An MSDS shall be posted in the immediate area where such product is stored and/or used and another copy of each MSDS shall be maintained in the job trailer at the project. Each employee who must handle a hazardous substance shall be instructed on the use of MSDS sheets and the specific information in the applicable MSDS for the product he/she is using, particularly-regarding spill control techniques.

- a. Products shall be kept in original containers with the original labels in legible condition.
- b. Original labels and MSDS shall be procured and used for each product.
- c. If surplus product must be disposed, manufacturer's and local/state/federal required methods for proper disposal must be followed.

3. Hazardous Waste

It is imperative that hazardous waste be properly identified and handled in accordance with all applicable hazardous waste standards, including the storage, transport and disposal of hazardous wastes. There are significant penalties for the improper handling of hazardous wastes. It is important that the Site Superintendent seeks appropriate assistance in making the determination of whether a substance or material is a hazardous waste. For example, hazardous waste may include certain hazardous substances, as well as pesticides, paints, paint solvents, cleaning solvents, pesticides, contaminated soils, and other materials, substances or chemicals that have been discarded (or are to be discarded) as being out-of-date, contaminated, or otherwise unusable, and can include the containers for those substances. The Contractor's Superintendent is also responsible for ensuring that site personnel are instructed as to these Hazardous Waste requirements and also that the requirements are being followed.

4. Product Specific Practices

The following product specific practices shall be followed on the job site:

Petroleum Products

On-site vehicles shall be monitored for leaks and receive regular preventative maintenance to reduce the chance of leakage. Petroleum products shall be stored in tightly sealed containers which are clearly labeled. Petroleum storage tanks shall be located at a minimum of 100 linear feet from drainage ways, inlets and surface waters. Any petroleum storage tanks stored on-site shall be located within a containment area that is designed with an impervious surface between the tank and the ground. The secondary containment must be designed to provide a containment volume that is equal to 110% of the volume of the largest tank. Any mobile petroleum tank shall be parked in a vehicular service area surrounded by a berm that provides a containment volume that is equal to 110% of the volume of the largest tank. Containment must provide sufficient volume to contain expected precipitation and 110% volume of the largest tank. Accumulated rainwater or spills from containment areas are to be promptly pumped into a containment device and disposed properly by a licensed hazardous waste transporter. Drip pans shall be provided for all dispensers. Any asphalt substances used on-site shall be applied according to the manufacturer's recommendations. The location of any fuel tanks and/or equipment storage areas must be identified on the Erosion Control Plan by the Contractor once the locations have been determined.

Fertilizers

Fertilizers shall be applied only in the minimum amounts recommended by the manufacturer. Once applied, fertilizer shall be worked in the soil to limit exposure to stormwater. The contents of any partially used bags of fertilizer shall be transferred to a sealable plastic bin to avoid spills.

Cleaning Solvents

All containers shall be tightly sealed and stored when not in use. Excess solvents shall not be discharged to the storm sewer system, but shall be properly disposed of according to manufacturer's instructions or state and federal regulations.

Concrete Wastes

Concrete trucks shall be allowed to wash out or discharge surplus concrete or drum wash water on the project site, but only in specifically designated diked and impervious washout areas which have been prepared to prevent contact between the concrete wash and stormwater. Waste generated from concrete wash water shall not be allowed to flow into drainage ways, inlets, receiving waters or any location other than the designated concrete washout. Waste concrete may be poured into forms to make rip-rap or other useful concrete products. Concrete washouts shall be located at minimum of 100 linear feet from drainage ways, inlets, surface waters and wetland resource areas.

The hardened residue from the concrete washout diked areas shall be disposed in the same manner as other non-hazardous construction waste materials or may be broken up and used on site as deemed appropriate by the Contractor. Maintenance of the washout is to include removal of hardened concrete. Facility shall not be filled beyond 95% capacity and shall be cleaned out once 75% full unless a new facility is constructed. The Contractor's Superintendent shall be responsible for seeing that these procedures are followed.

Saw-cut Portland Cement Concrete (PCC) slurry shall not be allowed to enter storm drains or watercourses. Saw-cut residue should not be left on the surface of pavement or be allowed to flow over and off pavement. Residue from saw-cutting and grinding shall be collected by vacuum and disposed of in the concrete washout facility.

5. Solid and Construction Wastes

All waste materials shall be collected and disposed at an appropriate solid waste disposal area.

6. Sanitary Wastes

A minimum of one portable sanitary unit shall be provided for every ten (10) workers on the site. Sanitary waste shall be collected from the portable units a minimum of one time per

week by a licensed portable facility provider in compliance with local and state regulations.

Sanitary waste units shall be located in an area where the likelihood of the unit contributing to stormwater discharges is negligible. Additional containment BMPs must be implemented, such as gravel bags or specially designed plastic skid containers around the base, to prevent wastes from contributing to stormwater discharges.

7. <u>Contaminated Soils</u>

Any contaminated soils (resulting from spills of hazardous substances or oil or discovered during the course of construction) which may result from construction activities shall be contained and cleaned up immediately and in accordance with applicable state and federal regulations. Contaminated soils not resulting from construction activities, or which pre-existed construction activities, but which are discovered by virtue of construction activities, should be reported in the same manner as spills, but with sufficient information to indicate that the discovery of an existing condition is being reported. If there is a release that occurs by virtue of the discovery of existing contamination, this should be reported as a spill, if it otherwise meets the requirements for a reportable spill.

3.3 SPILL PREVENTION AND RESPONSE PROCEDURES

The Contractor shall train personnel in the proper handling and cleanup of spilled hazardous substances or oil. No spilled hazardous substances or oil shall be allowed to come in contact with stormwater discharges. If such contact occurs, the stormwater discharge shall be contained on site until appropriate measures in compliance with state and federal regulations are taken to dispose of such contaminated stormwater. It shall be the responsibility of the Contractor's Superintendent to be properly trained, and to train all personnel in spill prevention and cleanup procedures.

- 3.3.1 In order to prevent or minimize the potential for a spill of hazardous substances or oil to come into contact with stormwater, the following steps shall be implemented:
 - a. All hazardous substances or oil (such as pesticides, petroleum products, fertilizers, detergents, construction chemicals, acids, paints, paint solvents, cleaning solvents, additives for soil stabilization, concrete curing compounds and additives, etc.) shall be stored in a secure location, with their lids on, preferably under cover, when not in use.
 - b. The minimum practical quantity of such materials shall be kept at the project.
 - c. A spill control and containment kit (containing, for example, absorbent materials, acid neutralizing powder, brooms, dust pans, mops, rags, gloves, plastic and metal trash containers, etc.) shall be provided at the storage site.
 - d. Manufacturer's recommended methods for spill cleanup shall be clearly posted and site personnel shall be trained regarding these procedures and the location of the information and cleanup supplies.

- e. It is the Contractor's responsibility to ensure that hazardous waste discovered or generated at the project site is disposed of properly by a licensed hazardous material disposal company. The Contractor is responsible for not exceeding hazardous waste storage requirements mandated by the EPA or state and local authority.
- 3.3.2 A spill contingency plan shall be implemented during construction, including the following provisions:
 - Equipment necessary to quickly attend to inadvertent spills or shall be stored on-site in a secure but accessible location. Such equipment shall include:
 - 1. Safety goggles.
 - 2. Chemically resistant gloves and overshoe boots.
 - 3. Water and chemical fire extinguishers.
 - Sand and shovels.
 - 5. Suitable absorbent materials.
 - 6. Storage containers.
 - 7. First aid equipment.
- 3.3.3 In the event of a spill of hazardous substances or oil, the following procedures must be followed:
 - a. All measures must be taken to contain and abate the spill and to prevent the discharge of the hazardous substance or oil to stormwater or off-site. (The spill area must be kept well ventilated and personnel must wear appropriate protective clothing to prevent injury from contact with the hazardous substances.)
 - b. For spills of less than five (5) gallons of material, proceed with source control and containment, clean-up with absorbent materials or other applicable means unless an imminent hazard or other circumstances dictate that the spill should be treated by a professional emergency response contractor.
 - c. For spills greater than five (5) gallons of material, immediately contact Richard J. Rheaume, LSP, Prime Engineering, Inc., P.O. Box 1088, Lakeville, MA 02347 (508) 947-0050. Provide information on the type of material spilled, the location of the spill, the quantity spilled, and the time of the spill and proceed with prevention, containment and/or clean-up if so desired.
 - d. Spills that exceed reportable quantities of certain substances specifically mentioned in federal regulations 40 CFR 110, 40 CFR 117, and 40 CFR 302 must be immediately reported to the EPA National Response Center, Telephone (800) 242-8802.

The Contractor's Superintendent shall be the spill prevention and response coordinator. He shall designate the individuals who shall receive spill prevention and response training. These individuals shall each become responsible for a particular phase of prevention and response. The names of these personnel shall be posted in the material storage area and in the office trailer on-site.

Any spill that occurs shall be documented on a spill report form that is enclosed as Attachment B-2.

ATTACHMENT A-1

INSPECTION AND MAINTENANCE REPORT FORM AND POST-AUTHORIZATION RECORDS

STORMWATER POLLUTION PREVENTION PLAN WEEKLY INSPECTION AND MAINTENANCE REPORT FORM

	Title	Date:
Specific Site Location:		·
:. ST	ABILIZATION MEASI	JRES
AREA	INSTALLED? (Yes/No)	CONDITION OF STABILIZATION MEASURI
Silt Fences		
Haybales		
Stabilization for Stockpiles		
Seeding and Planting		
Geotextile Fabrics		
TO BE PERFORMED B	Y:	ON OR
	Y:	
В		
Bi Make note	EFORE:	of the following:
Bi Make note	EFORE:of the date and location	of the following: vities
Make note *Temporar	EFORE: of the date and location 'The start of grading active y or permanent cease of g	of the following: vities rading activities
Make note *Temporar	eFORE:of the date and location •The start of grading activ	of the following: vities trading activities stabilization

STORMWATER POLLUTION PREVENTION PLAN WEEKLY INSPECTION AND MAINTENANCE REPORT FORM Continued

Weather information for the period since the last inspection (or since commencement of construction activity if the first inspection) including a best estimate of the beginning of each storm event, duration of each storm event, approximate amount of rainfall for each storm event
(in inches), and whether any discharges occurred;
· ·
Weather information and a description of any discharges occurring at the time of the inspection

Form A-III

STORMWATER POLLUTION PREVENTION PLAN (SWPPP) INSPECTION CHECKLIST - TO BE COMPLETED BY CONTRACTOR

Inspected By:		, Title	Date:	
YES	NO	DOES NOT		TYEM .
			Are the BMPs called location and according	for on the SWPPP installed in the proper og to the specification of the SWPPP?
			Are all operational st flow?	ormwater inlets protected from sediment
			Do any erosion/siltat out to maintain adequ	ion control measure require repair or clean nate function? If yes, indicate which ones.
				tion traffic routes, parking, and storage of ies restricted to areas specifically uses?
			Are the locations of materials in approve	temporary soil stockpiles or construction d areas?
				ndscaped areas require maintenance on, seeding or mulching?
			Is there any evidence	e that sediment is leaving the site?
·			Is there any evidence	e of erosion on cut or fill slopes?
				e of sediment, debris, or mud on public s with site access roads?
	-		Notes:	
<u></u>	***			
Action to	be Taken:		.:	

Note: See Page 13, Part 4 (Inspections) of the General Permit (Attachment "L") for additional inspection report requirements.

APPENDIX B

PERMANENT STORMWATER SYSTEM OPERATION AND MAINTENANCE PROGRAM

LONG TERM POLLUTION PREVENTION PROGRAM PERMANENT OPERATION AND MAINTENANCE PROGRAM FOR FAMILY DOLLAR FACILITY

1.0 INTRODUCTION

The Family Dollar Facility site has been designed to ensure stormwater quality. In order for this to continue in the long term, it is necessary to implement the following Long Term Operation and Maintenance Program.

2.0 RESPONSIBLE PARTY

Hunt Real Estate Services, Inc. 5100 W Kennedy Blvd., Suite 100 Tampa, FL 33609 ATTN: Kathleen Hess Telephone: (727) 458-4055

3.0 SOURCE CONTROL MEASURES

The most effective means of providing clean runoff is to prevent pollutants from coming into contact with the stormwater in the first place. This involves the following:

- 1. Keeping de-icing agents, fertilizers, stockpiles, etc. covered at all times. All such products shall be stored indoors or off-site.
- 2. All landscaping, fertilization, and other grounds maintenance shall be done by professional ground keepers who are trained at how to maintain the grounds.
- 3. An annual parking lot sweeping program shall be implemented. This program shall include removal of windblown debris and litter from landscaped areas.
- 4. A supply of speedy dry type oil absorbent material shall be kept on site to allow for the quick cleanup of minor spills.

4.0 MAINTENANCE OF STORM SYSTEM

This section presents the periodic maintenance that must be completed:

- 1. The catch basins shall be cleaned annually.
- 2. The Stormceptor shall be maintained as shown on the plans and as specified in Attachment B-1.

5.0 SPILL PREVENTION AND RESPONSE PLAN

The Property Manager, shall train personnel in the proper handling and cleanup of spilled hazardous substances or oil. No spilled hazardous substances or oil shall be allowed to come in contact with

stormwater discharges. If such contact occurs, the stormwater discharge shall be contained on site until appropriate measures in compliance with state and federal regulations are taken to dispose such contaminated stormwater. It shall be the responsibility of the Property Manager to be properly trained, and to train all personnel in spill prevention and cleanup procedures.

In order to prevent or minimize the potential for a spill of hazardous substances or oil to come into contact with stormwater, the following steps shall be implemented:

- a. All hazardous substances or oil (such as pesticides, petroleum products, fertilizers, detergents, chemicals, acids, paints, paint solvents, cleaning solvents, additives for soil stabilization, concrete curing compounds and additives, etc.) shall be stored in a secure location, with their lids on, preferably under cover, when not in use.
- b. The minimum practical quantity of such materials shall be kept at the facility.
- c. A spill control and containment kit (containing, for example, absorbent materials, acid neutralizing powder, brooms, dust pans, mops, rags, gloves, plastic and metal trash containers, etc.) shall be provided at the site.
- d. Manufacturer's recommended methods for spill cleanup shall be clearly posted and site maintenance personnel shall be trained regarding these procedures and the location of the information and cleanup supplies.
- e. It is the Property Manager's responsibility to ensure that hazardous waste discovered or generated at the project site are disposed properly by a licensed hazardous material disposal company. The Property Manager is responsible for not exceeding hazardous waste storage requirements mandated by the EPA or state and local authority.

A spill contingency plan shall be implemented including the following provisions:

- Equipment necessary to quickly attend to inadvertent spills or shall be stored on-site in a secure but accessible location. Such equipment shall include:
 - 1. Safety goggles.
 - 2. Chemically resistant gloves and overshoe boots.
 - Water and chemical fire extinguishers.
 - 4. Sand and shovels.
 - 5. Suitable absorbent materials.
 - 6. Storage containers.
 - 7. First aid equipment.

In the event of a spill of hazardous substances or oil, the following procedures must be followed:

- a. All measures must be taken to contain and abate the spill and to prevent the discharge of the hazardous substance or oil to stormwater or off-site. (The spill area must be kept well ventilated and personnel must wear appropriate protective clothing to prevent injury from contact with the hazardous substances.)
- b. For spills of less than five (5) gallons of material, proceed with source control and containment, clean-up with absorbent materials or other applicable means unless an

- imminent hazard or other circumstances dictate that the spill should be treated by a professional emergency response contractor.
- c. For spills greater than five (5) gallons of material, immediately contact Richard J. Rheaume, LSP, Prime Engineering, Inc., P.O. Box 1088, Lakeville, MA 02347 at (508) 947-0050 and provide information on the type of material spilled, the location of the spill, the quantity spilled, and the time of the spill and proceed with prevention, containment and/or clean-up, if so desired.
- d. Spills of amounts that exceed reportable quantities of certain substances specifically mentioned in federal regulations 40 CFR 110, 40 CFR 117, and 40 CFR 302 must be immediately reported to the EPA National Response Center at (800) 242-8802. The Property Manager shall be the spill prevention and response coordinator. He shall designate the individuals who shall receive spill prevention and response training. These individuals shall each become responsible for a particular phase of prevention and response. The names of these personnel should be posted in the material storage area and in the property office.

Any spill that occurs shall be documented on a spill report form that is enclosed as Attachment B-2.

6.0 SNOW AND ICE REMOVAL

Snow removal shall be primarily done by mechanical removal rather than chemical application. The judicious use of sand and salt without chemical additives is allowed in order to protect the safety of the public.

ATTACHMENT B-1

STORMCEPTOR STORM TREATMENT SYSTEM MAINTENANCE PROCEDURES

4.0 Stormceptor Maintenance Guidelines

The performance of all storm water quality measures decrease as they fill with sediment. Although the maintenance frequency will be site specific, Rinker Materials generally recommends annual maintenance be performed or when the sediment volume in the unit reaches 15% of the total storage. This recommendation is based on several factors:

- Minimal performance degradation due to sediment build-up.
- Sediment removal is easier when removed on a regular basis (as sediment builds up it compacts and solidifies making maintenance more difficult).
- Development of a routine maintenance interval helps ensure a regular maintenance schedule is followed. Although the frequency of maintenance will depend on site conditions, it is estimated that annual maintenance will be required for most applications; annual maintenance is a routine occurrence which is easy to plan for and remember.

Hydrocarbon Spills

In the event of any hazardous material spill, Rinker Materials recommends maintenance be performed immediately. Maintenance should be performed by a licensed liquid waste hauler. You should also notify the appropriate regulatory agencies as required.

4.1 Recommended Maintenance Procedure

Oil is removed through the 6" inspection/oil port and sediment is removed through the 24" diameter outlet riser pipe. Alternatively, oil could be removed from the 24" opening if water is removed from the treatment chamber, lowering the oil level below the drop pipes.

The depth of sediment can be measured from the surface of the Stormceptor with a dipstick tube equipped with a ball valve (Sludge Judge*). Rinker Materials recommends maintenance be performed once the sediment depth exceeds the guideline values provided in Table 8.

Table 8. Sedimo Required	ent Depths Indicating Maintenance*
Model	Sediment Depth
450 <i>i</i>	8" (200 mm)
900	8" (200 mm)
1200	10" (250 mm)
1800	15" (375 mm)
2400	12" (300 mm)
3600	17" (425 mm)
4800	15" (375 mm)
6000	18" (450 mm)
7200	15" (375 mm)
11000s	17" (425 mm)**
13000s	20" (500 mm)**
16000s	17" (425 mm)**

^{*} Depths are approximate

No entry into the unit is required for routine maintenance of the Inlet Stormceptor or the smaller disc insert models of the In-Line Stormceptor. Entry to the level of the by-pass may be required for servicing the larger in-line models. Any potential obstructions at the inlet can be observed from the surface. The by-pass chamber has been designed as a platform for authorized maintenance personnel, in the event that an obstruction needs to be removed, drain flushing needs to be performed, or camera surveys are required.

Typically, maintenance is performed by the Vacuum Service Industry, a well established sector of the service industry that cleans underground tanks, sewers, and catch-basins. Costs to clean a Stormceptor will vary based on the size of the unit and transportation distances. If you need assistance for cleaning a Stormceptor unit, contact your local Rinker Materials representative, or the Rinker Materials Stormceptor Information Line at (800) 909-7763.

^{**} Depths in each structure

Disposal

The requirements for the disposal of material from a Stormceptor are similar to that of any other Best Management Practices (BMPs). Local guidelines should be consulted prior to disposal of the separator contents.

In most areas the sediment, once dewatered, can be disposed of in a sanitary landfill. It is not anticipated that the sediment would be classified as hazardous waste. In some areas, mixing the water with the sediment will create a slurry that can be discharged into a trunk sanitary sewer. In all disposal options, approval from the disposal facility operator/agency is required. Petroleum waste products collected in Stormceptor (oil/chemical/fuel spills) should be removed by a licensed waste management company.

ATTACHMENT B-2

BLANK SPILL REPORT

SPILL REPORT

SITE ADDRESS:		
NAME OF PERSON COMPLETING THIS FOR	KM:	
DATE:	—	
TYPE OF MATERIAL:	QUANTITY:	
DESCRIPTION OF RELEASE:		
CIRCUMSTANCES LEADING TO RELEASE:		
	-	
LOCATION OF SPILL:		
RESPONSE ACTIONS:		
PERSONNEL:		
I EXOCITATELY		
ATTACH DOCUMENTATION OF NOTIFICATION OF NOTIFI		
(COPY AS NEEDED)		

APPENDIX C

INTERIM ILLICIT DISCHARGE STATEMENT

INTERIM ILLICIT DISCHARGE STATEMENT

1.0 INTRODUCTION

The following is an interim illicit discharge statement based on existing conditions and design conditions. Once construction is complete, a final illicit discharge statement shall be issued to the New Bedford Planning Board based on as built conditions.

2.0 **EXISTING CONDITIONS**

The existing facility is a vacant lot. There are no known illicit connections in this area. No sources of illicit discharges were uncovered when test pits were excavated. Based on this investigation, to the best of my knowledge there are no current illicit discharges to the storm drainage system. If during construction, an illicit discharge is discovered, it shall be removed immediately.

3.0 PROPOSED DESIGN

The proposed design calls for separate storm services to the storm drain. There are no points in the proposed storm drainage system where illicit discharges are likely to occur.

Certain types of discharges are allowable under the U.S. Environmental Protection Agency Construction General Permit, and it is the intent of the site's Long Term Pollution Prevention Plan to allow such discharges. These types of discharges shall be allowed under the conditions that no pollutants shall be allowed to come in contact with the water prior to or after its discharge.

I hereby certify that the preceding is accurate

Richard J. Rheaume

Prime Engineering Mnc.

NOV. 11, 2016 Date

APPENDIX D

CHECKLIST FOR STORMWATER REPORT



Checklist for Stormwater Report

A. Introduction

Important: When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.





A Stormwater Report must be submitted with the Notice of Intent permit application to document compliance with the Stormwater Management Standards. The following checklist is NOT a substitute for the Stormwater Report (which should provide more substantive and detailed information) but is offered here as a tool to help the applicant organize their Stormwater Management documentation for their Report and for the reviewer to assess this information in a consistent format. As noted in the Checklist, the Stormwater Report must contain the engineering computations and supporting information set forth in Volume 3 of the Massachusetts Stormwater Handbook. The Stormwater Report must be prepared and certified by a Registered Professional Engineer (RPE) licensed in the Commonwealth.

The Stormwater Report must include:

- The Stormwater Checklist completed and stamped by a Registered Professional Engineer (see page 2) that certifies that the Stormwater Report contains all required submittals.¹ This Checklist is to be used as the cover for the completed Stormwater Report.
- Applicant/Project Name
- Project Address
- Name of Firm and Registered Professional Engineer that prepared the Report
- Long-Term Pollution Prevention Plan required by Standards 4-6
- Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan required by Standard 8²
- Operation and Maintenance Plan required by Standard 9

In addition to all plans and supporting information, the Stormwater Report must include a brief narrative describing stormwater management practices, including environmentally sensitive site design and LID techniques, along with a diagram depicting runoff through the proposed BMP treatment train. Plans are required to show existing and proposed conditions, identify all wetland resource areas, NRCS soil types, critical areas, Land Uses with Higher Potential Pollutant Loads (LUHPPL), and any areas on the site where infiltration rate is greater than 2.4 inches per hour. The Plans shall identify the drainage areas for both existing and proposed conditions at a scale that enables verification of supporting calculations.

As noted in the Checklist, the Stormwater Management Report shall document compliance with each of the Stormwater Management Standards as provided in the Massachusetts Stormwater Handbook. The soils evaluation and calculations shall be done using the methodologies set forth in Volume 3 of the Massachusetts Stormwater Handbook.

To ensure that the Stormwater Report is complete, applicants are required to fill in the Stormwater Report Checklist by checking the box to indicate that the specified information has been included in the Stormwater Report. If any of the information specified in the checklist has not been submitted, the applicant must provide an explanation. The completed Stormwater Report Checklist and Certification must be submitted with the Stormwater Report.

¹ The Stormwater Report may also include the Illicit Discharge Compliance Statement required by Standard 10. If not included in the Stormwater Report, the Illicit Discharge Compliance Statement must be submitted prior to the discharge of stormwater runoff to the post-construction best management practices.

² For some complex projects, it may not be possible to include the Construction Period Erosion and Sedimentation Control Plan in the Stormwater Report. In that event, the Issuing authority has the discretion to issue an Order of Conditions that approves the project and includes a condition requiring the proponent to submit the Construction Period Erosion and Sedimentation Control Plan before commencing any land disturbance activity on the site.



Checklist for Stormwater Report

B. Stormwater Checklist and Certification

The following checklist is intended to serve as a guide for applicants as to the elements that ordinarily need to be addressed in a complete Stormwater Report. The checklist is also intended to provide conservation commissions and other reviewing authorities with a summary of the components necessary for a comprehensive Stormwater Report that addresses the ten Stormwater Standards.

Note: Because stormwater requirements vary from project to project, it is possible that a complete Stormwater Report may not include information on some of the subjects specified in the Checklist. If it is determined that a specific item does not apply to the project under review, please note that the item is not applicable (N.A.) and provide the reasons for that determination.

A complete checklist must include the Certification set forth below signed by the Registered Professional Engineer who prepared the Stormwater Report.

Registered Professional Engineer's Certification

I have reviewed the Stormwater Report, including the soil evaluation, computations, Long-term Pollution Prevention Plan, the Construction Period Erosion and Sedimentation Control Plan (if included), the Long-term Post-Construction Operation and Maintenance Plan, the Illicit Discharge Compliance Statement (if included) and the plans showing the stormwater management system, and have determined that they have been prepared in accordance with the requirements of the Stormwater Management Standards as further elaborated by the Massachusetts Stormwater Handbook. I have also determined that the information presented in the Stormwater Checklist is accurate and that the information presented in the Stormwater Report accurately reflects conditions at the site as of the date of this permit application.

Registered Professional Engineer Block and Signature

RICHARD RHEAUME No. 28373 SYIL SONAL ENTER	Signature and Date Nov. 11, 2010
	Checklist

redevelopment?

Redevelopment

New development

Mix of New Development and Redevelopment



Checklist for Stormwater Report

Checklist (continued)

LID Measures: Stormwater Standards require LID measures to be considered. Document what environmentally sensitive design and LID Techniques were considered during the planning and design of the project:

tne	project:
V	No disturbance to any Wetland Resource Areas
	Site Design Practices (e.g. clustered development, reduced frontage setbacks)
	Reduced Impervious Area (Redevelopment Only)
	Minimizing disturbance to existing trees and shrubs
	LID Site Design Credit Requested:
	☐ Credit 1
	Credit 2
	Credit 3
	Use of "country drainage" versus curb and gutter conveyance and pipe
	Bioretention Cells (includes Rain Gardens)
	Constructed Stormwater Wetlands (includes Gravel Wetlands designs)
	Treebox Filter
	Water Quality Swale
	Grass Channel
	Green Roof
	Other (describe):
Sta	andard 1: No New Untreated Discharges
V	No new untreated discharges
✓	Outlets have been designed so there is no erosion or scour to wetlands and waters of the Commonwealth
	Supporting calculations specified in Volume 3 of the Massachusetts Stormwater Handbook included.



Checklist for Stormwater Report

CI	hecklist (continued)
Sta	andard 2: Peak Rate Attenuation
	Standard 2 waiver requested because the project is located in land subject to coastal storm flowage and stormwater discharge is to a wetland subject to coastal flooding. Evaluation provided to determine whether off-site flooding increases during the 100-year 24-hour storm.
√	Calculations provided to show that post-development peak discharge rates do not exceed pre- development rates for the 2-year and 10-year 24-hour storms. If evaluation shows that off-site flooding increases during the 100-year 24-hour storm, calculations are also provided to show that post-development peak discharge rates do not exceed pre-development rates for the 100-year 24- hour storm.
Sta	andard 3: Recharge
	Soil Analysis provided.
	Required Recharge Volume calculation provided.
	Required Recharge volume reduced through use of the LID site Design Credits.
	Sizing the infiltration, BMPs is based on the following method: Check the method used.
	☐ Static ☐ Simple Dynamic ☐ Dynamic Field¹
	Runoff from all impervious areas at the site discharging to the infiltration BMP.
	Runoff from all impervious areas at the site is <i>not</i> discharging to the infiltration BMP and calculations are provided showing that the drainage area contributing runoff to the infiltration BMPs is sufficient to generate the required recharge volume.
	Recharge BMPs have been sized to infiltrate the Required Recharge Volume.
Y	Recharge BMPs have been sized to infiltrate the Required Recharge Volume <i>only</i> to the maximum extent practicable for the following reason:
	Site is comprised solely of C and D soils and/or bedrock at the land surface
	M.G.L. c. 21E sites pursuant to 310 CMR 40.0000
	☐ Solid Waste Landfill pursuant to 310 CMR 19.000
	Project is otherwise subject to Stormwater Management Standards only to the maximum extent practicable.
	Calculations showing that the infiltration BMPs will drain in 72 hours are provided.
	Property includes a M.G.L. c. 21E site or a solid waste landfill and a mounding analysis is included.

^{1 80%} TSS removal is required prior to discharge to infiltration BMP if Dynamic Field method is used.



Checklist for Stormwater Report

Cł	necklist (continued)
Sta	ndard 3: Recharge (continued)
	The infiltration BMP is used to attenuate peak flows during storms greater than or equal to the 10-year 24-hour storm and separation to seasonal high groundwater is less than 4 feet and a mounding analysis is provided.
	Documentation is provided showing that infiltration BMPs do not adversely impact nearby wetland resource areas.
Sta	ndard 4: Water Quality
	E Long-Term Pollution Prevention Plan typically includes the following: Good housekeeping practices; Provisions for storing materials and waste products inside or under cover; Vehicle washing controls; Requirements for routine inspections and maintenance of stormwater BMPs; Spill prevention and response plans; Provisions for maintenance of lawns, gardens, and other landscaped areas; Requirements for storage and use of fertilizers, herbicides, and pesticides; Pet waste management provisions; Provisions for operation and management of septic systems; Provisions for solid waste management; Snow disposal and plowing plans relative to Wetland Resource Areas; Winter Road Salt and/or Sand Use and Storage restrictions; Street sweeping schedules; Provisions for prevention of illicit discharges to the stormwater management system; Documentation that Stormwater BMPs are designed to provide for shutdown and containment in the event of a spill or discharges to or near critical areas or from LUHPPL; Training for staff or personnel involved with implementing Long-Term Pollution Prevention Plan; List of Emergency contacts for implementing Long-Term Pollution Prevention Plan.
_	A Long-Term Pollution Prevention Plan is attached to Stormwater Report and is included as an attachment to the Wetlands Notice of Intent. Treatment BMPs subject to the 44% TSS removal pretreatment requirement and the one inch rule for calculating the water quality volume are included, and discharge:
	is within the Zone II or Interim Wellhead Protection Area
	is near or to other critical areas
	is within soils with a rapid infiltration rate (greater than 2.4 inches per hour)
	involves runoff from land uses with higher potential pollutant loads.
	The Required Water Quality Volume is reduced through use of the LID site Design Credits.
V	Calculations documenting that the treatment train meets the 80% TSS removal requirement and, if



Checklist for Stormwater Report

Checklist (continued)				
Standard 4: Water Quality (continued)				
\checkmark	▼ The BMP is sized (and calculations provided) based on:			
	The ½" or 1" Water Quality Volume or			
_	The equivalent flow rate associated with the Water Quality Volume and documentation is provided showing that the BMP treats the required water quality volume.			
✓	The applicant proposes to use proprietary BMPs, and documentation supporting use of proprietary BMP and proposed TSS removal rate is provided. This documentation may be in the form of the propriety BMP checklist found in Volume 2, Chapter 4 of the Massachusetts Stormwater Handbook and submitting copies of the TARP Report, STEP Report, and/or other third party studies verifying performance of the proprietary BMPs.			
	A TMDL exists that indicates a need to reduce pollutants other than TSS and documentation showing that the BMPs selected are consistent with the TMDL is provided.			
Sta	ndard 5: Land Uses With Higher Potential Pollutant Loads (LUHPPLs)			
	The NPDES Multi-Sector General Permit covers the land use and the Stormwater Pollution Prevention Plan (SWPPP) has been included with the Stormwater Report. The NPDES Multi-Sector General Permit covers the land use and the SWPPP will be submitted <i>prior</i> to the discharge of stormwater to the post-construction stormwater BMPs.			
	The NPDES Multi-Sector General Permit does <i>not</i> cover the land use.			
	LUHPPLs are located at the site and industry specific source control and pollution prevention measures have been proposed to reduce or eliminate the exposure of LUHPPLs to rain, snow, snow melt and runoff, and been included in the long term Pollution Prevention Plan.			
	All exposure has been eliminated.			
	All exposure has <i>not</i> been eliminated and all BMPs selected are on MassDEP LUHPPL list.			
	The LUHPPL has the potential to generate runoff with moderate to higher concentrations of oil and grease (e.g. all parking lots with >1000 vehicle trips per day) and the treatment train includes an oil grit separator, a filtering bioretention area, a sand filter or equivalent.			
Sta	ndard 6: Critical Areas			
	The discharge is near or to a critical area and the treatment train includes only BMPs that MassDEP has approved for stormwater discharges to or near that particular class of critical area.			
	Critical areas and BMPs are identified in the Stormwater Report.			



Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Checklist (continued)

ent The	ord 7: Redevelopments and Other Projects Subject to the Standards only to the maximum practicable project is subject to the Stormwater Management Standards only to the maximum Extent acticable as a:
	Limited Project
	Small Residential Projects: 5-9 single family houses or 5-9 units in a multi-family development provided there is no discharge that may potentially affect a critical area. Small Residential Projects: 2-4 single family houses or 2-4 units in a multi-family development with a discharge to a critical area Marina and/or boatyard provided the hull painting, service and maintenance areas are protected from exposure to rain, snow, snow melt and runoff
	Bike Path and/or Foot Path
4	Redevelopment Project
	Redevelopment portion of mix of new and redevelopment.
The imp in \ the and	rtain standards are not fully met (Standard No. 1, 8, 9, and 10 must always be fully met) and an oblanation of why these standards are not met is contained in the Stormwater Report. The project involves redevelopment and a description of all measures that have been taken to prove existing conditions is provided in the Stormwater Report. The redevelopment checklist found folume 2 Chapter 3 of the Massachusetts Stormwater Handbook may be used to document that proposed stormwater management system (a) complies with Standards 2, 3 and the pretreatment at structural BMP requirements of Standards 4-6 to the maximum extent practicable and (b) proves existing conditions.

Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan must include the following information:

- Narrative;
- Construction Period Operation and Maintenance Plan;
- Names of Persons or Entity Responsible for Plan Compliance;
- Construction Period Pollution Prevention Measures;
- Erosion and Sedimentation Control Plan Drawings;
- Detail drawings and specifications for erosion control BMPs, including sizing calculations;
- Vegetation Planning;
- Site Development Plan;
- Construction Sequencing Plan;
- Sequencing of Erosion and Sedimentation Controls;
- Operation and Maintenance of Erosion and Sedimentation Controls;
- Inspection Schedule;
- Maintenance Schedule;
- Inspection and Maintenance Log Form.



A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan containing the information set forth above has been included in the Stormwater Report.



Checklist for Stormwater Report

Checklist (continued)

	andard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control ontinued)
	The project is highly complex and information is included in the Stormwater Report that explains why it is not possible to submit the Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan with the application. A Construction Period Pollution Prevention and Erosion and Sedimentation Control has <i>not</i> been included in the Stormwater Report but will be submitted <i>before</i> land disturbance begins.
	The project is not covered by a NPDES Construction General Permit.
	The project is covered by a NPDES Construction General Permit and a copy of the SWPPP is in the
V	Stormwater Report. The project is covered by a NPDES Construction General Permit but no SWPPP been submitted. The SWPPP will be submitted BEFORE land disturbance begins.
Sta	andard 9: Operation and Maintenance Plan
▼	The Post Construction Operation and Maintenance Plan is included in the Stormwater Report and includes the following information:
	Name of the stormwater management system owners;
	Party responsible for operation and maintenance;
	Schedule for implementation of routine and non-routine maintenance tasks;
	Plan showing the location of all stormwater BMPs maintenance access areas;
	Description and delineation of public safety features;
	Estimated operation and maintenance budget; and
	Operation and Maintenance Log Form.
_ 🗆	The responsible party is not the owner of the parcel where the BMP is located and the Stormwater Report includes the following submissions:
	A copy of the legal instrument (deed, homeowner's association, utility trust or other legal entity) that establishes the terms of and legal responsibility for the operation and maintenance of the project site stormwater BMPs;
	A plan and easement deed that allows site access for the legal entity to operate and maintain BMP functions.
Sta	andard 10: Prohibition of Illicit Discharges
\checkmark	 The Long-Term Pollution Prevention Plan includes measures to prevent illicit discharges;
V	An Illicit Discharge Compliance Statement is attached;
	NO Illicit Discharge Compliance Statement is attached but will be submitted <i>prior to</i> the discharge of any stormwater to post-construction BMPs.

APPENDIX E

HYDROLGIC COMPUTATIONS

Proposed Family Dollar, Orchard Street New Bedford, Massachusetts

Drainage Summary

2 YR STORM (3.4 in.)

Receptor

Pre Development

Post Development

Q Max (cfs)

Q Max (cfs)

Ocean

3.84

3.16

10 YR STORM (4.8 in.)

Receptor

Pre Development

Post Development

Q Max (cfs)

Q Max (cfs)

Ocean

5.45

4.85

100 YR STORM (7.0 in.)


Receptor

Ocean

Pre Development Q Max (cfs) Post Development Q Max (cfs)

7.98

7.48



project site









Routing Diagram for Pre-development
Prepared by {enter your company name here}, Printed 11/11/2016
HydroCAD® 10.00-13 s/n 01299 © 2014 HydroCAD Software Solutions LLC

Printed 11/11/2016 Page 2

Area Listing (all nodes)

(a	Area acres)	CN	Description (subcatchment-numbers)
	1.162	98	impervious (1S)

Printed 11/11/2016 Page 3

Soil Listing (all nodes)

Area	Soil	Subcatchment
 (acres)	Group	Numbers
0.000	HSG A	
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
1.162	Other	18

Printed 11/11/2016 Page 4

Ground Covers (all nodes)

 HSG-A	HSG-B	HSG-C	HSG-D	Other	Total	Ground	Subcatchment
(acres)	(acres)	(acres)	(acres)	(acres)	(acres)	Cover	Numbers
0.000	0.000	0.000	0.000	1.162	1.162	impervious	

Pre-development

Type III 24-hr 2 yr Rainfall=3.40"

Prepared by {enter your company name here}
HydroCAD® 10.00-13 s/n 01299 © 2014 HydroCAD Software Solutions LLC

Printed 11/11/2016

Page 5

Time span=0.00-48.00 hrs, dt=0.01 hrs, 4801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: project site

Runoff Area=50,622 sf 100.00% Impervious Runoff Depth=3.17" Flow Length=267' Tc=6.0 min CN=98 Runoff=3.84 cfs 0.307 af

Printed 11/11/2016

Page 6


Summary for Subcatchment 1S: project site

Runoff = 3.84 cfs @ 12.08 hrs, Volume=

0.307 af, Depth= 3.17"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs Type III 24-hr 2 yr Rainfall=3.40"

_	A	rea (sf)	CN I	Description			
*		50,622	98 i	mpervious			
	*	50,622		100.00% Im	pervious A	rea	
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
	0.7	50	0.0200	1.23		Sheet Flow,	
	1.2	217	0.0209	2.93		Smooth surfaces n= 0.011 P2= 3.40" Shallow Concentrated Flow, Paved Kv= 20.3 fps	
	4.1					Direct Entry,	
	6.0	267	Total				



Pre-development

Type III 24-hr 10 yr Rainfall=4.80" Printed 11/11/2016

Prepared by {enter your company name here}
HydroCAD® 10.00-13 s/n 01299 © 2014 HydroCAD Software Solutions LLC

Page 7

Time span=0.00-48.00 hrs, dt=0.01 hrs, 4801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: project site

Runoff Area=50,622 sf 100.00% Impervious Runoff Depth=4.56" Flow Length=267' Tc=6.0 min CN=98 Runoff=5.45 cfs 0.442 af

Printed 11/11/2016

Page 8


Summary for Subcatchment 1S: project site

Runoff = 5.45 cfs @ 12.08 hrs, Volume=

0.442 af, Depth= 4.56"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs Type iII 24-hr 10 yr Rainfall=4.80"

_	A	rea (sf)	CN I	Description		
*		50,622	98 i	mpervious		
		50,622		100.00% In	pervious A	rea
_	Tc (min)	Length (feet)	Slope (ft/ft)		Capacity (cfs)	Description
	0.7	50	0.0200	1.23	······································	Sheet Flow,
	1.2	217	0.0209	2.93		Smooth surfaces n= 0.011 P2= 3.40" Shallow Concentrated Flow,
	4.1					Paved Kv= 20.3 fps Direct Entry,
	6.0	267	Total	· •		



Pre-development

Type III 24-hr 100 yr Rainfall=7.00" Printed 11/11/2016

Prepared by {enter your company name here}
HydroCAD® 10.00-13 s/n 01299 © 2014 HydroCAD Software Solutions LLC

Pane 0

Time span=0.00-48.00 hrs, dt=0.01 hrs, 4801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: project site

Runoff Area=50,622 sf 100.00% Impervious Runoff Depth=6.76" Flow Length=267' Tc=6.0 min CN=98 Runoff=7.98 cfs 0.655 af

Printed 11/11/2016 Page 10


Summary for Subcatchment 1S: project site


Runoff = 7.98 cfs @ 12.08 hrs, Volume=

0.655 af, Depth= 6.76"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs Type III 24-hr 100 yr Rainfall=7.00"

_	Δ	rea (sf)	_CN	Description		
*		50,622	98 i	impervious		
	50,622 100.00% Impervious A				pervious A	Area
	Tc (min)	Length (feet)	Slope (ft/ft)		Capacity (cfs)	Description
	0.7	50	0.0200	1.23		Sheet Flow,
	1.2	217	0.0209	2.93		Smooth surfaces n= 0.011 P2= 3.40" Shallow Concentrated Flow, Paved Kv= 20.3 fps
	4.1					Direct Entry,
	6.0	267	Total	····	-	





project site









Routing Diagram for Post-development

Prepared by {enter your company name here}, Printed 11/11/2016

HydroCAD® 10.00-13 s/n 01299 © 2014 HydroCAD Software Solutions LLC

Printed 11/11/2016 Page 2

Area Listing (all nodes)

Area (acres)	CN	Description (subcatchment-numbers)
0.407	74	>75% Grass cover, Good, HSG C (1S)
0.756	98	impervious (1S)

Printed 11/11/2016 Page 3

Soil Listing (all nodes)

Area	Soil	Subcatchment
(acres)	Group	Numbers
0.000	HSG A	
0.000	HSG B	
0.407	HSG C	18
0.000	HSG D	
0.756	Other	1S

Printed 11/11/2016

Ground Covers (all nodes)

	HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
٠	0.000	0.000	0,407	0.000	0.000	0.407	>75% Grass cover, Good	18
	0.000	0.000	0.000	0.000	0.756	0.756	impervious	18

Type III 24-hr 2 yr Rainfall=3.40"

Prepared by {enter your company name here}
HydroCAD® 10.00-13 s/n 01299 © 2014 HydroCAD Software Solutions LLC

Printed 11/11/2016

Page 5

Time span=0.00-48.00 hrs, dt=0.01 hrs, 4801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: project site

Runoff Area=50,622 sf 65.01% Impervious Runoff Depth=2.35" Tc=6.0 min CN=90 Runoff=3.16 cfs 0.228 af

Printed 11/11/2016

Page 6

Summary for Subcatchment 1S: project site


Runoff

3.16 cfs @ 12.09 hrs, Volume=

0.228 af, Depth= 2.35"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs Type III 24-hr 2 yr Rainfall=3.40"

	A	rea (sf)	CN	Description	1				
*		32,911 17,711		impervious		ood, HSG C			
		50,622 17,711 32,911	90	Weighted A 34.99% Per 65.01% Imp	verage rvious Area				
	Tc (min)	Length (feet)	Slope (ft/ft)		Capacity (cfs)	Description			
	6.0		•			Direct Entry,		-	



Type III 24-hr 10 yr Rainfall=4.80" Printed 11/11/2016 LLC Page 7

Prepared by {enter your company name here}
HydroCAD® 10.00-13 s/n 01299 © 2014 HydroCAD Software Solutions LLC

Time span=0.00-48.00 hrs, dt=0.01 hrs, 4801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: project site

Runoff Area=50,622 sf 65.01% Impervious Runoff Depth=3.68" Tc=6.0 min CN=90 Runoff=4.85 cfs 0.357 af

Type III 24-hr 10 yr Rainfall=4.80"

Prepared by {enter your company name here} HydroCAD® 10.00-13 s/n 01299 © 2014 HydroCAD Software Solutions LLC

Printed 11/11/2016

Page 8

Summary for Subcatchment 1S: project site


Runoff

4.85 cfs @ 12.09 hrs, Volume=

0.357 af, Depth= 3.68"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs Type III 24-hr 10 yr Rainfall=4.80"

	Area (sf)	_CN	Description	1		
*	32,911 17,711		impervious		ood, HSG C	
	50,622 17,711 32,911	90	Weighted A 34.99% Per 65.01% Imp	verage vious Area	I	
	Tc Length	Slope (ft/ft)		Capacity (cfs)	Description	
(6.0				Direct Entry.	



Type III 24-hr 100 yr Rainfall=7.00" Printed 11/11/2016

Page 9

Prepared by {enter your company name here} HydroCAD® 10.00-13 s/n 01299 © 2014 HydroCAD Software Solutions LLC

Time span=0.00-48.00 hrs, dt=0.01 hrs, 4801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: project site

Runoff Area=50,622 sf 65.01% Impervious Runoff Depth=5.82" Tc=6.0 min CN=90 Runoff=7.48 cfs 0.564 af

Type III 24-hr 100 yr Rainfall=7.00"

Prepared by {enter your company name here} HydroCAD® 10.00-13 s/n 01299 © 2014 HydroCAD Software Solutions LLC

Printed 11/11/2016

Page 10

Summary for Subcatchment 1S: project site

Runoff

7.48 cfs @ 12.08 hrs, Volume=

0.564 af, Depth= 5.82"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs Type III 24-hr 100 yr Rainfall=7.00"

	Area (sf)	CN	Description				
*	32,911 17,711	98 74	impervious >75% Grass cove	er. G	ood, HSG C		
	50,622 17,711 32,911	90	Weighted Averag 34.99% Pervious 65.01% Imperviou	e Area			
(mi		Slope (ft/ft	Cape	city	Description		
6.	0				Direct Entry.	 	—

