

November 5, 2020

Department of City Planning 133 Williams Street Room 303 New Bedford, Ma 02740 Attention: Jennifer Carloni

Re: 947 and 965 Church Street

Dear Jennifer,

We respectfully submit the following as the application of Child & Family Services, Inc. for a Site Plan review for the proposed use of the above referenced property.

- 1. Check in the amount of Seven Hundred Eighty One 60/100 Dollars (\$781.60)
- Site Plan Review application with original signatures of owners and applicant attached-5 Copies.
- 3. Owner Authorization Letter.
- 4. Completed Site Plan Review Application Checklist-5 Copies
- 5. Plans; Site, Architectural, Signage and Lighting (4) 24x36 Copies and (1) 11x17 Copy.
- 6. Project Narrative-5 Copies
- 7. Certified Abutter's Lists-5 Copies
- 8. Copy of current owner's deed-5 Copies
- 9. Storm Water Management Plan 5 Copies
- 10. City of New Bedford Inspectional Services denial package-5 Copies

Thank you again for your kind attention to this matter. I look forward to working with you toward acquiring all of the necessary City of New Bedford approvals for this project.

Sincerely,

Gregory B. Siroonian

Gregory B. Siroonian - Architect



Site Plan Review Application Checklist

In order for the City of New Bedford Planning Board to accurately review your project in a timely manner, plan sets submitted with applications must be complete and thorough. A comprehensive understanding of this handout and submittal of all required documents and plans ensures an efficient review of your project.

Unless otherwise noted or determined by Planning Division Staff to not be required, the following information and drawings must be included in the submittal package for your application. For an application to be accepted, each and every item is required at the time of application submittal.

In certain instances, plans, or portions of plans, may be waived when not applicable for the review of a particular type of development, at the discretion of the City Planner. Requests for any such waiver(s) must be submitted, in writing, to Planning Division for consideration prior to application submittal.

All submitted materials must be legible, organized & bound (where appropriate) in a manner that allows for distribution of all proposal materials as 1 package. Please utilize double-sided printing for submitted reports, studies and statements when possible.

Initials	Indicate	For subparts of the required plans, please mark as follows:
Item Su	bmitted.	X = Shown on Plans W = Waiver Requested NA = Not Applicable
<u>Staff</u>	Applicant	
	1. <u>(</u>	Completed Application Form (with all required signatures; 16 Copies)
	2. <u>(</u>	Completed Site Plan Review Application Checklist (1 original & 15 copies)
	3. <u>P</u>	<u>Plans</u>
	X	Four (4) stapled and folded sets of full-sized plans (24" x 36") and Twelve (12) sets of reduced

- Four (4) stapled and folded sets of full-sized plans (24" x 36") and Twelve (12) sets of reduced plans (11" x 17") are required for all applications. Staff reserves the right to require additional copies.
- One (1) electronic copy (PDF & CAD) of all proposed activity plans (See Section 10 of Checklist for Requirements)
- All plans oriented so that north arrow points to top of sheet
- \boxtimes Plans shall be drawn at a minimum scale of 1"= 40' or less
- All plans shall be stamped by Commonwealth of Massachusetts-registered Professional Engineer, Professional Land Surveyor, and/or Professional Landscape Architect, as appropriate
- Plan sets shall be comprised of separate sheets as listed below unless otherwise approved by the City Planner
- All plans shall have a title block comprised of the following: Project Title, Sheet Title, Sheet Number; Registrant Stamp (i.e. PE, PLS, LA); Registrant's name and address; Street addresses of the project area parcels; Scale at which the plan is drawn; Plan Issue Date; and all plan revision dates (with corresponding revision descriptions).

Applicant 3a. <u>Cover Sheet</u>, to include the following information: X **X** Title Block Project name/title ☑ Name and address of Engineer / Architect / Landscape Architect Assessor's map and parcel number(s) Name and address of developer Registry Book and Page X Revision Date Block Street Number and/or Lot Number Name and address of property owner **Image Image Imag** X Lot Area Accessible Parking Spaces ☑ Van Accessible Parking Spaces ☐ Front, Side & Rear Setbacks of Screening Buffers **Buildings and Parking Areas** Percentage of Lot that is Upland ■ Building Height ▼ Total Square Footage of Upland □ Green Space ☑ Off-Street Parking Spaces Locus Map (At a scale of 1 inch = 100 feet, showing the entire project and its relation to existing areas, buildings and roads within a distance of 1,000 feet from the project boundaries or such other distances as may be approved or required by the Planning Board.) Plan Index with latest revision date of each individual plan 3b. Existing Conditions Plan Name of Surveyor or Surveyor Firm Date of survey Property lines with bearings and distances Monuments set/found at all lot corners Easements with bearings and distances suitable for registry filing Names of all abutters Benchmark locations (Based on USGS NGVD – show year) NHESP mapped areas (Areas of Estimated and Priority Habitats) Existing 21E Contaminated Site Information

Setbacks from property lines

Noor locations with sill elevations

X Floor elevations

Existing Buildings and Structures

★ Area of building

Principal use

Number of stories

Staff | Applicant

- **I** Existing Topography:
 - Contours at 2' intervals (1' contours or additional spot grades if site is flat)
 - Overhead and underground utilities including but not limited to water, sewer, drainage, electric, telephone, cable TV, gas, septic systems, detention structures, wells
 - Existing parking/paved areas including pavement type (parking, walkways, etc.)

 - 🗵 Listing of all existing utility owners and contact info located within the project limits
 - Adequate utility information outside the site to verify proposed utility connections
 - All utility pipe types, sizes, lengths, and slopes
 - All utility structure information including rim and invert elevations
 - All existing easements within 50 feet of property line-Identify any utility within the easement
 - All existing utility easements with bearings and distances
 - Existing pavement markings within site and on connecting roads
 - Existing features such as walls, curbing, landscaping, trees, walks, fences, trees over 12" caliper, lighting, poles, guys, signs, loading areas, fire hydrants, dumpster locations, known buried slabs, etc...
 - Wetlands, floodplain, water protection district delineation including offsets and buffer zones
 - M Streams, water courses, swales and all flood hazard areas
 - Rock Outcroppings
 - Test pit locations including groundwater depths when encountered
 - $oxed{\mathbb{E}}$ Historic buildings within 250 feet of the subject property

X 3c. <u>Demolition Plan</u>

- **Existing Conditions Plan plus:**
- ☐ Existing Buildings and Structures to be removed/demolished
- 🗵 Existing parking/paved areas to be removed/demolished
- ☑ Existing utilities to be removed/demolished
- Existing features to be removed/ demolished such as walls, curbing, landscaping trees, walks, fences, trees over 6" caliper, lighting, poles, guys, signs, etc.
- Dust Control Measures
- Proposed construction phase drainage infrastructure plan including (but not limited to) piping and natural watercourse profiles & cross-sections, retention/detention structures, drain manholes, catch basins, gutter inlets, headwalls, water quality BMPs, and erosion & sedimentation control features, etc.

X 3d. Construction/Layout Plan

Proposed Buildings and Structures

Staff Applicant

- Area of building or additions
- Number of stories
- Principal use
- X Floor elevations
- Door locations with sill elevations
- Proposed Topography, including but not limited to:
 - Proposed contours at 2'intervals
 - Parking lot setbacks to property line
 - Parking lot grades (not to exceed 5% or be less than 0.5%)
 - NA Walls
 - Parking spaces (delineated and dimensioned)
 - Accessible parking spaces & aisles
 - Wheelchair ramps
 - Sidewalks
 - Pavement type(s)

- Setback dimensions from property lines
- Out-buildings, detached garages, temp. construction trailers, etc.
- □ Lighting / Poles / Guys
- Pavement markings
- Loading areas / Loading Docks / Platforms
- X Fences
- Landscape areas
- ☑ Dumpster(s), Compactor(s) & Pads
- Spot Grades at 4 Building Corners
- Overall Plan Showing Areas of Cut & Fill
- Critical dimensions including aisle widths, parking stall dimensions, curb radius, driveway openings, etc.
- ☐ Grading at entrance-show spot grades if required
- Emergency Vehicle Access
- ☐ Truck Access (WB-50 unless otherwise approved by City Engineer)
- Snow Storage Areas, with limits of any fence protection (if applicable)
- ☑ Construction notes, including the following notes:
 - Any minor modifications (as determined by the City Engineer) to the information shown on the approved site plans shall be submitted to the City Engineer as a Minor Plan Revision for approval prior to the work being performed.
 - Any work and material within the City right-of-way shall conform to the City of New Bedford_requirements
 - All handicap parking, ramps, and access shall conform to AAB & MAAB requirements
 - All erosion control measures shall be in place prior to construction. Erosion Control shall conform to the City of New Bedford Conservation Commission requirements as stated in the Order of Conditions. (Refer to Erosion Control Plan if part of submission)
 - All pavement markings and signs shall conform to MUTCD requirements

X 2e. <u>Grading and Drainage Plan</u>

- Existing Conditions Plan and Construction/ Layout Plan plus:
- Existing and proposed site grading/ topography-Contours at 2' intervals (1'contours or additional spot grades if site is flat)

Staff | Applicant

- Proposed parking lots, sidewalks, islands, etc.
 - Parking lot grades shall not exceed 5% or be less than 0.5 %
- X Floor elevations & door locations
- Proposed drainage infrastructure plan including but not limited to piping and natural watercourse profiles & cross-sections, infiltration/retention/detention structures, drain manholes, headwalls, roof recharge systems, flow direction, water quality BMPs, etc.
- Adequate information off site to verify proposed drain connections
- Drainage system profiles including rim and invert elevations, material, types, sizes, lengths, utility crossings and slopes
- ☐ Utility easements with bearings and distances suitable for registry filing
- □ Delineation of all stockpile areas
- Provide safety fencing around stockpiles over 10' in height or otherwise restrict site access
- ⊠ For applications associated with residential or commercial/industrial subdivisions, include an overall development plan showing all construction activity and proposed grading for all project phases, and show the proposed building envelope within each house lot and the proposed grading, drainage, and storm water disposal for each lot.
- A design for the stormwater drainage systems prepared by a Registered Professional Engineer demonstrating that proposed development rates of runoff do not exceed predevelopment rates, as required under Massachusetts Stormwater Management Standards.

3f. <u>Utility and Grading Plan</u> (Show appropriate info from Existing Conditions & Construction/Layout Plan)

- ☑ Include all proposed utilities, including, but not limited to, Water, Sewer, Drainage, Electric, Telephone, Cable TV, Gas, Lighting, Title V Septic Systems & Detention and Retention Structures
 - Adequate utility information outside the site to verify proposed utility connections
 - All utility pipe types, sizes, lengths, and slopes
 - All utility structure information including rim and invert elevations
 - Any utility access vaults
 - All utility access handholes
 - All water services, hydrants, gates, shutoffs, tees
 - Utilities shall be underground if possible
 - All transformer locations
 - Required utility easements with dimensional bearings and distances
- Force main, if required, conforming to City of New Bedford requirements
- Mater main loop
- Sewer profile showing all utility crossings
- Sections through detention basin(s)
- Include the following notes:
 - The contractor shall obtain a Street Disturbance & Obstruction Permit prior to any construction within the right-of-way
 - All water and sewer material and construction shall conform to the City of New Bedford requirements

Staff | Applicant

- All water and sewer construction shall be inspected by the City Of New Bedford before being backfilled
- The City shall be notified at least 24 hours prior to the required inspections
- Detention basin, retention basin or other stormwater mechanisms (such as infiltration devices), if proposed.

X 3g. Landscape Plan

- ☑ Location, species & size of all proposed plantings
- All existing landscaping to be removed or retained
- Plant and tree legend
- Delineate & label all existing and proposed groundcovers, lawn areas, driveways, walkways, patios and other surface treatments
- Snow storage areas
- Proposed irrigation methods (on-site wells to be used unless otherwise approved)
- ▼ Verify sight distances at entrances

X **3h.** Erosion Control Plan (show appropriate information from Existing Conditions and Construction/Layout Plans)

- Straw bales or straw bale/silt fence combination and compost filter tubes
- Anti-tracking BMP area at all construction entrances
- □ Dust Control (Methods of)
- Protection of existing and proposed drainage structures with straw bales and/or silt sacks
- ☑ Delineation of all temporary stockpile areas
- Safety fencing around stockpiles over 10' in height or otherwise restricted site access
- Straw bales or straw bale/silt fence combination around all stockpiles
- ☑ Include the following notes:
 - All BMP erosion control measures shall be in place prior to demolition or any site work.
 - Erosion Control BMPs shall conform to US EPA, NPDES, MA DEP and Massachusetts Erosion and Sedimentation Control Guidelines for Urban and Suburban Areas.
 - Maintenance specifications for all proposed erosion and sedimentation controls.

X 3i. Floor Plan

- ☑ Include complete floor plan of all floors (entire building), including existing & proposed work
- 🗵 Label all rooms (e.g., bedroom, kitchen, bathroom), and include dimensions of room sizes
- Show the location of all existing and proposed doors, windows, and walls

Staff Applicant

☑ Identify waste storage and disposal area(s), including detail(s) for dumpster(s) and dumpster pick-up and trash & garbage compaction areas (if any)

X 3j. <u>Building Elevations</u>

- Show all structural building elevations (front, sides and rear façades) that will be affected by the proposed project
- For additions/alterations: label existing and new construction, as well as items to be removed
- ☑ Identify all existing and proposed exterior materials, treatments and colors- including roofing, roof eaves, eave brackets, siding, doors, trim, sills, windows, fences, and railings. Show details of proposed new exterior elements
- Show any exterior mechanical, duct work, and/or utility boxes
- ☑ Include dimensions for building height, wall length and identify existing and proposed floor elevations

X 3k. Sign Plan

- I Fully-dimensioned color elevations for all proposed signs
- Total square footage of existing signs and total square footage of proposed signs
- Existing and proposed sign locations on site plan
- Existing and proposed materials and methods of lighting for all signs

X 3l. <u>Lighting Plan</u>

- ☑ Location and orientation of all existing and proposed exterior lighting, including building and ground lighting and emergency spot lighting (if any)
- $oxed{\mathbb{N}}$ Height and initial foot-candle readings on the ground and the types of fixtures to be used
- Plan Must Show Illumination Patterns On-Site and Areas Off-Site
- Mew Bedford Washingtonian Type Fixtures Should Be Used, Where Applicable
- Provide Cut Sheet for All Lighting Fixtures

X 3m. <u>Detail Sheets (Typical Details)</u>

- ☑ Pavement Section Detail
- X Sidewalk Detail
- Curb Detail
- Driveway Detail
- ☑ Wheel Chair Ramp Detail
- Catch Basin Detail
- ☑ Drainage Manhole Detail
- Water/Sewer Trench Details (12" envelope)

- Sewer Manhole Detail (26" cover)
- ☑ Detention / Retention Basin Sections (from plan)
- ☑ Detention Basin Outlet Structure Detail
- Miscellaneous Detention / Retention Basin Details
- X Infiltration Device Details
- Stormwater BMPs (Water Quality Structure Details, etc.)
- **X** Bollards

<u>Staff</u>	<u>Applicant</u>							
	■ Water and Sewer Trench Sections		⊠ Sign Detail					
	🗵 Anti-Seepage Collar Detail		X Fence Detail					
	☐ Flared End Detail		Flowable Fill Trench					
	☐ Rip Rap Detail	X	Pavement Marking Details					
	Straw bales/Silt Fence Detail	X	Handicap Parking/Compact Parking					
			Signs					
	☐ Compost Filter Tube Detail	☐ Hydrant Detail (American –Darling						
	 Light Pole Foundation Detail 		62-B (Open Right) or Mueller Super Centurion Hydrant (Open Right)					
	☐ Retaining Wall Details		Thrust Block Detail					
	Tree/Shrub Planting Detail							
	4. <u>Project Narrative</u> (16 Copies), to include adecoproposed project and indicating, where appropriate		summary & description of the					
	The number of dwelling units to be built and the		age in residential use					
	 Evidence of compliance with parking and off-str 	eet lo	ading requirements					
	 The forms of ownership contemplated for the prany ownership or maintenance thereof 	opert	ry and a summary of the provisions of					
	 Identification of all land that will become comm 	on or	public land					
	Any other evidence necessary to indicate compliance with the zoning ordinance							
	 A written statement indicating the estimated time required to complete the proposed project and any and all phases thereof 							
	 A written estimate showing, in detail, the projected costs of all site improvements (and off-sit improvement) planned 							
	 Drainage calculations by a registered profession conforming to City of New Bedford subdivision determined by a certified wetland scientist if ap 	regula	ations, as well as wetland delineations					
	X 5. <u>Certified Abutters List</u> (16 copies)							
		Invo	lved Parcels; 16 Copies)					
	NA 7. Development Impact Statement (DIS), cor	npleted per §5350 of Zoning Code, (16					
	Copies), if required by Board							
	NA 8. Traffic Impact & Access Study (TIAS)	(16 C o	pies), if required by Board					
	X 9. Stormwater Management Report (9 Co	nioc)	if required comprised of the following:					
	MADEP Stormwater Standards Compliance CheOverall Project Description	CKIISU	(signed & stamped)					
	Existing Conditions							
	Laisting Conditions							

Staff Applicant

- Proposed Improvements
- Proposed Conditions
- Hydrologic Analysis for Existing & Proposed Conditions for Milestone Storm Event Intensities
- Stormwater Management Regulations
- Summary
- Appendix Existing/Proposed Conditions Plans showing the following:
 - - Subcatchment Labeled, Design Point, Area, Curve number, Tc (min.)
 - Soil Classifications Table (Existing Soils)
 - Map Unit Symbol, Map Unit Name, Hydrologic Soil Code
 - Overall Proposed Subcatchment Area Table
 - Subcatchment Labeled, Design Point, Area, Curve number, Tc (min.)
 - Soil Classifications Table (Including Proposed Boron Soils, Etc., if applicable)
 - Map Unit Symbol, Map Unit Name, Hydrologic Soil Code
- Appendix Hydrologic Analyses
 - HydroCAD Software Analyses (or equivalent software) Analyses (Existing & Proposed Conditions)
- Appendix Illicit Discharge Certification (signed & dated)

X 10. Electronic PDF and AutoCAD Files

- ☑ Shall consist of a CD with a printed CD Label in a CD case
- 🗵 CAD files shall be 2010 format or the latest revision of AutoCAD Civil 3D
- All project submissions shall include the following file types. All project related Drawing Files shall be provided in all 2 supported formats, listed below.
 - AutoCAD Drawing format (.dwg)
 - Adobe Portable Document Format (.pdf)
- PDF files shall be created from within the AutoCAD environment and contain Layer information.
- It is a requirement that each project drawing/sheet created for a project shall be published/plotted to DWG and PDF, and placed in the appropriate folder in the CD submission. All external references (DWG, DWF, DGN, PDF, TIFF, MrSID, JPG, etc.) which are used in support of the creation of these project sheets shall be stored within the XREF folder only (Subfolder of DWG) on the CD. Also the AutoCAD support files (fonts, plot style, etc.) should be supplied on the CD.

File Naming:

The following file naming standard for all CAD related files created, used, or submitted to the Planning Department shall be followed. This applies to all CAD drawings, DWF's, PDF's used in support of, or used in conjunction with this CAD Standard.

Staff | Applicant

File names shall begin with their project Planning Board Case number assigned (available through the Planning Department), followed by an underscore and the appropriate discipline code. In the instance where there is more than one file, assign an appropriate sequential number to the end (ex. 1,2,3). Special characters are not permitted except for the following; hyphens [-], underscores [_], and/or parenthesis [()].

Example 1.

A set of engineering design plans and documents were prepared for project file number 12-34; acceptable filenames would be as follows:

12-34_Existing Conditions1.dwg

12-34_Existing Conditions2.dwg

12-34_General1.dwg

12-34_Generale.dwg

X 11. Application Fee (All fees are due at time of application submission)

Official Use Only:

For the Planning Board, this ap	plication has been	received by the	Planning Division	of the Department of
Planning, Housing & Communi	ty Development of	n the date specif	fied below:	

Review date:	All materials submitted:	Yes	No	
Signature:	Fee:			



PLANNING BOARD

CITY OF NEW BEDFORD JONATHAN F. MITCHELL, MAYOR SUBMIT TO: Planning Department 133 William Street Room 303 New Bedford, MA 0274

SITE PLAN REVIEW APPLICATION

The undersigned, being the entitled: Site Plan Review Packet	Applicant, seeks Site Pla	an Approv	val for g Engine	prope ers, LLC	rty depict	ed on a	a plan 11-2-2020
1. Application Informat	ion						
Street Address:	947, 965 Church Stree	et					
Assessor's Map(s):	130G	I	Lot(s)	50/65	5/72		
Registry of Deeds Book:	1108		Page:				
Zoning District:	IA		<i>8</i>				
Applicant's Name (printed):	Child and Family Serv	vices, Inc					
Mailing Address:	3057 Acushnet Ave		edford		MA		02745
Contact Information:	(Street) 508 742 1026	(City)		jmazı	(State) ur@cfservi	ces.org	(Zip)
Applicant's Relationship to	Telephone Number Property: ☐Owner	Contra	act Ver	Email ndee	Address Other	Under	Agreement
List all submitted materials	(include document titles	s & volum	e num	ibers v	where appl	licable) below:
C-COVER SHEET, X EXISTING CONDITIONS PLAN, L LAYOUT PLAN, G GRADING AND DRAINAGE PLAN, V LANDSCAPE PLAN, E1 EROSION CONTROL PLAN, E2 EROSION CONTROL DETAILS, D SITE DETAILS, EX1.1 EXISTING FIRST FLOOR, EX1.2 EXISTING MEZZANINE FLOOR, EX2.1 EXISTING ELEVATIONS, A1.1 FIRST FLOOR PLAN A1.2 MEZZANINE FLOOR PLAN, A2.1 EXTERIOR ELEVATIONS, LT1.1 SITE LIGHTING PLAN. SIGANGE IS SHOWN ON DRAWING A2.1. PROJECT NARRATIVE, CERTIFIED ABUTTERS LITS, COPY OF DEED, STORM MANAGEMENT REPORT.							
By signing below, I/we acknow knowledge. I/we further under grounds for the revocation of the Board Members the right to acknowledge.	rstand that any false infor the approval (s). I/we also ccess the premises (both i	mation in give Plan interior an	tention ning D	nally p epartr	rovided or nent staff a	omitte and Pla	d is nning

City Hall • 133 William Street • Room 303 • New Bedford, MA 02740 • <u>www.newbedford-ma.gov</u> PH: (508)979-1488 • FX: (508)979-1576

${\bf 2.} \ \textbf{Review Applicability} \ (\textbf{C}$	heck All That Apply to Your Proposal	
Category Residential Commercial Industrial Mixed (Check all categories that apply)	Construction New Construction Expansion of Existing Conversion Rehabilitation	Scale < 2,000 gross sq feet > 2,000 gross sq feet 3 or more new residential units 1 or more new units in existing res. multi-unit Drive Thru Proposed Ground Sign Proposed Residential Driveway With > 1 curbcut
3. Zoning ClassificationsPresent Use of Premises:Proposed Use of Premises:	Retail Furniture Store Medical Office	
Zoning Relief Previously Gra	anted (Variances, Special Permits, wit	th Dates Granted):
4. Briefly Describe the Pr	roposed Project: enovations for new offices and clinical spaces. Screene	ed in area for outdoor activities.

5. Please complete the following:

	Existing	Allowed/Required	<u>Proposed</u>
Lot Area (sq ft)	118,712	NA	118,712
Lot Width (ft)	300	NA	300
Number of Dwelling Units	NA	NA	NA
Total Gross Floor Area (sq ft)	37,995	NA	38,250
Residential Gross Floor Area (sq ft)	NA	NA	NA
Non-Residential Gross Floor Area (sq ft)	NA	NA	NA
Building Height (ft)	21'	100'	21'
Front Setback (ft)	106	25	98.9/4.8
Side Setback (ft)	24.6	25	24.6
Side Setback (ft)	149.1	25	149.1

Rear Setback (ft)	86	25	5.3
Lot Coverage by Buildings (% of Lot Area)	27	50	27
Permeable Open Space (% of Lot Area)	43	20	27
Green Space (% of Lot Area)	43	20	27
Off-Street Parking Spaces	27+	73	131
Long-Term Bicycle Parking Spaces	NA	NA	NA
Short-Term Bicycle Parking Spaces	NA	NA	NA
Loading Bays	NA	NA	NA

6. Please complete the fol	lowing:			Existin	ng Propose	d
a) Number of custor	ners per	day:		30	35-40*	* See Narrative
b) Number of emplo	yees:			6	40-45*	
c) Hours of operatio	n:			10:00-7:	7:30-7:00 *	
d) Days of operation	ı :			6	5/7 *	
e) Hours of deliverie	es:			8:00-4:0	8:3-4:30*	
f) Frequency of deliv	veries:	☑ Daily	□Weekly	□Monthly	Other:	
7. Planning Board Special	Permits	5:				
The applicant is als	o request	ting a Spec	ial Permit fro	m the Planning	g Board.	
Specify the reques		,				
Impact Statement	how the	request me	eets approval	criteria listed i	n §5320 of the zo	ning code.
8. ZBA Variances and Spe	cial Peri	nits:				
NOTICE: Checking below a applicant must also file th						
The applicant is also	request	ing a speci	al permit fron	n the ZBA:		
Specify zoning code	section	& <u>title</u>				
1 7 0	2230		CIAL #25 MEDIC	CAL		
	5300-5390	SPECIA	L PEMITS			
The applicant is also	request	ing a varia	nce from the	ZBA:		
Specify zoning cod	le <u>sectior</u>	<u>1</u> & <u>title</u>				
	2720	TABLE (OF DIM REQ-SID	E YARD		
	2750	YARDS II	N RESIDENTIAL D	ESITRICT		
	2755	SIDE Y		DINO		
	3100 3140	LOCAT	NG AND LOA ION & LAYO	UT OF PARKI	NG AND LOADI	NG FACILITIES

9. OWNERSHIP VERIFICATION

This section is to be completed & signed by the	
I hereby authorize the following Applic	ant: Child and Family Services, Inc.
at the following address:	Child and Family Services, Inc. 3057 Acushnet Ave New Bedford, Ma
to apply for:	Site Plan Review
on premises located at:	947, 965 Church Street
in current ownership since:	repruary 6, 2014
whose address is:	965 Church Street New Bedford, MA
for which the record title stands in the name of	Chaffee Church Properties, LLC CO Debra Holden
whose address is:	965 Church Street New Bedford, MA
hu a dood duly accorded in the	County: Bristol County-South Book: 1108 Page: 90
OR Registry District of the Land Court, Co	ertificate No.: Book: Page:
further understand that any false information intrevocation of the approval(s). I/we also give Plan the right to access the premises (both interior an notice for the purpose of taking photographs and	I herein is true to the best of my/our knowledge. I/we tentionally provided or omitted is grounds for the uning Department staff and Planning Board Members and exterior) at reasonable times and upon reasonable d conducting other visual inspections. I department staff and Planning Board Members and exterior and exterior are reasonable disconducting other visual inspections.

OWNER'S AUTHORIZATION LETTER I/we hereby certify that I/we am/are the owner(s) of the above described property. I/we am/are respectfully requesting processing and approval of the above referenced permit(s) review. I/we hereby authorize the Applicant listed on this application to act on my/our behalf during the processing and presentation of this request. They shall be the principal contact with the City in processing this application.

Child and Family Services, Inc.	
Applicant	
965 Church Street New Bedford, MA	
Property	
Debra Holden	9/4/20
Owner's Signature	Date / /

CHAFFEE CHURCH PROPERTIES LLC, C/O DEBRA HOLDEN

DEBRA Holden

Owner's Printed Name

Project Narrative

Address: 965 Church Street, Parcel 130G 50, 72 & 65.

Zoning District: Mixed Use: IA

General

Child and Family Services is proposing major site and building improvements to this property to house their facility. The size of the building will not change. The use will be changed from a furniture store to a medical office the proposed programs for the facility are listed below with more specific detail.

Approximately one-half of the building will operate as a Mental Health Counseling Center. These programs will operate from 7:30 a.m. to 7:00 p.m. five days per week. The peak building use time is mid-afternoon. When we return to pre-COVID levels of building occupancy, we expect a maximum of 40-45 employees and 35-40 clients to be in this part of the building during mid-afternoon. Approximately 25% of our clients utilize public transportation or taxis to arrive at appointments.

The other half of the building will house the 24 hour programs (CBAT, ES and CCS). As the name indicates, these programs operate 24 hours per day, 365 days per year. The peak building use time is mid-afternoon. These programs have not been materially-impacted by COVID. We expect a maximum of 35-40 employees and 7-14 ES clients and visitors to be in this part of the building during midafternoon. In addition, there will be 18->24 CBAT & CCS clients in residence at any one time. The clients (ES, CBAT & CCS) arrive via friends/family (a few drive themselves), public transportation, taxi or ambulance. Ambulances are used to transport clients from the hospital to the CBAT & CCS programs (hospital diversion programs providing lower levels of care). On average, one client arrives by ambulance each day (these are non-emergency transports that do not employ sirens or flashers). Deliveries will normally occur between 8:30 and 4:30 each day (office supplies, food and household items, etc. used in the various programs.

Proposed Programs to be in Building

Community Based Acute Treatment Program (CBAT)

CBAT is a 15 bed, single room unit that provides intensive short term care to children and adolescents, aged 4-17. CBAT is inclusive of all genders and provides a structured and secured treatment setting for children and adolescents experiencing behavioral and emotional crisis. CBAT is a 24 hour therapeutic living environment with moderate levels of supervision and intensity of service and is used as a diversionary placement to inpatient hospitalization or as a bridge from hospital inpatient stay to home.

Once admitted to the CBAT, the clinicians work with families and guardians to formulate an individualized treatment plan that identifies the goals and needs of the client to help stabilize their emotional and behavioral crisis for safe return to the community. During the course of treatment,

clients receive individual therapy, group therapy, family therapy, and psychiatric assessment. Clients also receive schooling 5 days a week to allow them to maintain their educational needs. The average length of stay at the CBAT is 10 days

Licensing:

The program is licensed by the Department of Early Education and Care (EEC).

Emergency Services Program (Crisis Center or ES)

The Crisis Center operates 24 hours a day and provides care for people of all ages in need of emergency mental health counseling. An emergency service clinician evaluates the clients in crisis and arranges appropriate treatment after consultation with a psychiatrist. An experienced master's level clinician is available seven days a week and there is always a psychiatrist on-site or on-call.

It is from this site that ES supports the New Bedford Police Department by:

- 1) Providing a co-response service to officers responding to mental health calls throughout the city (ES staff are dispatched separately and arrive on site to assist the police officer)
- 2) Siting one staff member at the Police Department's North End Station who rides-along with the officer to provide crisis intervention and hospital ED diversion.

What We Do:

- Offer assessments and interventions 24 hours a day, 365 days a year.
- Work with the consumer, their family and collaterals.
- Identify the least restrictive level of care.
- Provide services at one of our community based sites or in the home, schools, residential settings, hospitals, etc.
- Provide follow up to assure adequate support.
- Crisis counseling and consultation to the family.
- Telephone support to youth and family.
- Coordination with crisis stabilization providers.
- Collaboration with Intensive Care Coordinator (ICC) and In-Home Therapy (IHT) for youth receiving those services.

The program is licensed by the Massachusetts Behavioral Health Partnership (MBHP).

Our Staffing:

Our staffing pattern consists of up to eight clinicians during the major part of the week and a minimum of two clinicians on over-nights. Administrator on call duties provide a back-up clinician at any given time if volume demands it. Our clinicians have a variety of specialties including substance abuse, child interventions and working with the elderly.

Community Crisis Stabilization (CCS)

CCS is a twelve bed unit that receives adult patients from our Emergency Services (ES) and from other ES programs in the area. CCS is for patients who need support, monitoring, and/or medication stabilization, but do not need hospital inpatient admission.

Clients admitted to CCS are seen by a psychiatrist and a social worker on a daily basis. Groups are provided to include education, symptom management, coping strategies, stress relief, etc. Family or significant other meetings are often facilitated to assist clients with a smooth transition back to the community. The average length of stay in CCS is three days. Admission is voluntary.

Our staffing pattern consists of:

- 24-hour nursing availability
- A full-time and part-time social worker
- Cross over social workers from our Emergency Services (24/7, as needed)
- A mental health worker (24/7)
- Psychiatry is scheduled on the unit each day to address the needs of our clients. A multidisciplinary team meeting occurs every week day to discuss issues related to each case on the unit. All clients leave the unit with appointments for out-patient providers in the community.

Mental Health Counseling Center

This program offers individual counseling to children, adolescents, and adults as well as family and couples therapy. Counselors have earned advanced professional degrees in either psychology or social work and are licensed or working towards licensure in the state of Massachusetts. Additionally, counselors receive ongoing training and continuing education to help individuals work through a variety of challenges utilizing a full range of therapeutic interventions as well as collaboration with supports

In addition, psychiatrists and nurse practitioners specializing in adult, child, and geriatric psychiatry provide one-on one medication management sessions with clients and support other programs (such as CCS & CBAT). and.

Parking and Offloading Requirements

Per Chapter 9 Section 3100 of the City of New Bedford Zoning Bylaws, this project being a medical office/clinic, will require one parking space per 200 square feet (sf) of gross floor area (GFA) for the first 10,000 sf and one additional space per 1000 sf beyond 10,000 sf of GFA. Therefore, this project requires a minimum of 73 spaces. The applicant anticipates the need for additional parking above the required minimum, as such the site has been designed to provide 131 parking spaces, including 5 handicap accessible spaces as required by ADA. Additionally, one loading space is required to be provided in a manner such that loading/unloading shall not take place within a public way. This project proposes to provide one loading space located within the project site at the south west corner of the building.

The requested 131 parking spaces provide peak-time, pre-COVID capacity for staff and visitors. The non-peak parking needs are less than half this amount. Expected average hourly staff & visitor arrivals during the business day are 30."

Ownership

Child and Family Services, Inc. will own the building and be responsible for all site and building maintenance.

Project Schedule and Costs


Once CFS receives all required approvals from the city the final construction drawings will be completed and submitted for a building permit. It is aniticaped that construction will take approximately 9 months to complete. Project construction costs are estimated as follows:

Site Improvements	\$0
Exterior Envelope	\$0
Interior Build Out	\$0

Total:

Drainage Calculations

See attached drainage calculations.





Date Paid

Confirmation Number

City of New Bedford REQUEST for a CERTIFIED ABUTTERS LIST

This information is needed so that an official abutters list as required by MA General Law may be created and used in notifying abutters. You, as applicant, are responsible for picking up and paying for the certified abutters list from the assessor's office (city hall, room #109).

SUBJECT PRO	OPER	ΤΥ					
MAP# 13	30G		LOT(S)#	72			
ADDRESS: 94	17 Ch	urch Street					
OWNER INFO	ORM	ATION					
		hurch Properties LLC					
MAILING ADDRESS: 965 Church Street, New Bedford, MA 02745							
APPLICANT/	CONT	ACT PERSON INFORMA	TION				
NAME (IF DIF		Child and Family		nc. c/o Johnna Tierney			
MAILING AD	DRESS	S (IF DIFFERENT): 1061 PI	easant Stree	et			
			dford, MA (
TELEPHONE #		508-999-1332					
EMAIL ADDRESS:		jtierney@hlspc.com					
		REQUEST: Check appro	ALC: THE REAL PROPERTY.				
✓ ZONING BOARD OF APPEALS APPLICATION							
PLANNING BOARD APPLICATION							
CONSERVATION COMMISSION APPLICATION							
LICENSI	LICENSING BOARD APPLICATION						
OTHER (Please explain):							

Once obtained, the Certified List of Abutters must be attached to this Certification Letter.

Submit this form to the Planning Division Room 303 in City Hall, 133 William Street. You, as applicant, are responsible

for picking up and paying fo	r the certified abutter	s list from the assessor		109).
Official Use Only:				
	d on the attached "abu		SSOrs, I do hereby certify thorded and appear on the more of the m	
Printed Name		Signat	Date	
Amount Due	\$10.00			

9/17/2020

3958405

September 17, 2020 Dear Applicant,

Please find below the List of Abutters within 300 feet of the property known as <u>965 Church Street (Map: 130G, Lot: 50)</u>. The current ownership listed herein must be checked and verified by the City of New Bedford Assessor's Office. Following said verification, the list shall be considered a Certified List of Abutters.

Please note that multiple listed properties with identical owner name and mailing address shall be considered duplicates and shall require only 1 mailing. Additionally, City of New Bedford-Owned properties shall not require mailed notice

Parcel	Location Location	Additionally, City of New Bedford-Owned properties shall not require mailed notice. Owner and Mailing Address
130G-170		
1500 1,0	Jo Mildelli L	MCCOLLESTER FAMILY LIMITED PARTNERSHIP (THE), 5 BROWNELL AVE
130G-65	DUTTON ST	DARTMOUTH, MA 02747-3732
1300-03	DOTTONSI	CHAFFEE CHURCH PROPERTIES LLC, C/O DEBRA HOLDEN
		965 CHURCH STREET
130G-159	946 CHURCH ST	NEW BEDFORD, MA 02745
1300-139	940 CHURCH ST	GOYETTE THERESA "TRS", REUSCH PAULA R "TRS"
		765 WILDWOOD RD
130G-44	CHUDOLLOT	NEW BEDFORD, MA 02740
1300-44	CHURCH ST	XCEL REALTY LLC,
		78 MOORINGS RD
130G-126	CITA PEDED CO	MARION, MA 02738
130G-126	CHAFFEE ST	GOYETTE JOSEPH M,
		765 WILDWOOD RD
1200 00	OVI A PEDDE CO	NEW BEDFORD, MA 02745
130G-92	CHAFFEE ST	SULYMA JOHN P JR, SULYMA DEBORAH T
		1203 CHAFFEE ST
1200 41		NEW BEDFORD, MA 02745
130G-41		NO Data
130G-42		No Data
130G-43		No Data
130G-164	59 TARKILN PL	JAZ BRUSH U.S.A. INC
		59 TARKILN PLACE
		NEW BEDFORD, MA 02745
130G-124	CHAFFEE ST	GLASSMAN ARTHUR,
		926 CHURCH STREET
		NEW BEDFORD, MA 02745
130G-155	DUTTON ST	GLASSMAN ARTHUR,
		926 CHURCH STREET
		NEW BEDFORD, MA 02745
130G-28	1259 CHAFFEE	SILVA JOSE J, SILVA MARIA F
i	ST	1259 CHAFFEE STREET
		NEW BEDFORD, MA 02745

September 17, 2020 Dear Applicant,

Please find below the List of Abutters within 300 feet of the property known as <u>965 Church Street (Map: 130G, Lot: 50)</u>. The current ownership listed herein must be checked and verified by the City of New Bedford Assessor's Office. Following said verification, the list shall be considered a Certified List of Abutters.

Please note that multiple listed properties with identical owner name and mailing address shall be considered duplicates and shall require only 1 mailing. Additionally, City of New Bedford-Owned properties shall not require mailed notice.

Parcel	Location	Owner and Mailing Address
130G-50		
1300-30	965 CHURCH ST	CHAFFEE CHURCH PROPERTIES LLC, C/O DEBRA HOLDEN
		965 CHURCH STREET
		NEW BEDFORD, MA 02745
130G-72	947 CHURCH ST	CHAFFEE CHURCH PROPERTIES LLC,
		965 CHURCH STREET
		NEW BEDFORD, MA 02745

114494

QUITCLAIM DEED

REGISTERED & UNREGISTERED LAND

KNOW ALL MEN BY THESE PRESENTS that We, ALBINO SANTOS and MARIA I. SANTOS both of Durtmouth. Bristol County. Massachusetts. being all of the Trustees of the 965 CHURCH STREET REALTY TRUST under Declaration of Trust dated November 10, 2003, recorded in the Bristol County (S.D.) Registry of Deeds in Book 6648, Page 32, for consideration paid, and in full consideration of One and 00/100 (\$1.00) Dollar grant to CHAPPRE CHURCH PROPERTIES, LLC, a Massachusetts limited liability company having a mailing address of 965 Church Street, New Bedford, MA 02745, with QUITCLAIM COVENANTS

the land in New Redford, Bristol County, Massachusetts, with any buildings thereon bounded and described as follows: REGISTERED LAND Five (5) parcels of registered land and any buildings thereon in New Bedford,

Bristol County, Massachusetts, bounded and described as follows: PARCEL ONE: Northerly by the southerly line of Chaffor Street, two hundred nineteen (219) feet:

Easterly by land now or formerly of Gilbert Furtado, eighty-five (85) feet; Southerly by Lots 7, 8, 9, 10 & 11 on the plan of land hereinafter mentioned, one hundred ninety-nine and 64/100 (199.64) feet; and

Westerly . by land now or formerly of Acushnet Saw Mills Co., eightyseven and 18/100 (87 18) foot

Said land is shown as Lots 1, 2, 3, 4 & 5 on the plan mentioned below.

PARCEL TWO:

Southerly by the northerly line of Dutton Street, one hundred twenty (120) feet:

Lot 9 on the plan of land hereinafter mentioned, eighty-five Westerly by (85) feet:

Northerly by Lots 4 & 5 on said plan and by land now or formerly of Gilbert Furtado, one hundred twenty (120) feet; and

land now or formerly of Kenneth E. Browne, eighty-five (85) Eastorly

Said land is shown as Lots 6, 7 & 8 on the plan mentioned below.



114494

PARCEL THREE:

- 2 -Southerly by the northerly line of Dutton Street, one hundred and 27/100 (100.27) feet:

Westerly by land now or formerly of Acushnet Saw Mills Co., eighty-

seven and 18/100 (87.18) feet; Northerly by Lats 1, 2 & 3 on the plan of land hereinafter mentioned, one hundred nineteen and 64/100 (119.64) feet; and

Easterly by Lot 8 on said plan, eighty-five (85) feet.

Said land is shown as Lots 9, 10 & 11 on the plan mentioned below.

All of said boundaries are determined by the Court to be located as shown on plan 27797A, drawn by Jack Turner, Surveyor, dated August 12, 1957, as modified and approved by the Court, filed in the Land Registration Office at Boston, a copy of a portion of which is filed in the Bristol County (S.D.) Registry of Deeds in Land Registration Book 36, Page 13, with Certificate of Title No. 7012.

PARCEL FOUR:

Northerly by the southerly line of Chaffee Street, two hundred six and 38/100 (206 38) feet:

Rasterly by the westerly line of Church Street, eighty-five and 01/100 (85:01) feet:

Southerly by lands now or formerly, of Antonio Carlesi, et al, and of Antonio Caldeira, two hundred seven and 91/100 (207.91) feet: and

Westerly by said land now or formerly of Antonio Caldeira, eighty-five (85) feet.

All of said boundaries are determined by the Court to be located as shown on plan 40470A, drawn by Gorald M. Fitzgerald, Surveyor, dated February 10, 1980, as modified and approved by the Court, filed in the Land Registration Office at Boston, a copy of a portion of which is filed in the Bristol County (S.D.) Registry of Deeds in Land Registration Book 74, Page 133, with Certificate of Title No. 13718.

For Title to PARCKLS ONE through FOUR, see Transfer Certificate of Title No. 20390.

PARCEL FIVE: Easterly

Northerly by the southerly line of Dutton Stroot, two hundred eighty-eight and 88/100 (288.88) feet: by Lots 20 and 19 on the plan hereinafter mentioned, eighty-

four and 80/100 (84.80) feet: Southerly by land now or formerly of Ulric Lacourse, et al., two hundred seventy.two and 02/100 (272.02) fect; and

-3-

.

All of said boundaries are determined by the Court to be located as shown on plan 27797.4 Aware My Jack Turner, Surveyor, dated August 12, 1967, as modified and approved by the Court, filed in the Land Registration Office at Seston, a copy of a portion of which is filled in the Bristol County (E.D.) Registry of Deeds in Land Registration Book 30, Page 10, 1967, and 1979, an

For Title to PARCEL FIVE, see Transfer Certificate of Title No. 23119.

UNREGISTERED LAND

Two (2) parcels of land in New Bedford, Bristol County, Massachusetts, with any buildings thereon bounded and described as follows:

PARCEL ONE: The fee interest in and to Dutton Street as it abuts Lots 12 through 18 and

20 inclusive as shown on Land Court Plan 27797A, drawn by Jack Turner, Surveyor, dated August 12, 1987, as modified and approved by the Court, filed in the Iand Registration Office in Boston, a copy of a portion of which is filed in the Bristot County (S.D.) Registry of Deeds in Land Registration Book 36, Page 13, with Certificate of Title No. 7012.

For Title to PARCEL ONE, see deed from Albino Santon and Maria L. Santon, Trustees of the Kinky-Santon Family Living Trust under Declaration of Trust dated February 28, 2012, as set forth in a Certificate of Trust registered as Decument No. 11018 in and Registry of Deeds, said deed being dated June 10, 2013 and recorded in said Registry of Deeds in Book 10903, Page 208.

PARCEL TWO:

Beginning at the southwesterly corner of the land to be conveyed at a point in the northerly line of Dutton Street, add point being one hundred sixty-nine and 45/100 (189-40) feet distant therein westerly from its intersection with the westerly line of Church Street; thence running

Northerly eighty-five and no/100 (85.00) feet to a point for a corner; thence running

Easterly one hundred sixty-seven and 91/100 (167.91) feet to the westerly

line of Church Street: thence running

Southerly in line of said Church Street, eighty-five and 12/100 (85.12) feet to the northerly line of Dutton Street; and thence running

Westerly in line of last-named Street, one hundred sixty-nine and 45/100 (169,45) feet to the point of beginning.

Containing 52.76 square rods, more or less, and being shown as Lots 104, 105, 106 and 107 on a Plan of Land entitled 'Oakland Farms', New Bedford, Mass., property of Joseph A. Lardner and Fred J. Bentley, dated June 19, 1914, drawn by Abram Gifford and filed in the Bristol County (S.D.) Registry of Deeds in Plan Book 14, Page 31.

For title to PARCEL TWO, see deed from ALBINO SANTOS and MARIA L. SANTOS, dated February 2, 2004 and recorded in said Registry of Deeds in Book 6770, Page 1.

114494

- 4 Said premises are conveyed subject to real estate taxes for the current fiscal
year, which the Grantos(s), by the acceptance of this deed, hereby assume(s)
and asrnee(s) to new.

TITLE NOT EXAMINED.

WITNESS our hands and seals this __6th __day of February, 2014.

alking Lantor ALBINO SANTOS, Trustee Marie L. Agistos

COMMONWEALTH OF MASSACHUSETTS

Bristol, as.

purpose.

On this 5th day of February, 2014, before me, the undersigned notary public, personally appeared ALBINO SANTOS and MARIA L. SANTOS, whose identities were proved to me through Pil personal lasquistder | 1 out not affirmation of the signature of

Richard E. Notary Public My Commission Expires: 4/2/2015

CERTIFICATE OF MOMINEE TRUSTEE

114494

Me, Albino Santos and Maria L. Santos, Trustees of 965 Church Street Realty Trust under Declaration of Trust dated November 10, 2001, recorded in the Brishol County (S.D.) Registry of Deeds in Book 6648, Page 32, bereby certify that:

Said Trust is in full force and effect;

All the beneficiaries are of full age;

3) All beneficiaries are competent;

4) Pursuant to the Trust, when specifically authorized and directed by the beneficiaries of the Trust, the Trusteen have full right, power and authority to deal with any property owned or held by the Trust with the same force and effect as though such property were individually owned; and

 All the beneficiaries of said Trust have consented to the transfer of the property to the Chaffee Church Properties, LLC.

Signed	under	the	penalties	cf	perjury	this	_6th	day	o:
ebruary			2014.						

albino Santos, Trustee

Maria L. Santos, Trustee

BK 11008 PG 95 114494

The Commonwealth of Massachusetts

Bristol, ss. New Bedford

> Notary Public-Richard E. Street 177 My Commission Expires 47272015



Stormwater Management Report

Medical Clinic Redevelopment 947-965 Church Street

New Bedford, Massachusetts

Dated:

November 2, 2020

Prepared for:

Child & Family Services, Inc. 3057 Acushnet Avenue New Bedford, MA 02745

Prepared by:

Zenith Consulting Engineers, LLC 3 Main Street Lakeville, MA 02347





TABLE OF CONTENTS

DRAINAGE SUMMARY

SOIL REPORT

ILLICIT DISCHARGE STATEMENT

DEP STORMWATER CHECKLIST

HYDROCAD OUTPUT

Pre-Development Calculations

2 Year Storm10 Year Storm100 Year Storm

Post-Development Calculations

2 Year Storm10 Year Storm100 Year Storm

OPERATIONS AND MAINTENANCE PLAN

STORMWATER NARRATIVE Commercial Redevelopment, 947-965 Church Street, New Bedford, Massachusetts

The storm drainage system at the proposed medical clinic/office development located at 947 & 956 Church Street in New Bedford, Massachusetts, has been designed to create a reduction in the rate and volume of storm water runoff when compared to the existing site. In addition, the project's design will improve the quality of the runoff discharging from the site. The collection and treatment systems will be in the form of deep sump catch basins and a Stormceptor water quality unit. Hydrologic computations were performed in order to model the rate of flow of stormwater from the site under both existing and proposed conditions for a broad range of design storms.

1.0 STORM WATER COLLECTION SYSTEM

Throughout the proposed project, storm water will be collected from the impervious areas by a series of deep sump catch basins.

The collected runoff will be conveyed to the water quality components through smooth interior walled HDPE piping with corrugated exterior walls. The corrugated exterior of the piping provides for exceptional strength and bearing capacity. The smooth interior walls of the piping provide a smoothness that exceeds that of concrete pipe, thus providing increased hydraulic capacity. The piping is designed to provide self-cleansing velocities in large storm events to remain essentially maintenance free throughout its life.

Runoff from all impervious surfaces will be directed through a water quality unit for removal of Total Suspended Solids (TSS) and then into the existing municipal drainage system in Church Street.

2.0 STORM WATER MANAGEMENT FACILITIES

Current Department of Environmental Protection Policies require that the peak runoff rate after development is not more than peak runoff rate prior to development for the 2 and 10 year 24-hour storm events. Additionally, it is required that the storm water management system be evaluated for the 100-year storm projections.

Hydrologic modeling has been conducted for the design of the drainage system. HydroCAD Version 10.00 was utilized to perform this hydrologic and hydraulic modeling. The 2, 10, and 100-year design storms were evaluated. The hydrologic and hydraulic modeling established that the stormwater management systems will effectively attenuate the full range of design storms. That is, the peak rate of flow after development will be less than under existing conditions. The drainage summary provided with this document tabulates the projected decrease in runoff rate when the site is subjected to the design storm events. The complete hydrologic and hydraulic computational output is presented in this document.

2.1 LOW IMPACT DEVELOPMENT (LID) CONSIDERATIONS

The Massachusetts Stormwater Handbook encourages the use of Low Impact Development (LID) techniques by offering design credits for their implementation. No credits are sought or required for this project and, therefore, no LID techniques are required. Nevertheless, the project design incorporates LID techniques by proposing no impacts to wetlands Other LID measures were incorporated including providing the minimum amount of pavement required to provide safe vehicular access to and around the site for all vehicle types.

3.0 WATER QUALITY CONSIDERATIONS

On November 18, 1996, The Massachusetts Department of Environmental Protection (MADEP) issued the Storm Water Management Policy. The goal of this policy is to improve water quality and address flooding problems, which are sometimes caused by development projects, by the implementation of performance standards for storm water management. These standards were issued as guidelines with the possibility that in several years, after review by design engineers, they might be implemented as regulations. The project was designed to meet and exceed all relevant standards established in the policy. The following sections describe how each of these standards will be achieved on this project by incorporating Best Management Practices into the design. In January, 2008, the revised policy was issued.

3.1 UNTREATED STORM WATER - Standard 1

Standard 1 recommends that no new storm water conveyance, such as storm drain outfalls, discharge untreated storm water directly to wetlands or waterways of the Commonwealth. Flows from woods, fields, and other undeveloped areas are to be considered uncontaminated, however, runoff from paved road surfaces should receive treatment prior to discharge.

In designing this project, provisions have been made so that the runoff from all paved surfaces will receive proper treatment prior to discharge. All the proposed improvements will be located and graded such that runoff from the roadways will be directed to a series of BMP structures. This collected runoff will receive a treatment utilizing Best Management Practice (BMP) measures designed into the water quality unit and infiltration basin as further described under the discussions for Standards 2 through 9. Through the collection and treatment of all runoff from paved areas, DEP Standard 1 is satisfied.

3.2 POST DEVELOPMENT PEAK DISCHARGE RATES - Standard 2

Standard 2 prescribes that storm water management systems be implemented in order to ensure that post-development peak rates of discharge do not exceed existing rates of runoff for standard 2-year and 10-year design storms. In addition, the pre and post peak rates for the 100-year storm must be evaluated to assure that there will not be increased off-site flooding. Hydrologic calculations have been conducted in designing the storm water control measures to ensure that this standard is satisfied.

HydroCAD version 10.00, a computer aided design program, was selected for modeling the hydrology and hydraulics of storm water runoff for the site and its contributing drainage area. This program utilizes the latest techniques to predict the consequences of any given storm event and to verify that the drainage system is adequate to meet the performance standards for the area under consideration. The HydroCAD computer model uses TR-20 and TR-55 methodologies to generate runoff hydrographs and perform hydraulic routings through the modeled project.

Runoff hydrographs were generated for each subcatchment area. For post-development, all paved areas, driveways, sidewalks, roof areas and lawn areas were considered in determining composite runoff curve numbers for each subcatchment. For pre-development, the project area was evaluated in its existing condition. The soils within the development area of this project are described as hydrologic soils group C and Urban fill soils, according to the U.S.D.A., Soil Conservation Service mapping. Soil Observation holes were dug onsite and confirmed the soil conditions as urban fills and highly compacted soils with high estimated seasonal high groundwater tables.

In evaluating the same areas under pre and post development conditions, a direct comparison can be made as to the net increase or decrease in runoff rates attributable to altered land uses. The Drainage Summary table included in this report presents a summary of the hydrologic modeling conducted for this project. As presented in this table, the drainage system successfully moderates the flow for the full range of design storms and this standard is met.

3.3 RECHARGE TO GROUNDWATER - STANDARD 3

The loss of annual recharge to groundwater will be minimized through the increase of landscaped areas for the redevelopment. The annual recharge from the post development site will approximate the annual recharge from the pre-development conditions based on an assessment of soil types. Standard 3 of the DEP Stormwater Policy prescribes that the storm water runoff volume to be recharged to groundwater should be determined using existing soil. According to the U.S.D.A. Soil Conservation Service mapping, the surficial soils are Hydrologic Soil Group C as well as Urban Fill. The DEP Stormwater Policy requires that a certain volume of runoff be infiltrated to groundwater based on the type of soil present and the amount of impervious area being generated by the proposed development. For Type C soils, the recharge rate has been established to be 0.25 inches of runoff. As noted above, soil observation holes performed by ZCE revealed the presence of compact urban fills with shallow estimated seasonal high groundwater elevations which severely inhibits the implementation of infiltration BMPs in the design of the project. Due to these soil conditions (all HSG C & D soils) and the project being a redevelopment, Standard 3 is required to be met to the maximum extent practicable. The increase of lawn/landscaped areas on the site will promote infiltration to a greater degree over the existing condition. Therefore, Standard 3 is met to the maximum extent practicable.

3.4 REMOVAL OF 80% OF TOTAL SUSPENDED SOLIDS - Standard 4

The existing site contains no water quality treatment measures prior to discharge to the Church Street Drainage system. Since the project is a redevelopment, Standard 4 is required to be met to the maximum extent practicable. A series of stormwater BMP's have been designed in order to improve the water quality treatment over the existing condition. These proposed measures include:

- · Deep sump catch basins will collect runoff from all paved surfaces of the site.
- · A proprietary water quality unit (Stormceptor STC 4800) will be provided for the runoff from all paved areas before discharging to the Church Street drainage system.

The combination of the above features will result in the removal of 80% of the total suspended solids which represents a significant improvement over the existing condition. The following table depicts the proposed treatment train:

A BMP	B TSS Removal Rate*	C Starting TSS Load**	D Amount Removed (BxC)	E Remaining load (C-D)
Deep Sump Catch Basins	25%	1.00**	.25	.75
First Defense Water Quality Unit	73%	.75	.55	.20
TOTAL TSS REMOVAL .80 x 100 = 80% Removal		Removal		

^{**} Equals remaining load from previous BMP (E)

Due to the presence of unsuitable soils and the lack

3.5 USES WITH HIGHER POTENTIAL POLLUTANT LOADS - Standard 5

The DEP Storm Water Management Policy - Standard 5 requires that storm water discharges with higher potential pollutant loads be provided with specific BMP's. This development is not considered a use with a higher potential pollutant load. As such, this standard is satisfied.

3.6 STORM WATER DISCHARGES TO CRITICAL AREAS - Standard 6

Standard 6 of the DEP Storm water Policy seeks to protect critical areas. Critical areas are specifically designated Outstanding Resource Waters (ORW's) such as shell fish beds, swimming beaches, cold water fisheries and recharge areas for public water supplies. Such areas require the use of specific BMP's. This project does not discharge to a Critical Area. Therefore, this standard is satisfied by the application of those measures.

^{*} TSS Removal Rates As Published in the DEP Storm Water Policy Handbook (3/97)

3.7 REDEVELOPMENT OF PREVIOUSLY DEVELOPED SITES - Standard 7

Standard 7 applies to sites which have been previously developed and are being redeveloped. Diminished performance of BMP's is allowed in these areas. This project is a redevelopment and therefore, the design of the storm water management system meets certain design standards to the maximum extent practicable as noted above.

3.8 EROSION AND SEDIMENT CONTROL -Standard 8

Erosion and sediment control measures have been developed for this project and are included in the construction set of drawings. These plans show the proposed locations for erosion control devices. The following supplemental provisions are also a part of this plan.

Erosion and Sedimentation Control measures which are proposed to be implemented during construction include the installation of and silt fencing which has the bottom 6 inches buried in the ground. Any extra excavated soil which is not used to bury the base of the fence will be cast up-gradient of the silt fence.

- Erosion control devices such as silt fence, haybales and silt socks shall be inspected after every major rainfall runoff event (over 1½" depth of precipitation). All damaged or misaligned devices shall be immediately repaired. Silt shall be immediately removed from all areas of the silt fence when depth of accumulation exceeds 6 inches.
- Sumps and out falls shall be inspected after every major rainfall runoff event (over 1½" depth of precipitation). Silt shall be immediately removed from all sumps where the depth of accumulation exceeds 9 inches.)
- · All exposed construction areas will be stabilized upon completion in order to minimize the time that these areas are not stabilized.

With the full impact of the measures presented on the Erosion and Sedimentation Control Plans, along with the provisions stipulated above, Standard 8 will be satisfied.

3.9 OPERATIONS AND MAINTENANCE PLAN - Standard 9

Standard 9 of the DEP Storm Water Policy prescribes the adoption of a formal operation and maintenance plan to ensure that the storm water management systems function properly as designed. The proposed Operations and Maintenance Plan is attached in an appendix to this report. The plan includes Stormwater operations and Maintenance procedures, Construction Period Pollution Control measures and a Source Control and Pollution Prevention Plan.



Proposed Commercial Redevelopment, 947-965 Church Street, New Bedford Drainage Summary

2 YR STORM (3.2 in.)

Receptor	Pre Development		Post Development	
-	Q Max (cfs)	V (AF)	Q Max (cfs)	V (AF)
Church St Drainage	8.53	0.669	7.72	0.577

10 YR STORM (5.1 in.)

Receptor	Pre Development		Post Development	
-	Q Max (cfs)	V (AF)	Q Max (cfs)	V (AF)
Church St Drainage	13.07	1.051	12.39	0.950

100 YR STORM (7.0 in.)

Receptor	Pre Development		Post Development	
	Q Max (cfs)	V (AF)	Q Max (cfs)	V (AF)
Church St Drainage	18.11	1.480	17.54	1.374

SOIL REPORT



MAP LEGEND MAP INFORMATION The soil surveys that comprise your AOI were mapped at Area of Interest (AOI) С 1:20.000. Area of Interest (AOI) C/D Soils Warning: Soil Map may not be valid at this scale. D **Soil Rating Polygons** Enlargement of maps beyond the scale of mapping can cause Not rated or not available Α misunderstanding of the detail of mapping and accuracy of soil **Water Features** line placement. The maps do not show the small areas of A/D contrasting soils that could have been shown at a more detailed Streams and Canals Transportation B/D Rails ---Please rely on the bar scale on each map sheet for map measurements. Interstate Highways C/D Source of Map: Natural Resources Conservation Service **US Routes** Web Soil Survey URL: D Major Roads Coordinate System: Web Mercator (EPSG:3857) Not rated or not available -Local Roads Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts Soil Rating Lines Background distance and area. A projection that preserves area, such as the Aerial Photography Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required. This product is generated from the USDA-NRCS certified data as of the version date(s) listed below. Soil Survey Area: Bristol County, Massachusetts, Southern Part Survey Area Data: Version 14, Jun 9, 2020 Soil map units are labeled (as space allows) for map scales 1:50.000 or larger. Not rated or not available Date(s) aerial images were photographed: Dec 31, 2009—Jul 3. 2017 **Soil Rating Points** The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background A/D imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident. B/D

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
307B	Paxton fine sandy loam, 0 to 8 percent slopes, extremely stony	С	1.3	31.0%
602	Urban land		2.9	69.0%
Totals for Area of Interest		4.2	100.0%	

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.


If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher





3 Main Street Lakeville, MA 02347 (508) 947-4208 - www.zcellc.com

➢ Civil Engineering
 ➢ Septic Design (Title 5)
 ➢ Septic Inspections (Title 5)
 ➢ Commercial and Industrial Site Plans
 ➢ Chapter 91 Permitting

ILLICIT DISCHARGE STATEMENT (STANDARD #10)

RE: 947-965 Church Street New Bedford, MA

Standard 10 of the Massachusetts Stormwater Handbook prohibits illicit discharges to stormwater management systems. The following is an illicit discharge compliance statement based on existing conditions and design conditions for the proposed project.

EXISTING CONDITIONS

The existing site is a warehouse facility. Based on all the information available to the undersigned, and therefore, to the best of my knowledge, there are no current illicit discharges to the storm drainage system. If during construction, an illicit discharge is discovered, it shall be removed immediately.


PROPOSED DESIGN

The proposed project design does not include any illicit discharges. There are no points in the proposed storm drainage system where illicit discharges are likely to occur.

I hereby certify that the preceding is accurate.

Rene L. Gagnow P.E.

Zenith Consulting Engineers, LLC.





Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

A. Introduction

Important: When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.





A Stormwater Report must be submitted with the Notice of Intent permit application to document compliance with the Stormwater Management Standards. The following checklist is NOT a substitute for the Stormwater Report (which should provide more substantive and detailed information) but is offered here as a tool to help the applicant organize their Stormwater Management documentation for their Report and for the reviewer to assess this information in a consistent format. As noted in the Checklist, the Stormwater Report must contain the engineering computations and supporting information set forth in Volume 3 of the Massachusetts Stormwater Handbook. The Stormwater Report must be prepared and certified by a Registered Professional Engineer (RPE) licensed in the Commonwealth.

The Stormwater Report must include:

- The Stormwater Checklist completed and stamped by a Registered Professional Engineer (see page 2) that certifies that the Stormwater Report contains all required submittals. This Checklist is to be used as the cover for the completed Stormwater Report.
- Applicant/Project Name
- Project Address
- Name of Firm and Registered Professional Engineer that prepared the Report
- Long-Term Pollution Prevention Plan required by Standards 4-6
- Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan required by Standard 8²
- Operation and Maintenance Plan required by Standard 9

In addition to all plans and supporting information, the Stormwater Report must include a brief narrative describing stormwater management practices, including environmentally sensitive site design and LID techniques, along with a diagram depicting runoff through the proposed BMP treatment train. Plans are required to show existing and proposed conditions, identify all wetland resource areas, NRCS soil types, critical areas, Land Uses with Higher Potential Pollutant Loads (LUHPPL), and any areas on the site where infiltration rate is greater than 2.4 inches per hour. The Plans shall identify the drainage areas for both existing and proposed conditions at a scale that enables verification of supporting calculations.

As noted in the Checklist, the Stormwater Management Report shall document compliance with each of the Stormwater Management Standards as provided in the Massachusetts Stormwater Handbook. The soils evaluation and calculations shall be done using the methodologies set forth in Volume 3 of the Massachusetts Stormwater Handbook.

To ensure that the Stormwater Report is complete, applicants are required to fill in the Stormwater Report Checklist by checking the box to indicate that the specified information has been included in the Stormwater Report. If any of the information specified in the checklist has not been submitted, the applicant must provide an explanation. The completed Stormwater Report Checklist and Certification must be submitted with the Stormwater Report.

¹ The Stormwater Report may also include the Illicit Discharge Compliance Statement required by Standard 10. If not included in the Stormwater Report, the Illicit Discharge Compliance Statement must be submitted prior to the discharge of stormwater runoff to the post-construction best management practices.

² For some complex projects, it may not be possible to include the Construction Period Erosion and Sedimentation Control Plan in the Stormwater Report. In that event, the issuing authority has the discretion to issue an Order of Conditions that approves the project and includes a condition requiring the proponent to submit the Construction Period Erosion and Sedimentation Control Plan before commencing any land disturbance activity on the site.



Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

B. Stormwater Checklist and Certification

The following checklist is intended to serve as a guide for applicants as to the elements that ordinarily need to be addressed in a complete Stormwater Report. The checklist is also intended to provide conservation commissions and other reviewing authorities with a summary of the components necessary for a comprehensive Stormwater Report that addresses the ten Stormwater Standards.

Note: Because stormwater requirements vary from project to project, it is possible that a complete Stormwater Report may not include information on some of the subjects specified in the Checklist. If it is determined that a specific item does not apply to the project under review, please note that the item is not applicable (N.A.) and provide the reasons for that determination.

A complete checklist must include the Certification set forth below signed by the Registered Professional Engineer who prepared the Stormwater Report.

Registered Professional Engineer's Certification

I have reviewed the Stormwater Report, including the soil evaluation, computations, Long-term Pollution Prevention Plan, the Construction Period Erosion and Sedimentation Control Plan (if included), the Long-term Post-Construction Operation and Maintenance Plan, the Illicit Discharge Compliance Statement (if included) and the plans showing the stormwater management system, and have determined that they have been prepared in accordance with the requirements of the Stormwater Management Standards as further elaborated by the Massachusetts Stormwater Handbook. I have also determined that the information presented in the Stormwater Checklist is accurate and that the information presented in the Stormwater Report accurately reflects conditions at the site as of the date of this permit application.

Registered Professional Engineer Block and Signature



II/z/w

Checklist

	Project Type: Is the application for new development, redevelopment, or a mix of new and redevelopment?		
	New development		
\boxtimes	Redevelopment		
	Mix of New Development and Redevelopment		



Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Checklist (continued)

LID Measures: Stormwater Standards require LID measures to be considered. Document what environmentally sensitive design and LID Techniques were considered during the planning and design of the project:

\boxtimes	No disturbance to any Wetland Resource Areas
	Site Design Practices (e.g. clustered development, reduced frontage setbacks)
	Reduced Impervious Area (Redevelopment Only)
\boxtimes	Minimizing disturbance to existing trees and shrubs
	LID Site Design Credit Requested:
	☐ Credit 1
	☐ Credit 2
	☐ Credit 3
	Use of "country drainage" versus curb and gutter conveyance and pipe
	Bioretention Cells (includes Rain Gardens)
	Constructed Stormwater Wetlands (includes Gravel Wetlands designs)
	Treebox Filter
	Water Quality Swale
	Grass Channel
	Green Roof
	Other (describe):
Sta	ndard 1: No New Untreated Discharges
\boxtimes	No new untreated discharges
\boxtimes	Outlets have been designed so there is no erosion or scour to wetlands and waters of the Commonwealth
	Supporting calculations specified in Volume 3 of the Massachusetts Stormwater Handbook included.



Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Checklist (continued)
Standard 2: Peak Rate Attenuation
 Standard 2 waiver requested because the project is located in land subject to coastal storm flowage and stormwater discharge is to a wetland subject to coastal flooding. Evaluation provided to determine whether off-site flooding increases during the 100-year 24-hour storm.
Calculations provided to show that post-development peak discharge rates do not exceed pre- development rates for the 2-year and 10-year 24-hour storms. If evaluation shows that off-site flooding increases during the 100-year 24-hour storm, calculations are also provided to show that post-development peak discharge rates do not exceed pre-development rates for the 100-year 24- hour storm.
Standard 3: Recharge
Required Recharge Volume calculation provided.
Required Recharge volume reduced through use of the LID site Design Credits.
☐ Sizing the infiltration, BMPs is based on the following method: Check the method used.
☐ Static ☐ Simple Dynamic ☐ Dynamic Field¹
Runoff from all impervious areas at the site discharging to the infiltration BMP.
Runoff from all impervious areas at the site is <i>not</i> discharging to the infiltration BMP and calculations are provided showing that the drainage area contributing runoff to the infiltration BMPs is sufficient to generate the required recharge volume.
Recharge BMPs have been sized to infiltrate the Required Recharge Volume.

Site is comprised solely of C and D soils and/or bedrock at the land surface

☐ M.G.L. c. 21E sites pursuant to 310 CMR 40.0000

extent practicable for the following reason:

☐ Solid Waste Landfill pursuant to 310 CMR 19.000

Project is otherwise subject to Stormwater Management Standards only to the maximum extent practicable.

Recharge BMPs have been sized to infiltrate the Required Recharge Volume *only* to the maximum

☐ Calculations showing that the infiltration BMPs will drain in 72 hours are provided.

☐ Property includes a M.G.L. c. 21E site or a solid waste landfill and a mounding analysis is included.

¹ 80% TSS removal is required prior to discharge to infiltration BMP if Dynamic Field method is used.



Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Cł	necklist (continued)
Sta	ndard 3: Recharge (continued)
	The infiltration BMP is used to attenuate peak flows during storms greater than or equal to the 10-year 24-hour storm and separation to seasonal high groundwater is less than 4 feet and a mounding analysis is provided.
	Documentation is provided showing that infiltration BMPs do not adversely impact nearby wetland resource areas.
Sta	ndard 4: Water Quality
The • • • • • • • • • • • • • • • • • • •	E Long-Term Pollution Prevention Plan typically includes the following: Good housekeeping practices; Provisions for storing materials and waste products inside or under cover; Vehicle washing controls; Requirements for routine inspections and maintenance of stormwater BMPs; Spill prevention and response plans; Provisions for maintenance of lawns, gardens, and other landscaped areas; Requirements for storage and use of fertilizers, herbicides, and pesticides; Pet waste management provisions; Provisions for operation and management of septic systems; Provisions for solid waste management; Snow disposal and plowing plans relative to Wetland Resource Areas; Winter Road Salt and/or Sand Use and Storage restrictions; Street sweeping schedules; Provisions for prevention of illicit discharges to the stormwater management system; Documentation that Stormwater BMPs are designed to provide for shutdown and containment in the event of a spill or discharges to or near critical areas or from LUHPPL; Training for staff or personnel involved with implementing Long-Term Pollution Prevention Plan; List of Emergency contacts for implementing Long-Term Pollution Prevention Plan.
	A Long-Term Pollution Prevention Plan is attached to Stormwater Report and is included as an attachment to the Wetlands Notice of Intent. Treatment BMPs subject to the 44% TSS removal pretreatment requirement and the one inch rule for calculating the water quality volume are included, and discharge: is within the Zone II or Interim Wellhead Protection Area
	is near or to other critical areas
	is within soils with a rapid infiltration rate (greater than 2.4 inches per hour)
	involves runoff from land uses with higher potential pollutant loads

☐ The Required Water Quality Volume is reduced through use of the LID site Design Credits.

applicable, the 44% TSS removal pretreatment requirement, are provided.

☐ Calculations documenting that the treatment train meets the 80% TSS removal requirement and, if



Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Checklist (continued) Standard 4: Water Quality (continued) The BMP is sized (and calculations provided) based on: The ½" or 1" Water Quality Volume or The equivalent flow rate associated with the Water Quality Volume and documentation is provided showing that the BMP treats the required water quality volume. ☐ The applicant proposes to use proprietary BMPs, and documentation supporting use of proprietary BMP and proposed TSS removal rate is provided. This documentation may be in the form of the propriety BMP checklist found in Volume 2, Chapter 4 of the Massachusetts Stormwater Handbook and submitting copies of the TARP Report, STEP Report, and/or other third party studies verifying performance of the proprietary BMPs. A TMDL exists that indicates a need to reduce pollutants other than TSS and documentation showing that the BMPs selected are consistent with the TMDL is provided. Standard 5: Land Uses With Higher Potential Pollutant Loads (LUHPPLs) ☐ The NPDES Multi-Sector General Permit covers the land use and the Stormwater Pollution Prevention Plan (SWPPP) has been included with the Stormwater Report. The NPDES Multi-Sector General Permit covers the land use and the SWPPP will be submitted *prior* to the discharge of stormwater to the post-construction stormwater BMPs. The NPDES Multi-Sector General Permit does *not* cover the land use. LUHPPLs are located at the site and industry specific source control and pollution prevention measures have been proposed to reduce or eliminate the exposure of LUHPPLs to rain, snow, snow melt and runoff, and been included in the long term Pollution Prevention Plan. All exposure has been eliminated. All exposure has *not* been eliminated and all BMPs selected are on MassDEP LUHPPL list. The LUHPPL has the potential to generate runoff with moderate to higher concentrations of oil and grease (e.g. all parking lots with >1000 vehicle trips per day) and the treatment train includes an oil grit separator, a filtering bioretention area, a sand filter or equivalent. Standard 6: Critical Areas The discharge is near or to a critical area and the treatment train includes only BMPs that MassDEP has approved for stormwater discharges to or near that particular class of critical area. Critical areas and BMPs are identified in the Stormwater Report.



Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Checklist (continued)

Standard 7: Redevelopments and Other Projects Subject to the Standards only to the maximum extent practicable

\boxtimes	The project is subject to the Stormwater Management Standards only to the maximum Extent Practicable as a:
	☐ Limited Project
	 Small Residential Projects: 5-9 single family houses or 5-9 units in a multi-family development provided there is no discharge that may potentially affect a critical area. Small Residential Projects: 2-4 single family houses or 2-4 units in a multi-family development with a discharge to a critical area Marina and/or boatyard provided the hull painting, service and maintenance areas are protected from exposure to rain, snow, snow melt and runoff
	☐ Bike Path and/or Foot Path
	Redevelopment portion of mix of new and redevelopment.
	Certain standards are not fully met (Standard No. 1, 8, 9, and 10 must always be fully met) and an explanation of why these standards are not met is contained in the Stormwater Report. The project involves redevelopment and a description of all measures that have been taken to improve existing conditions is provided in the Stormwater Report. The redevelopment checklist found in Volume 2 Chapter 3 of the Massachusetts Stormwater Handbook may be used to document that the proposed stormwater management system (a) complies with Standards 2, 3 and the pretreatment and structural BMP requirements of Standards 4-6 to the maximum extent practicable and (b) improves existing conditions.

Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan must include the following information:

- Narrative;
- Construction Period Operation and Maintenance Plan;
- Names of Persons or Entity Responsible for Plan Compliance;
- Construction Period Pollution Prevention Measures;
- Erosion and Sedimentation Control Plan Drawings;
- Detail drawings and specifications for erosion control BMPs, including sizing calculations;
- Vegetation Planning;
- Site Development Plan;
- Construction Sequencing Plan;
- Sequencing of Erosion and Sedimentation Controls;
- Operation and Maintenance of Erosion and Sedimentation Controls;
- Inspection Schedule;
- Maintenance Schedule;
- Inspection and Maintenance Log Form.
- A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan containing the information set forth above has been included in the Stormwater Report.




Massachusetts Department of Environmental Protection Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Checklist (continued)

	ndard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control ntinued)
	The project is highly complex and information is included in the Stormwater Report that explains why it is not possible to submit the Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan with the application. A Construction Period Pollution Prevention and Erosion and Sedimentation Control has <i>not</i> been included in the Stormwater Report but will be submitted <i>before</i> land disturbance begins.
	The project is <i>not</i> covered by a NPDES Construction General Permit.
	The project is covered by a NPDES Construction General Permit and a copy of the SWPPP is in the
\boxtimes	Stormwater Report. The project is covered by a NPDES Construction General Permit but no SWPPP been submitted. The SWPPP will be submitted BEFORE land disturbance begins.
Sta	ndard 9: Operation and Maintenance Plan
	The Post Construction Operation and Maintenance Plan is included in the Stormwater Report and includes the following information:
	Name of the stormwater management system owners;
	□ Party responsible for operation and maintenance;
	Schedule for implementation of routine and non-routine maintenance tasks;
	☑ Plan showing the location of all stormwater BMPs maintenance access areas;
	□ Description and delineation of public safety features;
	○ Operation and Maintenance Log Form.
	The responsible party is not the owner of the parcel where the BMP is located and the Stormwater Report includes the following submissions:
	A copy of the legal instrument (deed, homeowner's association, utility trust or other legal entity) that establishes the terms of and legal responsibility for the operation and maintenance of the project site stormwater BMPs;
	A plan and easement deed that allows site access for the legal entity to operate and maintain BMP functions.
Sta	andard 10: Prohibition of Illicit Discharges
\boxtimes	The Long-Term Pollution Prevention Plan includes measures to prevent illicit discharges;
\boxtimes	An Illicit Discharge Compliance Statement is attached;
	NO Illicit Discharge Compliance Statement is attached but will be submitted <i>prior to</i> the discharge of any stormwater to post-construction BMPs.














Prepared by {enter your company name here}, Printed 11/2/2020 HydroCAD® 10.00-16 s/n 09356 © 2015 HydroCAD Software Solutions LLC



PRE-DEVELOPMENT CALCULATIONS 2-YEAR STORM - 3.40" RAINFALL

965 Church St-Pre-Post-103020

Prepared by {enter your company name here}

HydroCAD® 10.00-16 s/n 09356 © 2015 HydroCAD Software Solutions LLC

Page 2


Summary for Subcatchment 1S: Flow to Church Street

Runoff = 8.53 cfs @ 12.09 hrs, Volume= 0.669 af, Depth> 2.94"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type III 24-hr 2-Yr Storm Rainfall=3.40"

Area ((ac)	CN	Desc	Description					
0.	769	98	Pave	Paved parking, HSG C					
0.7	778	98	Root	Roofs, HSG C					
1.0	012	96	Grav	el surface	, HSG C				
0.	138	70	Brus	h, Fair, HS	G C				
0.0	028	74	>759	>75% Grass cover, Good, HSG C					
2.	725	96	Weig	Weighted Average					
1.	1.178 43.23% Pervious Area								
1.5	547		56.7	7% Imperv	ious Area				
Tc	Lengt		Slope	Velocity	Capacity	Description			
(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)				
6.0						Direct Entry,			

Subcatchment 1S: Flow to Church Street



Page 3

965 Church St-Pre-Post-103020

Prepared by {enter your company name here} HydroCAD® 10.00-16 s/n 09356 © 2015 HydroCAD Software Solutions LLC

Summary for Link 1L: Church Street-Pre


Inflow Area = 2.725 ac, 56.77% Impervious, Inflow Depth > 2.94" for 2-Yr Storm event

Inflow 0.669 af

8.53 cfs @ 12.09 hrs, Volume= 8.53 cfs @ 12.09 hrs, Volume= 0.669 af, Atten= 0%, Lag= 0.0 min Primary

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 1L: Church Street-Pre



PRE-DEVELOPMENT CALCULATIONS 10-YEAR STORM – 5.10" RAINFALL

965 Church St-Pre-Post-103020

Prepared by {enter your company name here}

HydroCAD® 10.00-16 s/n 09356 © 2015 HydroCAD Software Solutions LLC

Page 4


Summary for Subcatchment 1S: Flow to Church Street

Runoff = 13.07 cfs @ 12.09 hrs, Volume= 1.051 af, Depth> 4.63"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type III 24-hr 10-Yr Storm Rainfall=5.10"

Area	(ac)	CN	Desc	Description					
0.	769	98	Pave	Paved parking, HSG C					
0.	778	98	Root	Roofs, HSG C					
1.0	012	96	Grav	el surface	, HSG C				
0.	138	70	Brus	Brush, Fair, HSG C					
0.	028	74	>759	>75% Grass cover, Good, HSG C					
2.	725	96	Weig	Weighted Average					
1.	1.178 43.23% Pervious Area								
1.	547		56.7	7% Imperv	ious Area				
Τ.		41.	01	V. I	0	Description			
Tc	Leng		Slope	Velocity	Capacity	Description			
(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)				
6.0						Direct Entry,			

Subcatchment 1S: Flow to Church Street



Page 5

965 Church St-Pre-Post-103020

Prepared by {enter your company name here} HydroCAD® 10.00-16 s/n 09356 © 2015 HydroCAD Software Solutions LLC

Summary for Link 1L: Church Street-Pre


Inflow Area = 2.725 ac, 56.77% Impervious, Inflow Depth > 4.63" for 10-Yr Storm event

Inflow 1.051 af

13.07 cfs @ 12.09 hrs, Volume= 13.07 cfs @ 12.09 hrs, Volume= 1.051 af, Atten= 0%, Lag= 0.0 min Primary

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 1L: Church Street-Pre



PRE-DEVELOPMENT CALCULATIONS 100-YEAR STORM – 7.00" RAINFALL

965 Church St-Pre-Post-103020

Prepared by {enter your company name here}

HydroCAD® 10.00-16 s/n 09356 © 2015 HydroCAD Software Solutions LLC

Page 6


Summary for Subcatchment 1S: Flow to Church Street

Runoff = 18.11 cfs @ 12.09 hrs, Volume= 1.480 af, Depth> 6.52"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type III 24-hr 100-Yr Storm Rainfall=7.00"

Area	(ac)	CN	Desc	Description					
0.	769	98	Pave	Paved parking, HSG C					
0.	778	98	Root	Roofs, HSG C					
1.0	012	96	Grav	el surface	, HSG C				
0.	138	70	Brus	Brush, Fair, HSG C					
0.	028	74	>759	>75% Grass cover, Good, HSG C					
2.	725	96	Weig	Weighted Average					
1.	1.178 43.23% Pervious Area								
1.	547		56.7	7% Imperv	ious Area				
Τ.		41.	01	V. I	0	Description			
Tc	Leng		Slope	Velocity	Capacity	Description			
(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)				
6.0						Direct Entry,			

Subcatchment 1S: Flow to Church Street



965 Church St-Pre-Post-103020

Prepared by {enter your company name here} HydroCAD® 10.00-16 s/n 09356 © 2015 HydroCAD Software Solutions LLC

Page 7

Summary for Link 1L: Church Street-Pre


Inflow Area = 2.725 ac, 56.77% Impervious, Inflow Depth > 6.52" for 100-Yr Storm event


18.11 cfs @ 12.09 hrs, Volume= Inflow 1.480 af

18.11 cfs @ 12.09 hrs, Volume= 1.480 af, Atten= 0%, Lag= 0.0 min Primary

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 1L: Church Street-Pre












Street-Post





POST-DEVELOPMENT CALCULATIONS 2-YEAR STORM - 3.40" RAINFALL

Prepared by {enter your company name here} HydroCAD® 10.00-16 s/n 09356 © 2015 HydroCAD Software Solutions LLC

Page 2


Summary for Subcatchment 2S: Flow to Church Street-Post

Runoff 7.72 cfs @ 12.09 hrs, Volume= 0.577 af, Depth> 2.54"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type III 24-hr 2-Yr Storm Rainfall=3.40"

Area	(ac)	CN	Desc	cription				
1.	220	98	Pave	Paved parking, HSG C				
0.	770	98	Roof	Roofs, HSG C				
0.	115	96	Grav	el surface	, HSG C			
0.	620	74	>75%	√ Grass co	over, Good	I, HSG C		
2.	725	92	Weig	hted Aver	age			
0.	735		26.9	7% Pervio	us Area			
1.	990		73.0	3% Imperv	ious Area			
Тс	Leng	th	Slope	Velocity	Capacity	Description		
(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)			
6.0						Direct Entry,		

Subcatchment 2S: Flow to Church Street-Post



Page 3

965 Church St-Pre-Post-103020

Prepared by {enter your company name here}
HydroCAD® 10.00-16 s/n 09356 © 2015 HydroCAD Software Solutions LLC

Summary for Link 3L: Church Street-Post


Inflow Area = 2.725 ac, 73.03% Impervious, Inflow Depth > 2.54" for 2-Yr Storm event

7.72 cfs @ 12.09 hrs, Volume= Inflow 0.577 af

7.72 cfs @ 12.09 hrs, Volume= Primary 0.577 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 3L: Church Street-Post



POST-DEVELOPMENT CALCULATIONS 10-YEAR STORM – 5.10" RAINFALL

Prepared by {enter your company name here} HydroCAD® 10.00-16 s/n 09356 © 2015 HydroCAD Software Solutions LLC

Page 4


Summary for Subcatchment 2S: Flow to Church Street-Post

Runoff 12.39 cfs @ 12.09 hrs, Volume= 0.950 af, Depth> 4.18"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type III 24-hr 10-Yr Storm Rainfall=5.10"

Area	(ac)	CN	Desc	cription				
1.	220	98	Pave	ed parking,	HSG C			
0.	770	98	Roof	Roofs, HSG C				
0.	115	96	Grav	Gravel surface, HSG C				
0.	620	74	>75%	√ Grass co	ver, Good	HSG C		
2.	725	92	Weig	hted Aver	age			
0.	735			7% Pervio				
1.	990		73.0	3% Imperv	ious Area			
Тс	Leng	th	Slope	Velocity	Capacity	Description		
(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)			
6.0						Direct Entry,		

Subcatchment 2S: Flow to Church Street-Post



Prepared by {enter your company name here} HydroCAD® 10.00-16 s/n 09356 © 2015 HydroCAD Software Solutions LLC

Page 5

Summary for Link 3L: Church Street-Post


Inflow Area = 2.725 ac, 73.03% Impervious, Inflow Depth > 4.18" for 10-Yr Storm event

Inflow 0.950 af

12.39 cfs @ 12.09 hrs, Volume= 12.39 cfs @ 12.09 hrs, Volume= 0.950 af, Atten= 0%, Lag= 0.0 min Primary

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 3L: Church Street-Post



POST-DEVELOPMENT CALCULATIONS 100-YEAR STORM – 7.00" RAINFALL

Prepared by {enter your company name here} HydroCAD® 10.00-16 s/n 09356 © 2015 HydroCAD Software Solutions LLC

Page 6


Summary for Subcatchment 2S: Flow to Church Street-Post

Runoff 17.54 cfs @ 12.09 hrs, Volume= 1.374 af, Depth> 6.05"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type III 24-hr 100-Yr Storm Rainfall=7.00"

Area	(ac)	CN	Desc	cription				
1.	220	98	Pave	Paved parking, HSG C				
0.	770	98	Roof	Roofs, HSG C				
0.	115	96	Grav	el surface	, HSG C			
0.	620	74	>75%	% Grass co	ver, Good	HSG C		
2.	725	92	Weig	hted Aver	age			
0.	735			7% Pervio				
1.	990		73.0	3% Imperv	ious Area			
Tc	Leng	th	Slope	Velocity	Capacity	Description		
<u>(min)</u>	(fee	et)	(ft/ft)	(ft/sec)	(cfs)			
6.0						Direct Entry,		

Subcatchment 2S: Flow to Church Street-Post



Prepared by {enter your company name here}
HydroCAD® 10.00-16 s/n 09356 © 2015 HydroCAD Software Solutions LLC

Page 7

Summary for Link 3L: Church Street-Post


Inflow Area = 2.725 ac, 73.03% Impervious, Inflow Depth > 6.05" for 100-Yr Storm event

Inflow = 17.54 cfs @ 12.09 hrs, Volume= 1.374 af

Primary = 17.54 cfs @ 12.09 hrs, Volume= 1.374 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 3L: Church Street-Post





<u>OPERATIONS AND MAINTENANCE PLAN</u> Commercial Redevelopment, 947-965 Church Street, New Bedford

The following is the proposed operation and maintenance plan for the storm water management systems at the commercial redevelopment located at 947-965 Church Street in New Bedford, Massachusetts:

· Owner: Child & Family Services, Inc.

3057 Acushnet Avenue New Bedford, MA 02745

Parties responsible for Operation and Maintenance: Same as above

CONTENTS

- 1. Stormwater Management Systems Operations and Maintenance Plan
- 2. Construction Period Pollution Prevention Plan
- 3. Source Control and Long-term Pollution Prevention Plan

STORMWATER MANAGEMENT SYSTEMS OPERATIONS AND MAINTENANCE PLAN

Commercial Redevelopment, 947-965 Church Street, New Bedford, MA

The storm water management facilities were designed to require little or no intervention in the operation and to require little or no maintenance once the project is built and stable vegetative cover is established. However, the drainage improvements shall be subject to the following maintenance schedule:

A. Routine Maintenance

- 1. Debris: All debris and litter are to be removed from all catch basins, drains, and surrounding areas at least twice per year.
- 2. Re-seeding: Embankments that have excessive erosion or slumping are to be regraded and seeded (with canary grass or tall fescue grass) during the spring or fall growing seasons as needed.
- 3. Inspect: Catch basins and roof drains shall be inspected on a monthly basis. Any potential blockages in the down spouts will be removed if discovered. Gutters will be cleaned at least twice per year.

B. Periodic Maintenance

1. Accumulated sediment in the water quality unit will be inspected and removed in accordance with the manufacturer's recommendations or, at a minimum, once per year. If the accumulated sediment is equal to 15% of the capacity of the device, the sediment shall be cleaned out using a vacuum truck.

C. Non-routine Maintenance

1. Structural: All catch basins, water quality units, and pipes shall be inspected once every four (4) years for proper function, clogging, signs of deterioration and structural inadequacy. Any adverse situations are to be repaired as needed.

D. Non-periodic Inspection

1. The storm water management system shall be inspected after two years of full operation by a Registered Professional Civil Engineer to confirm its adequacy. The inspection shall include an examination of all components of the system including catch basin/water quality unit and infiltration systems.

- E. Annual Budget
- 1. The estimated annual budget for the O & M is \$2,500.

OPERATION AND MAINTENANCE PLAN LOG FORM

Refer to Site Plan for details on the drainage system. Use Log Form that follows as required upon completion of inspections and maintenance tasks, and file.


Medical Clinic Building 947-965 Church Street, New Bedford, MA Drainage System **Operation & Maintenance Log Form**

STORMWATER RMP'S

STORMWATER BMP'S							
STRUCTURE	DATE INSPECTED	SEDIMENT BUILDUP (YES/NO)	IF SEDIMENT BUILDUP, DATE CLEANED				
CB-1							
CB-2							
CB-3							
CB-4							
CB-5							
CB-6							
DMH-5 (STC 4800)							
OTHER:							
Note: Sediment to be removed from catch basins once the depth reaches 24"							

REQUIRED MAINTENANCE:	
TO BE PERFORMED BY:	ON
INSPECTION BY:	DATE

STORMWATER BMP PLAN



CONSTRUCTION PERIOD POLLUTION PREVENTION PLAN

947-965 Church Street, New Bedford, MA

1.0 INTRODUCTION

It is proposed to convert the existing commercial structure at the above-referenced facility into a medical clinic. The existing gravel areas will be converted into additional parking for the proposed facility. The following erosion and sediment control program material management practices and spill control program have been developed to that end.

2.0 PRECONSTRUCTION MEASURES

Prior to the initiation of any construction, erosion control measures shall be installed as shown on the plans. In addition, silt sacks shall be placed in all existing and proposed catch basin inlets. A preconstruction conference shall then be held with the New Bedford Planning Department's Agent/ Department of Public Infrastructure in order to confirm that sediment control conditions are adequate for construction to start.

3.0 CONSTRUCTION PERIOD MEASURES

The following are the minimal measures required for erosion and sediment control, material handling and for spill control.

3.1 EROSION AND SEDIMENTATION CONTROL

The following measures shall be maintained throughout the site construction phase of the project.

Catch Basin Protection

Proposed catch basins shall be protected with silt sacks prior to the completion of paving. If excessive siltation is discovered to be entering the catch basin inlets, then hay bales shall also be placed around grates and catch basins within the construction/demolition areas to ensure that runoff entering the catch basin has been filtered through the bales prior to discharge.

Stabilized Construction Entrance

A temporary stabilized construction entrance shall be installed at the locations shown on the erosion control plan. The purpose of the construction entrance is to remove sediment attached to vehicle tires and minimize its transport and deposition onto public road surfaces. The construction entrance shall be composed of a 6-inch thick (minimum) bed of 2-inch diameter crushed stone that extends a minimum of 50 feet. The construction entrance shall be a minimum of 25 feet wide, and shall flare to a minimum width of 45 feet wide at the junction with the roadway. The crushed stone bed shall be removed and replenished as necessary to maintain the proper function.

Erosion and Sediment Control - Maintenance

The project general contractor shall have primary responsibility for implementing temporary and permanent controls described in the plan and shall be responsible for assuring Contractor compliance with contract documents including all erosion and sediment control measures.

- Damaged or deteriorated items shall be repaired or replaced immediately after identification.
- The underside of haybales should be kept in close contact with the earth and reset as necessary.
- Silt Socks shall be inspected after every major rainfall runoff event (over ½" depth of precipitation) or every 14 days, whichever occurs first. All damaged or misaligned fences shall be immediately repaired. Silt shall be immediately removed from all areas of the silt fence when depth of accumulation exceeds 9 inches. Each report shall be documented on the form enclosed in Appendix E.
- Sumps shall be inspected after every major rainfall runoff event (over ½" depth of precipitation) or every 14 days, whichever occurs first. Silt shall be immediately removed from all sumps where the depth of accumulation exceeds 9 inches.
- All exposed construction areas shall be stabilized upon completion in order to minimize the time that these areas are unstabilized.

3.2 MATERIALS MANAGEMENT PRACTICES

The following are the material management practices that shall be used to reduce the risk of spills or other accidental exposure of materials and substances to stormwater runoff. The Contractor's Superintendent shall be responsible for ensuring that these procedures are followed:

1. Good Housekeeping

The following good housekeeping practices shall be followed on-site during construction:

- a. An effort shall be made to store only enough products required to do the job.
- b. All materials stored on-site shall be stored in a neat, orderly manner and, if possible, under a roof or in a containment area. At a minimum, all containers shall be stored with their lids on when not in use. Drip pans shall be provided under all dispensers.
- c. Products shall be kept in their original containers with the original manufacturer's label in legible condition.
- d. Substances shall not be mixed with one another unless recommended by the manufacturer.
- e. Whenever possible, all of a product shall be used up before disposing the

container.

- f. Manufacturer's recommendations for proper use and disposal shall be followed.
- g. The Contractor's Superintendent shall be responsible for daily inspections to ensure proper use and disposal of materials.

2. Hazardous Substances

These practices shall be used to reduce the risks associated with Hazardous Substances. Material Safety Data Sheets (MSDS's) for each product with hazardous properties that is used at the Project shall be obtained and used for the proper management of potential wastes that may result from these products. An MSDS shall be posted in the immediate area where such product is stored and/or used and another copy of each MSDS shall be maintained in the job trailer at the Project. Each employee who must handle a Hazardous Substance shall be instructed on the use of MSDS sheets and the specific information in the applicable MSDS for the product he/she is using, particularly regarding spill control techniques.

- a. Products shall be kept in original containers with the original labels in legible condition.
- b. Original labels and MSDS's shall be procured and used for each product.
- c. If surplus product must be disposed, manufacturer's and local/state/federal required methods for proper disposal must be followed.

3. Hazardous Waste

It is imperative that all Hazardous Waste be properly identified and handled in accordance with all applicable Hazardous Waste Standards, including the storage, transport and disposal of the Hazardous Wastes. There are significant penalties for the improper handling of Hazardous Wastes. It is important that the Site Superintendent seeks appropriate assistance in making the determination of whether a substance or material is a Hazardous Waste. For example, Hazardous Waste may include certain Hazardous Substances, as well as pesticides, paints, paint solvents, cleaning solvents, pesticides, contaminated soils, and other materials, substances or chemicals that have been discarded (or are to be discarded) as being out-of-date, contaminated, or otherwise unusable, and can include the containers for those substances; other materials and substances can also be or become Hazardous Wastes, however. The Contractor's Superintendent is also responsible for ensuring that all site personnel are instructed as to these Hazardous Waste requirements and also that the requirements are being followed.

4. Product Specific Practices

The following product specific practices shall be followed on the job site:

Petroleum Products

All on-site vehicles shall be monitored for leaks and receive regular preventative maintenance to reduce the chance of leakage. Petroleum products shall be stored in tightly sealed containers which are clearly labeled. Petroleum storage tanks shall be located at minimum 100 linear feet from drainage ways, inlets and surface waters. Any petroleum storage tanks stored on-site shall be located within a containment area that is designed with an impervious surface between the tank and the ground. The secondary containment must be designed to provide a containment volume that is equal to 110% of the volume of the largest tank. Any mobile petroleum tank shall be parked in a vehicular service area surrounded by a berm that provides a containment volume that is equal to 110% of the volume of the largest tank. Containment must provide sufficient volume to contain expected precipitation and 110% volume of the largest tank. Accumulated rainwater or spills from containment areas are to be promptly pumped into a containment device and disposed properly by a licensed Hazardous Waste transporter. Drip pans shall be provided for all dispensers. Any asphalt substances used on-site shall be applied according to the manufacturer's recommendations. The location of any fuel tanks and/or equipment storage areas must be identified on the Erosion Control Plan by the Contractor once the locations have been determined.

Fertilizers

Fertilizers shall be applied only in the minimum amounts recommended by the manufacturer. Once applied, fertilizer shall be worked in the soil to limit exposure to stormwater. The contents of any partially used bags of fertilizer shall be transferred to a sealable plastic bin to avoid spills.

Cleaning Solvents

All containers shall be tightly sealed and stored when not in use. Excess solvents shall not be discharged to the storm sewer system, but shall be properly disposed of according to manufacturer's instructions or state and federal regulations.

Concrete Wastes

Concrete trucks shall be allowed to wash out or discharge surplus concrete or drum wash water on the project site, but only in specifically designated diked and impervious washouts which have been prepared to prevent contact between the concrete wash and stormwater. Waste generated from concrete wash water shall not be allowed to flow into drainage ways, inlets, receiving waters or any location other than the designated concrete washout. Waste concrete may be poured into forms to make rip-rap or other useful concrete products. Concrete washouts shall be located at minimum 100 linear feet from

drainage ways, inlets, surface waters and wetland resource areas.

The hardened residue from the concrete washout diked areas shall be disposed in the same manner as other non-hazardous construction waste materials or may be broken up and used on site as deemed appropriate by the Contractor. Maintenance of the washout is to include removal of hardened concrete. Facility shall not be filled beyond 95% capacity and shall be cleaned out once 75% full unless a new facility is constructed. The Contractor's Superintendent shall be responsible for seeing that these procedures are followed.Saw-cut Portland Cement Concrete (PCC) slurry shall not be allowed to enter storm drains or watercourses. Saw-cut residue should not be left on the surface of pavement or be allowed to flow over and off pavement. Residue from saw-cutting and grinding shall be collected by vacuum and disposed of in the concrete washout facility.

5. Solid and Construction Wastes

All waste materials shall be collected and disposed of at an appropriate solid waste disposal area.

6. Sanitary Wastes

A minimum of one portable sanitary unit shall be provided for every ten (10) workers on the site. All sanitary waste shall be collected from the portable units a minimum of one time per week by a licensed portable facility provider in complete compliance with local and state regulations.

All sanitary waste units shall be located in an area where the likelihood of the unit contributing to stormwater discharges is negligible. Additional containment BMPs must be implemented, such as gravel bags or specially designed plastic skid containers around the base, to prevent wastes from contributing to stormwater discharges.

7. Contaminated Soils

Any contaminated soils (resulting from spills of hazardous substances or oil or discovered during the course of construction) which may result from construction activities shall be contained and cleaned up immediately in accordance with the procedures given in the Material Management Plan and in accordance with applicable state and federal regulations. Contaminated soils not resulting from construction activities, or which pre-existed construction activities, but which are discovered by virtue of construction activities, should be reported in the same manner as spills, but with sufficient information to indicate that the discovery of an existing condition is being reported. If there is a release that occurs by virtue of the discovery of existing contamination, this should be reported as a spill, if it otherwise meets the requirements for a reportable spill.

SOURCE CONTROL AND LONG-TERM POLLUTION PREVENTION PLAN 947-965 Church Street, New Bedford, MA

1.0 INTRODUCTION

The development of the above referenced facility has been designed to provide improved stormwater quality compared to existing conditions. In order for this to continue in the long term, it is necessary to implement the following Source Control and Pollution Prevention Plan.

2.0 RESPONSIBLE PARTY

Responsible Party: Child and Family Services, Inc.

3057 Acushnet Avenue, New Bedford, MA

Attention: TBD

3.0 SOURCE CONTROL MEASURES

The most effective means of providing clean runoff is to prevent pollutants from coming into contact with the stormwater in the first place. This involves the following:

- 1. Keeping de-icing agents, fertilizers, stockpiles, etc covered at all times. If practical, all such products shall be stored indoors or off-site.
- 2. All landscaping, fertilization and other grounds maintenance shall be done by professional groundkeepers who are trained at how to maintain the grounds.
- 3. Periodic parking lot sweeping program shall be implemented. This program shall include removal of windblown debris and litter from landscaped areas.
- 4. A supply of speedy dry type oil absorbent material shall be kept on-site to allow for the quick cleanup of minor spills.

4.0 SPILL PREVENTION AND RESPONSE PLAN

The Property Manager, shall train all personnel in the proper handling and cleanup of spilled Hazardous Substances or Oil. No spilled Hazardous Substances or Oil shall be allowed to come in contact with stormwater discharges. If such contact occurs, the stormwater discharge shall be contained on site until appropriate measures in compliance with state and federal regulations are taken to dispose such contaminated stormwater. It shall be the responsibility of the Property

Manager to be properly trained, and to train all personnel in spill prevention and cleanup procedures.

In order to prevent or minimize the potential for a spill of hazardous substances or oil to come into contact with stormwater, the following steps shall be implemented:

- a. All hazardous substances or oil (such as pesticides, petroleum products, fertilizers, detergents, chemicals, acids, paints, paint solvents, cleaning solvents, additives for soil stabilization, concrete curing compounds and additives, etc.) shall be stored in a secure location, with their lids on, preferably under cover, when not in use.
- b. The minimum practical quantity of all such materials shall be kept at the facility.
- c. A spill control and containment kit (containing, for example, absorbent materials, acid neutralizing powder, brooms, dust pans, mops, rags, gloves, plastic and metal trash containers, etc.) shall be provided at the site.
- d. Manufacturer's recommended methods for spill cleanup shall be clearly posted and site maintenance personnel shall be trained regarding these procedures and the location of the information and cleanup supplies.
- e. It is the Property Manager's responsibility to ensure that all hazardous waste discovered or generated at the Project site are disposed properly by a licensed hazardous material disposal company. The Property Manager is responsible for not exceeding hazardous waste storage requirements mandated by the EPA or state and local authority.

A spill contingency plan shall be implemented including the following provisions:

- Equipment necessary to quickly attend to inadvertent spills or shall be stored onsite in a secure but accessible location. Such equipment shall include:
 - 1. Safety goggles.
 - 2. Chemically resistant gloves and overshoe boots.
 - 3. Water and chemical fire extinguishers.
 - 4. Sand and shovels.
 - 5. Suitable absorbent materials.
 - 6. Storage containers.
 - 7. First aid equipment.

In the event of a spill of hazardous substances or oil, the following procedures must be followed:

a. All measures must be taken to contain and abate the spill and to prevent the

discharge of the hazardous substance or oil to stormwater or off-site. (The spill area must be kept well ventilated and personnel must wear appropriate protective clothing to prevent injury from contact with the hazardous substances.)

- b. For spills of less than five (5) gallons of material, proceed with source control and containment, clean-up with absorbent materials or other applicable means unless an imminent hazard or other circumstances dictate that the spill should be treated by a professional emergency response contractor.
- c. For spills greater than five (5) gallons of material immediately contact a Massachusetts Licensed Site Professional L.S.P. Provide information on the type of material spilled, the location of the spill, the quantity spilled, and the time of the spill and proceed with prevention, containment and/or clean-up if so desired.
- d. Spills of amounts that exceed reportable quantities of certain substances specifically mentioned in federal regulations 40 CFR 110, 40 CFR 117, and 40 CFR 302 must be immediately reported to the EPA National Response Center, Telephone (800) 242-8802.

The Property Manager shall be the spill prevention and response coordinator. He shall designate the individuals who shall receive spill prevention and response training. These individuals shall each become responsible for a particular phase of prevention and response. The names of these personnel should be posted in the material storage area and in the property office.

5.0 SNOW AND ICE REMOVAL

Snow removal shall be primarily done by mechanical removal rather than chemical application. The judicious use of sand and salt without chemical additives is allowed in order to protect the safety of the public. Snow shall be primarily stored onsite along the southern landscaped area on the property.



DEPARTMENT OF INSPECTIONAL SERVICES

133 WILLIAM STREET – ROOM 308 NEW BEDFORD, MA 02740

New Bedford Comprehensive Zoning Code Review Code of Ordinances — Chapter-9

965 Church Street – PLOT: 130G – LOT: 50 – ZONED DISTRICT: IA SS Dutton Street – PLOT: 130G – LOT: 65 – ZONED DISTRICT: IA

Site Plan Review Required is from the Planning Board

Special Permit & Variance is Required from the Zoning Board of Appeals

Zoning Code Review as follows:

Site Plan Review

Planning Board

- SECTIONS
 - 5400 Site Plan Review
 - 5410 Purpose
 - 5420 Applicability
 - 5421 Any new industrial or commercial construction or expansion over two thousand (2,000) gross square feet or any new industrial or commercial construction or expansion requiring more than five (5) additional parking spaces.
 - 5425 New industrial or commercial construction or additions less than two thousand (2,000) square feet if requiring a new curb cut or driveway or if substantially affecting existing internal circulation.
 - 5430-5490B

Variance

Zoning Board of Appeals

SECTIONS

- 1200 Definitions
 - Structure A combination of materials assembled at a fixed location to give support or shelter, such as a building, framework, retaining wall, tent, reviewing stand, platform, bin, fence, sign, flagpole, recreational tramway, mast for radio antenna or the like.
- 2700 Dimensional Regulation
- 2710 General
- 2720 Table of Dimensional Requirements Appendix-B
 - Side Yard-Ft
- 2750 Yards in Residence District
- 2755 Side Yard
- 3100 Parking and Loading
- 3110 Applicability
- 3140 Location and Layout of Parking and Loading Facilities
 - 3146 When five (5) or more parking spaces are required on a lot, the provisions of Section 3300 shall apply.
 All spaces shall be laid out so that vehicles can enter or leave any parking space directly from a drive or aisle other than a street.
 Additionally, all spaces shall be laid out so the vehicles entering a street may do so facing the street.

Special Permit

Zoning Board of Appeals

SECTIONS

- 2200 USE REGULATIONS
- 2210 General
- 2230 Table of Use Regulations Appendix-A
 - Commercial: #25 Medical offices, center, or clinic
- 5300-5390 Special Permit

****<u>Note:</u> Owner and/or leasee to contact DPI to discontinue the unpaved portion of Dutton Street between 965 Church Street and 947 Church Street that will be used for it parking. ****

